

FILE NUMBER:

SHEET OF]

GENERAL NOTES

- 1. ALL CONSTRUCTION SHALL COMPLY WITH BOROUGH, TOWNSHIP AND COUNTY CODES AND STANDARDS. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE OSHA, FEDERAL, STATE AND LOCAL REGULATIONS.
- 2. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY CONSTRUCTION PERMITS REQUIRED TO PERFORM ALL OF THE WORK. THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES. PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS
- 3. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT THE OWNER IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND/OR FIELD CONDITIONS SO THAT APPROPRIATE REVISIONS CAN BE MADE PRIOR TO CONSTRUCTION. ANY CONFLICT BETWEEN DRAWINGS AND THE SPECIFICATIONS SHALL BE CONFIRMED WITH THE OWNER PRIOR TO BIDDING.
- 4. SHOULD ANY UNCHARTED, OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, CONSULT THE OWNER IMMEDIATELY BEFORE PROCEEDING FURTHER WITH THE WORK IN THIS AREA.
- THE CONTRACTOR SHALL ABIDE BY ALL OSHA, FEDERAL, STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN CLOSE PROXIMITY TO OVERHEAD ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT THE POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER SAFEGUARDS.
- 6. THE CONTRACTOR SHALL RESTORE ANY STRUCTURES, PIPE, UTILITY, PAVEMENT, CURBS SIDEWALKS, LANDSCAPED AREAS, ETC. WITHIN THE SITE OR ADJOINING PROPERTIES DISTURBED DURING DEMOLITION OR CONSTRUCTION TO THEIR ORIGINAL CONDITION OR BETTER, AND TO THE SATISFACTION OF THE OWNER AND LOCAL MUNICIPALITY.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE TO INSTALL AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF PEDESTRIANS AND VEHICLES CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS, FENCES AND UNIFORM TRAFFIC CONTROLLERS IN ACCORDANCE WITH PENNDOT MP LOCAL GOVERNING AUTHORITIES. CONTRACTOR SHALL MAINTAIN ALL TRAFFIC LANES AND PEDESTRIAN WALKWAYS AT ALL TIMES UNLESS WRITTEN APPROVAL FROM PennDOT, LOCAL MUNICIPALITY, COUNTY, OR OTHER GOVERNING AUTHORITY IS RECEIVED.
- THE CONTRACTOR SHALL NOTIFY THE OWNER SHOULD ANY DISCREPANCY REGARDING THE PROPOSED WORK OR UNFORESEEN CONDITIONS ARISE PRIOR TO PROCEEDING FURTHER
- THE CONTRACTOR SHALL PROVIDE AS-BUILT RECORDS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND UTILITIES) TO THE OWNER FOLLOWING COMPLETION OF CONSTRUCTION
- 10. REFER TO DETAIL SHEETS FOR EROSION AND SEDIMENT CONTROL, STORM DRAINAGE, UTILITY, PAVING, CURBING, SIGNAGE, AND OTHER DETAILS AS APPLICABLE.
- 11. PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH PENNDOT SPECIFICATIONS AND SHALL BE EITHER COLD LAID THERMOPLASTIC TAPE OR PAINTED AS DESIGNATED ON THE
- 12. ALL SITE DIMENSIONS ARE REFERENCED TO THE FACE OF CURBS OR EDGE OF PAVING UNLESS OTHERWISE NOTED. ALL BUILDING DIMENSIONS ARE REFERENCED TO THE OUTSIDE FACE OF THE STRUCTURE UNLESS OTHERWISE NOTED.
- 13. ALL PAVING MATERIALS FURNISHED AND WORK COMPLETED SHALL BE IN STRICT ACCORDANCE WITH PennDOT SPECIFICATIONS PUBLICATION 408 AND PennDOT STANDARD DETAILS AS AMENDED UNLESS OTHERWISE SPECIFIED.
- 14. THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL AND DISPOSAL OF ALL RUBBISH, TRASH, DEBRIS, AND ORGANIC MATERIAL IN A LAWFUL MANNER.
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS FOR BUILDING, WALLS, CONCRETE SLABS, AND UTILITY SERVICE POINT CONNECTIONS AND NOTIFYING THE OWNER OF ANY CONFLICTS OR DISCREPANCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL REFERENCE BUILDING CONSTRUCTION PLANS FOR EXACT LOCATIONS OF ALL UTILITY CONNECTIONS TO BUILDINGS, DOOR STEP LOCATIONS, ETC.
- 16. INFORMATION ON EXISTING UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND FIELD SURVEY AND IS CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES INCLUDING SERVICES PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT THE PA ONE CALL SYSTEM 72 HOURS BEFORE COMMENCEMENT OF WORK AT 1-800-242-1776 AND VERIFY
- 17. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL PRODUCTS, MATERIALS AND PLAN SPECIFICATIONS TO THE ARCHITECT AS REQUIRED FOR REVIEW AND APPROVAL, PRIOR TO FABRICATION OR DELIVERY TO THE SITE. ALLOW A MINIMUM OF 14 WORKING DAYS FOR
- 18. PLANS PREPARED UTILIZING DATA FROM SURVEY PREPARED GREGORY C. NOLL OF VALLEY LAND SERVICES, LLC, AT 4383 HECKTOWN ROAD, BETHLEHEM, PA 18020, AND DATED

TITLE

COVER SHEET

SITE DETAILS

SITE PLAN

ALTA/NSPS SURVEY

DEMOLITION PLAN

LANDSCAPE PLAN

SITE UTILITY PLAN

SITE UTILITY DETAILS

GRADING & STORM DRAINAGE PLAN

PHOTOMETRIC LIGHTING PLAN

EROSION & SEDIMENTATION CONTROL PLAN

EROSION & SEDIMENTATION CONTROL DETAILS

EROSION & SEDIMENTATION CONTROL DETAILS

POST-CONSTRUCTION STORMWATER MANAGEMENT PLAN

POST-CONSTRUCTION STORMWATER MANAGEMENT DETAILS

POST-CONSTRUCTION STORMWATER MANAGEMENT DETAILS

SHEET

2 of 16

C1.0

C1.3

D1.0

L1.0

PCSM1

PCSM3

CS

Preliminary/Final Land Development Plans For Proposed

Dieners Hill

SITE LOCATION MAP SCALE: 1"=2,000'

AutoZone Store #2800 489 Pottsville St. Clair Highway Township of East Norwegian & Borough of St. Clair, County of Schuylkill Commonwealth of Pennsylvania

SUBSURFACE COAL REPORT

SEE SUBSURFACE COAL REPORT PREPARED BY ACA ENGINEERING, INC. DATED OCTOBER 18, 2021, REGARDING A HIGH RISK OF SUBSIDENCE AT THE PROJECT SITE, AND GROUTING RECOMMENDATIONS. CONTRACTOR TO INCLUDE COST OF MINE GROUTING IN PROJECT BID.

*PARKING REQUIREMENTS

* REQUIREMENTS PER SCHUYLKILL COUNTY SALDO.

PARKING REQUIREMENTS FOR RETAIL STORE: PARKING STALL SIZE: 9' x 18' REQUIRED; 9' x 18' PROPOSED. (E. NORWEGIAN TWP./SCHUYLKILL COUNTY) PARKING STALL SIZE: 9' x 20' REQUIRED; 9' x 20' PROPOSED. (ST. CLAIR BOROU

ONE (1) PARKING STALL PER 200 SO. FT. OF FLOOR AREA ACCESSIBLE TO CUSTOMERS

3,296 SF ÷ 200 SF = 17 PARKING STALLS REQUIRED

3,296 SF = CUSTOMER FLOOR ACCESS AREA

37 PARKING STALLS PROPOSED 31 STALLS @ 9' x 18' (SCHUYLKILL COUNTY) 6 STALLS @ 9' x 20' (ST. CLAIR BOROUGH)

7,382 SF = TOTAL FLOOR AREA 4,086 SF = MERCHANDISE STORAGE AREA BEHIND COUNTER

SURVEYORS & ENGINEERS, LLC

Surveyors • Engineers • Site Planners 375 Northgate Drive Warrendale, PA 15086 Ph: (724) 934-2810 Fax: (724) 934-2811 mdmcadd@mdmllc.com www.mdmllc.com

DEVELOPMENT STATEMENT & SCHEDULE

DEVELOPMENT INCLUDES DEMOLITION OF EXISTING BUILDING AND CAR WASH, CONSTRUCTION OF A 7,382 SF BUILDING, TRASH CORRAL, PARKING INCLUDING HANDICAP ACCESSIBLE SPACES, ASSOCIATED UTILITIES, AND LANDSCAPING IMPROVEMENTS. APPROXIMATE START OF PROJECT IS JUNE 1, 2022 AND APPROXIMATE COMPLETION BY DECEMBER 31, 2022.

HIGHWAY OCCUPANCY NOTE

"A HIGHWAY OCCUPANCY PERMIT IS REQUIRED PURSUANT TO SECTION 420 OF THE ACT OF JUNE 1, 1945 (P.L. 1242, No. 428), KNOWN AS THE 'STATE HIGHWAY LAW', BEFORE ACCESS TO A STATE HIGHWAY IS PERMITTED. ACCESS TO THE STATE HIGHWAY SHALL BE AS AUTHORIZED BY A HIGHWAY OCCUPANCY PERMIT, AND THE TOWNSHIP COUNCIL APPROVAL OF THIS PLAN IN NO WAY IMPLIES THAT SUCH A PERMIT CAN BE ACQUIRED."

WAIVERS REQUESTED

ST. CLAIR BOROUGH WAIVER REQUESTS:

- SALDO §302 (§302.A.3 & §302.C.1) REGARDING THE GENERAL PROCEDURE FOR SUBDIVISIONS AND LAND DEVELOPMENTS TO HAVE THE PLAN SUBMISSION CONSIDERED AS A PRELIMINARY & FINAL LAND DEVELOPMENT PLAN. THE PLANS PRESENTED INCLUDE THE REQUIREMENTS FROM BOTH THE PRELIMINARY AND FINAL MAJOR SUBDIVISION PLAN CHECKLISTS. WAIVER REQUEST GRANTED ON XX/XX/2021
- 2. SALDO §1105.G.1 REGARDING THE MINIMUM DISTANCE FROM THE CENTERLINE FROM AN ACCESS ROAD OR DRIVEWAY, AT ITS POINT OF ACCESS TO THE STREET, TO THE CENTERLINE OF THE INTERSECTING STREET, SHALL NOT BE LESS THAN THREE HUNDRED FEET (300') IF EITHER STREET IS AN ARTERIAL STREET (RTE. 61 IS ARTERIAL). WAIVER REQUEST GRANTED ON XX/XX/2021

BOROUGH OF SAINT CLAIR CERTIFICATE OF MUNICIPAL APPROVAL

AT A MEETING HELD ON _______, 20_____, THE BOROUGH OF SAINT CLAIR PLANNING COMMISSION BY ______ DULY ENACTED,

APPROVED THE LAND DEVELOPMENT OF THE PROPERTY OF AUTOZONE DEVELOPMENT

PRESIDENT
SECRETARY

	CERTIF	ICATE	OF (DWNER	SHI
--	---------------	-------	------	--------------	-----

FLOOD ZONE NOTE

By graphical representation only, this site is located in Zone X

#42107C0354E, which has an effective date of November 19,

Panel No. 422015 0354 E, and 422003 0354 E, Map

FINAL APPROVAL BY THE SCHUYLKILL COUNTY PLANNING COMMISSION.

2014 and is not in a special flood hazard area.

REGISTERED PROFESSIONAL LAND SURVEYOR

REGISTERED PROFESSIONAL ENGINEER

PENNSYLVANIA REGISTRATION NUMBER: ____SU075048

PENNSYLVANIA REGISTRATION NUMBER: ____PE052940E

(unshaded), as shown on Flood Insurance Rate Map, Community

SCHUYLKILL COUNTY PLANNING COMMISSION APPROVAL

THE SUBDIVISION/LAND DEVELOPMENT PLAN AS SHOWN HEREON IS HEREBY GRANTED

CERTIFICATE OF ACCURACY

HEREBY CERTIFY THAT, TO THE BEST OF MY KNOWLEDGE, ALL DRAWINGS BEARING MY

CERTIFICATE OF ACCURACY

HEREBY CERTIFY THAT, TO THE BEST OF MY KNOWLEDGE, ALL DRAWINGS BEARING MY

SEAL ARE TRUE AND CORRECT AS TO ACCURACY AS REQUIRED BY THE COMMISSION

CERTIFICATE OF OWNERSHIP

THIS PLAN IS HEREBY EXECUTED AND DELIVERED BY <u>LEEMILT'S PETROLEUM, INC.</u> WHICH IS THE OWNER (OR EQUITABLE OWNER) OF THE PROPERTY SHOWN ON THIS

PLAN, AND THE SAID PLAN WAS MADE BY AUTHORITY THE OF THE CORPORATION.

IN WITNESS WHEREOF LEEMILT'S PETROLEUM, INC. HAS DULY CAUSED THIS TO

AND ITS CORPORATE SEAL TO BE AFFIXED THERETO THIS

SEAL ARE TRUE AND CORRECT AS TO ACCURACY AS REOUIRED BY THE COMMISSION AND WERE PREPARED BY ME OR UNDER MY DIRECTION AND FOR WHICH I ACCEPT FULL

RESPONSIBILITY AND THAT THE PERIMETER MONUMENTS HAVE BEEN ACCURATELY

STATE: COUNTY:
ON THIS DAY OF 20, BEFORE ME, THE
UNDERSIGNED OFFICER, PERSONALLY APPEARED WHO BEING DULY SWORN ACCORDING TO LAW, DEPOSES AND CONFIRMS THAT SA IS THE OWNER (OR EQUITABLE OWNER) OF THE PROPERTY SHOWN ON THIS PLAN. WITNESS MY HAND AND SEAL THE DAY AND DATE ABOVE WRITTEN. M

NOTARY
MY COMMISSION EXPIRES:

CERTIFICATE	OF	OWNERSHIP

THIS PLAN IS HEREBY EXECUTED AND I	DELIVERED BY AUTOZONE DEVELOPMENT, LLC
, ,	OWNER) OF THE PROPERTY SHOWN ON THIS
PLAN, AND THE SAID PLAN WAS MADE I	BY AUTHORITY THE OF THE CORPORATION.
IN WITNESS WHEREOF <u>AUTOZONE DEV</u>	/ELOPMENT, LLC HAS DULY CAUSED THIS TO
DE EVECUTED DY ITC VICE DRECIDENT	AND DV ITC
BE EXECUTED BY ITS VICE-PRESIDENT,	AND BY ITS
SECRETARY,	AND ITS CORPORATE SEAL TO BE AFFIXED
<u> </u>	

CRETART,AND		_ AND ITS CORPO	KATE SEAL	. TO BE AFFIXED	,
ERETO THIS	DAY OF		20	<u>-</u> :	
			_		
			-		

	<u>CERTIFICATE OF OWNERSHIP</u>			
	STATE: COUNTY:			
,	ON THIS DAY OF 20, BEFORE ME, THE			
	UNDERSIGNED OFFICER, PERSONALLY APPEARED WHO BEING DULY SWORN ACCORDING TO LAW, DEPOSES AND CONFIRMS THAT SAID IS THE OWNER (OR EQUITABLE OWNER) OF THE PROPERTY SHOWN ON THIS PLAN. WITNESS MY HAND AND SEAL THE DAY AND DATE ABOVE WRITTEN.			

MY COMMISSION EXPIRES:

	4
	4
	4
	4
	4
	4
	4
	4
	4
	4
	4
	4
	4
	4

UPI CERTIFICATION BLOCK



SCALE: AS NOTED

REVISIONS

1 11-30-21 PER BOROUGH & COUNTY COMME

ARCHITECT: LE

DRAFTSMAN: CWT

CHECKED BY: CAD

7n2-R

ZONING INFORMATION

CONTENTS: BOROUGH OF ST. CLAIR ZONING DISTRICT: C-2 (GENERAL COMMERCIAL DISTRICT) RETAIL & WHOLESALE OF GOODS, PREPARED FOODS, AND SERVICES IS A PERMITTED USE

(570) 429-0640 WITHIN THIS ZONING DISTRICT. ROLAND PRICE REQUIRED DESCRIPTION MINIMUM LOT AREA 10,000 SF 37,581 SF (TOTAL) MINIMUM LOT WIDTH 50' MINIMUM FRONT YARD SETBACK 20'-0" 83'-4" 10'-0" EACH SIDE MINIMUM SIDE YARD SETBACK 25'-1" MINIMUM REAR YARD SETBACK 20'-0" N/A 10'-0" ARTERIAL OR MINIMUM PAVED AREA SETBACK COLLECTOR <2 ACRES 14'-0" MAX 35'-0" OR 2.5 STORIES 19'-0" MAXIMUM BUILDING HEIGHT MAXIMUM BUILDING COVERAGE N/A 35% N/A MAXIMUM IMPERVIOUS COVERAGE 35%

50% OF FRONT YARD

SETBACK = 10'-0"

TOWNSHIP OF EAST NORWEGIAN ZONING DISTRICT: C-3 (HIGHWAY COMMERCIAL DISTRICT) A RETAIL STORE IS A PERMITTED USE WITHIN THIS ZONING DISTRICT.

MINIMUM SIGN SETBACK

ZONING INFORMATION WAS OBTAINED FROM: SCHUYLKILL COUNTY PLANNING & ZONING DEPT. **401 NORTH SECOND STREET** POTTSVILLE, PA 17901 (570) 628-1416 ZONING OFFICER

12'-8"

ZONING INFORMATION WAS OBTAINED FROM:

BOROUGH OF SAINT CLAIR

16 SOUTH THIRD STREET

SAINT CLAIR, PA 17970

DESCRIPTION	REQUIRED	PROPOSED
IINIMUM LOT AREA	10,000 SF	37,581 SF (TOTAL)
INIMUM LOT WIDTH	75'-0"	220.83'
INIMUM FRONT YARD SETBACK	35'-0"	80'-2"
INIMUM SIDE YARD SETBACK	25'-0"	25'-1"
IINIMUM REAR YARD SETBACK	25'-0"	N/A
MINIMUM PAVED AREA SETBACK	10'-0" (20-99 PARKING SPACES)	2'-9" MIN. 7'-7" MAX.
MAXIMUM BUILDING HEIGHT	100'-0"	19'-0"
MAXIMUM BUILDING COVERAGE	60%	19.6%
MAXIMUM IMPERVIOUS COVERAGE	90%	70.8%
MINIMUM SIGN SETBACK	25'-0"	N/A

UTILITY SERVICE INFORMATION

GAS SERVICE NATURAL GAS SERVICE IS PPL ELECTRIC UTILITIES NOT AVAILABLE TO THIS SITE. 220 MOREA ROAD FRACKVILLE, PA 17931 570-459-7368 MR. BRENDAN DOTY W.O. #58539704

TELEPHONE SERVICE VERIZON 11 RIDGE ROAD BLOOMSBURG, PA 17815 570-490-9301

WATER SERVICE SCHUYLKILL COUNTY MUNICIPAL AUTHORITY 221 SOUTH CENTER STREET

MR. ROBERT JAWORSKI

UTILITY MANAGER

P.O. BOX 960 POTTSVILLE, PA 17901 570-728-4376 MR. KYLE MAHONEY,

LAND OWNER:

LEEMILT'S PETROLEUM, INC.

NEW YORK, NY 10017-6318

WARRENDALE, PA 15086

(724) 934-2810

292 MADISON AVENUE, 9TH FLOOR

SCHUYLKILL COUNTY PLANNING OFFICE **401 NORTH SECOND STREET** POTTSVILLE, PA 17901 570-628-1038

PennDOT DISTRICT 5-0 1002 HAMILTON STREET ALLENTOWN, PA 18101 MR. BRETT KLINGEL DISTRICT PERMIT MANAGER (610) 871-4167

SANITARY SEWER SERVICE SAINT CLAIR SEWER AUTHORITY 16 SOUTH THIRD STREET SAINT CLAIR, PA 17970 MR. JOE COLLINS (570) 429-0640

BENESCH ENGINEERING 400 ONE NORWEGIAN PLAZA POTTSVILLE, PA 17901 570-624-4286 MR. CHRIS McCOACH

LESSEE/DEVELOPER: AUTOZONE DEVELOPMENT, LLC PROPERTY MANAGEMENT DEPT. 8700 123 SOUTH FRONT STREET P.O. BOX 2198 MEMPHIS, TN 38103 JASON OLSEN, SR. DIRECTOR REAL ESTATE (901) 495-7625

ENGINEER: MDM SURVEYORS & ENGINEERS, LLC 375 NORTHGATE DRIVE


(610) 365-2907 EUGENE S. DVORCHAK, PE, PA LIC. No. PE052940E

KEVIN MURPHY, PRE-CONSTRUCTION SPECIALIST SURVEYOR:

VALLEY LAND SERVICES, LLC 4383 HECKTOWN ROAD BETHLEHEM, PA 18020 GREGORY C. NOLL, PLS, PA LIC. No. SU075048

LLC, AS SHOWN HEREON. VICE-PRESIDENT BOROUGH OF SAINT CLAIR
CERTIFICATE OF MUNICIPAL APPROVAL SERTIFICATE OF OVANIERCUIT AT A MEETING HELD ON _____ SAINT CLAIR BOROUGH COUNCIL BY ______ DULY ENACTED, APPROVED THE LAND DEVELOPMENT OF THE PROPERTY OF AUTOZONE DEVELOPMENT LLC, AS SHOWN HEREON.

SCHUYLKILL RECORDER OF DEED





LAND OWNERS:

(646) 349-0721

P.O. BOX 2198

(901) 495-7625

SURVEYOR:

MEMPHIS, TN 38103

LEEMILTS PETROLEUM, INC.

NEW YORK, NY 10017-6318

LESSEE/DEVELOPER:

123 SOUTH FRONT STREET

VALLEY LAND SERVICES, LLC

4383 HECKTOWN ROAD

BETHLEHEM, PA 18020

375 NORTHGATE DRIVE

WARRENDALE, PA 15086

(610) 365-2907

(724) 934-2810

ENGINEER:

AUTOZONE DEVELOPMENT, LLC

PROPERTY MANAGEMENT DEPT. 8700

JASON OLSON, SR. DIRECTOR REAL ESTATE

KEVIN MURPHY, PRE-CONSTRUCTION SPECIALIST

GREGORY C. NOLL, PLS, PA LIC. No. SU075048

EUGENE S. DVORCHAK, PE, PA LIC. No. PE052940E

BOROUGH OF ST. CLAIR

ZONED "A-1"

PID 62-05-0038.000

N/F SKAD SOLUTIONS LLC

DBV 2528 PG 1452

51 ANN STREET

TOWNSHIP OF EAST NORWEGIAN

NNER: SKAD SOLUTIONS, LLC

803 HAYCOCK VIEW DRIVE

PERKASIE, PA 18944

PID 08-02-001.001

N/F LOWE'S HOME CENTERS, INC

DBV 0093 PG 104

391 POTTSVILLE ST CLAIR HWY

TOWNSHIP OF EAST NORWEGIAN

ZONED "C-3"

OWNER: ROBERT SEITZINGER

LOWES HOME CENTERS, INC.

TAX DEPT. 1000 LOWES BOULEVARD

MOORESVILLE, NC 28117

ZONED "C-3"

MDM SURVEYORS & ENGINEERS, LLC

BENCHMARK-

BOROUGH OF ST. CLAIR ASPHALT

ZONED "C-2"

(IN FEET 1 inch = 20 ft.

ELEV.=784.82

SITE LOCATION MAP SCALE: 1"=2,000'

GENERAL CONSTRUCTION NOTES

- 1. ALL CONSTRUCTION SHALL COMPLY WITH LOCAL MUNICIPALITY AND COUNTY CODES AND STANDARDS. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE OSHA, FEDERAL, STATE AND LOCAL REGULATIONS.
- THE CONTRACTOR SHALL OBTAIN ALL NECESSARY CONSTRUCTION PERMITS REQUIRED TO PERFORM ALL THE WORK. THE CONTRACTOR SHALL POST ALL BONDS, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK.
- 3. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT THE OWNER IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND/OR FIELD CONDITIONS SO THAT APPROPRIATE REVISIONS CAN BE MADE PRIOR TO CONSTRUCTION. ANY CONFLICT BETWEEN DRAWINGS AND THE SPECIFICATIONS SHALL BE CONFIRMED WITH THE CONSTRUCTION MANAGER PRIOR TO
- 4. SHOULD ANY UNCHARTED, OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, CONSULT THE ENGINEER AND THE ARCHITECT IMMEDIATELY BEFORE PROCEEDING FURTHER WITH THE WORK IN THIS AREA.
- DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER, LOCAL MUNICIPALITY AND/OR UTILITY COMPANY. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY OR PERMANENT SERVICE HAS BEEN PROVIDED.
- 6. THE CONTRACTOR SHALL ABIDE BY ALL OSHA, FEDERAL, STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN CLOSE PROXIMITY TO OVERHEAD ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT THE POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER
- THE CONTRACTOR SHALL RESTORE ANY STRUCTURES, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS, ETC. WITHIN THE SITE OR ADJOINING PROPERTIES DISTURBED DURING DEMOLITION OR CONSTRUCTION TO THEIR ORIGINAL CONDITION OR BETTER, AND TO THE SATISFACTION OF THE OWNER AND LOCAL MUNICIPALITY. ALL COSTS TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE BASE BID FOR THIS
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE TO INSTALL AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF PEDESTRIANS AND VEHICLES CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS, FENCES AND UNIFORM TRAFFIC CONTROLLERS IN ACCORDANCE WITH THE STATE DEPARTMENT OF TRANSPORTATION OR AS REQUIRED OR DIRECTED BY THE SITE ENGINEER OR CONSTRUCTION MANAGER OR LOCAL GOVERNING AUTHORITIES. CONTRACTOR SHALL MAINTAIN ALL TRAFFIC LANES AND PEDESTRIAN WALKWAYS AT ALL TIMES UNLESS WRITTEN APPROVAL FROM THE DEPARTMENT OF TRANSPORTATION, LOCAL MUNICIPALITY, COUNTY, OR OTHER GOVERNING AUTHORITY IS RECEIVED
- 9. THE CONTRACTOR SHALL NOTIFY THE ENGINEER SHOULD ANY DISCREPANCY REGARDING THE PROPOSED WORK OR UNFORESEEN CONDITIONS ARISE PRIOR TO PROCEEDING FURTHER WITH THE AFFECTED WORK.
- 10. THE CONTRACTOR SHALL PROVIDE AS-BUILT RECORDS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND UTILITIES) TO THE OWNER AND THE ARCHITECT FOLLOWING COMPLETION OF CONSTRUCTION ACTIVITIES.
- 11. REFER TO DETAIL SHEETS FOR EROSION AND SEDIMENT CONTROL, STORM DRAINAGE, UTILITY, PAVING, CURBING, SIGNAGE, AND RETAINING WALL DETAILS AS APPLICABLE.
- 12. PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH DEPARTMENT OF TRANSPORTATION GUIDELINES AND SHALL BE EITHER COLD LAID THERMOPLASTIC TAPE OR PAINTED AS DESIGNATED ON THE PLANS OR PAVEMENT MARKING DETAILS.
- 13. SITE DIMENSIONS ARE REFERENCED TO THE FACE OF CURBS OR EDGE OF PAVING UNLESS OTHERWISE NOTED. ALL BUILDING DIMENSIONS ARE REFERENCED TO THE OUTSIDE FACE OF THE STRUCTURE UNLESS OTHERWISE NOTED.
- 14. ALL PAVING MATERIALS FURNISHED AND WORK COMPLETED SHALL BE IN STRICT ACCORDANCE WITH THE STATE DEPARTMENT OF TRANSPORTATION GUIDELINES UNLESS
- OTHERWISE SPECIFIED. 15. THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL AND DISPOSAL OF ALL RUBBISH, TRASH, DEBRIS, AND ORGANIC MATERIAL IN A LAWFUL MANNER.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS FOR BUILDING, WALLS, CONCRETE SLABS, AND UTILITY SERVICE POINT CONNECTIONS AND NOTIFYING THE OWNER AND ENGINEER OF ANY CONFLICTS OR DISCREPANCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL REFERENCE BUILDING CONSTRUCTION PLANS FOR EXACT LOCATIONS OF ALL UTILITY CONNECTIONS TO BUILDINGS AND DOOR STEP LOCATIONS.
- 17. PIPE BOLLARDS SHALL BE INSTALLED IN TRAFFIC AND LOADING AREAS AS REQUIRED TO PROTECT BUILDING CORNERS, RECEIVING AREAS, HYDRANTS, TRANSFORMERS, METERS, GENERATORS, COMPACTORS, STEPS, AND RAILINGS, AS NECESSARY.
- 18. THE OWNER, AT THEIR DISCRETION, RESERVES THE RIGHT TO MODIFY THE DETAILS AND STANDARDS OF CONSTRUCTION FOR ALL PRIVATE FACILITIES FROM THAT INDICATED ON THE APPROVED PLAN, PROVIDED THAT THE ALTERNATE STANDARD COMPLIES WITH LOCAL CODE AND/OR UTILITY COMPANY REQUIREMENTS AND THE GENERAL DESIGN INTENT OF THE PROJECT IS NOT COMPROMISED.
- 19. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL PRODUCTS, MATERIALS AND PLAN SPECIFICATIONS TO THE OWNER AS REQUIRED FOR REVIEW AND APPROVAL, PRIOR TO FABRICATION OR DELIVERY TO THE SITE. ALLOW A MINIMUM OF 14 WORKING DAYS
- 20. THE CONTRACTOR SHALL REFERENCE ARCHITECTURAL PLANS FOR EXACT DIMENSIONS AND CONSTRUCTION DETAILS OF THE BUILDING, ROOF DRAINS, AND CONCRETE
- 21. TRAFFIC CONTROL SIGNAGE SHALL CONFORM TO THE STATE DEPARTMENT OF TRANSPORTATION STANDARD DETAIL SHEETS AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. SIGNS SHALL BE INSTALLED PLUMB.
- 22. INFORMATION ON EXISTING UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT THE PA ONE CALL SYSTEM WITHIN THREE (3) WORKING DAYS BEFORE
- 23. NO PART OF THE LOT IS LOCATED WITHIN ANY FLOODPLAIN AREAS.
- 24. FIRE LANES SHALL BE ESTABLISHED AND PROPERLY DESIGNATED IN ACCORDANCE WITH THE LOCAL MUNICIPALITY AND LOCAL FIRE DEPARTMENT REQUIREMENTS.

COMMENCEMENT OF WORK AT 1-800-242-1776 AND VERIFY ALL LOCATIONS.

292 MADISON AVENUE, 9th FLOOR **GENERAL NOTES**

- 1. PROOF ROLL BUILDING AND ALL PARKING AREAS. NOTIFY THE ARCHITECT OF ANY UNACCEPTABLE AREAS.
 - 2. EDGE OF NEW PAVEMENT TO BE FLUSH WITH EXISTING PAVEMENT.
 - 3. ALL SIDEWALK CURB AND GUTTER STREET PAVING, CURB CUTS, DRIVEWAY APPROACHES, HANDICAP RAMP, ETC. CONSTRUCTED OUTSIDE THE PROPERTY LINE IN THE RIGHT-OF-WAY SHALL CONFORM TO ALL MUNICIPAL AND/OR STATE SPECIFICATIONS AND REQUIREMENTS.
 - 4. FOR AREAS OUTSIDE THE PROPERTY LINES, REPAIR AND/OR REPLACE ALL DAMAGE DONE TO EXISTING ELEMENTS (SIDEWALKS, PAVING, LANDSCAPING, ETC.) AS REQUIRED BY OWNER AND/OR GOVERNING AUTHORITY.
 - 5. FOR PROPOSED UTILITY LOCATIONS, SEE THE SITE UTILITY PLAN. 6. PROPOSED USE: RETAIL SALE OF AUTO PARTS.

LIMIT SIGN

7. SEE SUBSURFACE COAL REPORT PREPARED BY ACA ENGINEERING, INC., DATED OCTOBER 18, 2021, REGARDING A HIGH RISK OF SUBSIDENCE AT THE PROJECT SITE, AND GROUTING RECOMMENDATIONS. CONTRACTOR TO INCLUDE COST OF MINE

GROUTING IN PROJECT BID. 8. INFORMATION REGARDING CLEAR SIGHT TRIANGLES AND STATIONS HAS BEEN PROVIDED BY WOOSTER & ASSOCIATES.

TOWNSHIP OF EAST NORWEGIAN

D62-05-0037.000

& GETTY REALTY CORP

DBV 1359 PG 0286

BERKSHIRE CONSTR CO INC

SWILLE ST CLAIR HWY

LE. EASEMENT

POLE AND WIRES

|\ BK 264 PG 657

<u>UP#: B-12</u>

BLDG. AREA = 7,382 SF

PARKING SPACES = 37

FINISH FLOOR ELEV. = 779.30

ID 08-07-0014.000

BERKSHIRE CONSTR CO INC

TTTY REAL ESTATE CORP

FASFMFNT

4 FT FACILITY

CLEARANCE

BK 264 PG 657

SIGHT LINE LOOKING

ALFRED BENESCH-COMPANY SIGN

RIGHT (DRIVE B)

4,086 SF = MERCHANDISE STORAGE AREA BEHIND COUNTER 3,296 SF = CUSTOMER FLOOR ACCESS AREA

PARKING STALL SIZE: 9' x 20' REQUIRED; 9' x 20' PROPOSED. (ST. CLAIR BOROUGH)

3,296 SF ÷ 200 SF = 17 PARKING STALLS REQUIRED

ONE (1) PARKING STALL PER 200 SQ. FT. OF FLOOR AREA ACCESSIBLE TO CUSTOMERS.

* REQUIREMENTS PER SCHUYLKILL COUNTY SALDO.

7,382 SF = TOTAL FLOOR AREA

PARKING REQUIREMENTS FOR RETAIL STORE:

SUMMARY CHART UPI 62-05-0037.000 AREA: 28,825.942± SF = 0.662 ACRES UPI 08-07-0014.000 AREA: 8,754.308± SF = 0.201 ACRES TOTAL PROPERTY AREA: 37,581 SF = 0.9 ACRES LIMIT OF DISTURBANCE: 42,250 SF = 1.0 ACRES TOTAL NUMBER OF LOTS IN DEVELOPMENT: 1 PROPOSED WATER SYSTEM: PUBLIC PROPOSED SANITARY SYSTEM: PUBLIC DEED SOURCE: DEED BOOK VOLUME 1359, PAGE 0286 PROPOSED USE: COMMERCIAL - RETAIL SALE OF AUTO PARTS

*PARKING REQUIREMENTS

PARKING STALL SIZE: 9' x 18' REQUIRED; 9' x 18' PROPOSED. (E. NORWEGIAN TWP./SCHUYLKILL COUNTY)

31 STALLS @ 9' x 18' (SCHUYLKILL COUNTY)

6 STALLS @ 9' x 20' (ST. CLAIR BOROUGH)

37 PARKING STALLS PROPOSED

ST. CLAIR: 20202272148 EAST NORWEGIAN: 20202272149

CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR **CONSTRUCTION PHASE AND 10 WORKING** DAYS IN DESIGN STAGE - STOP CALL PENNSYLVANIA ONE CALL SYSTEM, INC

SEE PLANS PREPARED BY

43281S50568

OWNER: JOANN T. & THOMAS P. BRENNAN

56 N. SECOND STREET

ST. CLAIR, PA 17970

PID 08-07-0015.001

N/F JOANN BRENNAN & THOMAS P BRENNAN

DBV 2507 PG 1460

435 POTTSVILLE-ST CLAIR HIGHWAY

TOWNSHIP OF EAST NORWEGIAN

ZONED "C-3"

WOOSTER & ASSOCIATES FOR

INFORMATION REGARDING WORK

WITHIN PennDOT RIGHT-OF-WAY

1-800-242-1776

- 1 PIPE GUARD SEE DETAIL 11/C1.A.
- 2 DUMPSTER LAYOUT SEE DETAILS 12, 13, 14 & 15/C1.A.
- (3) SERVICE DOOR SEE DETAIL 10/C1.A.
- CONCRETE PAVING SEE DETAIL 3/C1.A. EXPANSION AND CONTROL JOINTS - SEE DETAILS 20 & 21/C1.A. MAXIMUM
- CONCRETE LIGHT POLE BASE SEE DETAIL ON PHOTOMETRIC LIGHTING PLAN (PH1.0). AIM LIGHT FIXTURE IN DIRECTION AS INDICATED.
- 7 ROLL-OVER CURB @ CONCRETE PAVING SEE DETAIL 1/C1.A.
- 7A ROLL-OVER CURB @ ASPHALT PAVING SEE DETAIL 2/C1.A.
- (8) WHEEL STOP. SEE DETAIL 22/C1.A.
- 9 ACCESSIBLE RAMP. CONSTRUCT 6" WIDE CONCRETE CURB AGAINST BUILDING AT
- (10) FROST-PROOF HOSE BIBB SEE DETAIL 6, SHEET M2.

- (12) BARRIER-FREE PARKING SYMBOL SEE DETAIL 7/C1.A.
- 4" WIDE DIAGONAL STRIPES PAINTED WITTE AT 2.1. O.C. STRIPES AT ACCESSIBLE PARKING TO BE BLUE SEE DETAIL 4" WIDE DIAGONAL STRIPES PAINTED WHITE AT 2 FT. O.C.
- PROVIDE ONE VAN ACCESSIBLE SIGN.

- ACCESSIBLE RAMP SEE DETAILS 5 & 6/C1.A MAX. SLOPE 1:12 (8.33%), MAX. CROSS-SLOPE 1:50 (2.00%), TRUNCATED DOME
- NEW LANDSCAPE AREA PROVIDE 3" TOPSOIL & SOD. SEE NEW LANDSCAPE AREA - PROVIDE 3 TOF 301L SHEET L1.0 FOR ADDITIONAL INFORMATION.
- 3'x13'x20' OAH PYLON SIGN. (UNDER SEPARATE PERMIT). ALL SIGNS SHALL BE PERMITTED IN ACCORDANCE WITH MUNICIPAL REGULATIONS.
- (20) SLOPE CURB FLUSH TO PAVEMENT AT 4:1 SLOPE.
- EXISTING MONITORING WELL TO REMAIN. CONFIRM WITH ENVIRONMENTAL CONSULTANT. INSTALL CAST FRAME AND
- (22) 5'x5' CONCRETE PAD. SEE DETAIL 18/C1.A.
- NEW CONCRETE CURB TO MATCH EXISTING, PER MUNICIPAL NEW CONCRETE COREQUIREMENTS.
- BUILDING. SEE SITE UTILITY PLAN (U1.0). FURNISH AND INSTALL 6" Ø STD. BOLLARDS FILLED WITH CONCRETE TO PROTECT TANK. SEE DETAIL 11/C1.A.
- 8" THK. POURED-IN-PLACE CONCRETE RETAINING WALL. SEE DETAIL ON SHEET C1.A. SEE GRADING PLAN FOR ELEVATIONS.
- (27) CONCRETE SPLASH BLOCK. SEE DETAIL 16/C1.A.
- NEW FULL-DEPTH ASPIRAL FAVERILES. ... MATCH EXISTING. SEAL ALL EDGES WITH AC-20. PER NEW FULL-DEPTH ASPHALT PAVEMENT AT UTILITY WORK, TO BOROUGH ENGINEER, EXISTING PAVEMENT IS 1.5" WEARING ON 8" RCP. RESTORATION MUST MATCH EXISTING.
- (29) OFF-STREET LOADING AREA 10' x 50'.
- "STOP" SIGN (R1-1) MOUNTED ON GALVANIZED STEEL POLE,

ZONING INFORMATION

BOROUGH OF ST. CLAIR ZONING DISTRICT: C-2 (GENERAL COMMERCIAL DISTRICT) RETAIL & WHOLESALE OF GOODS, PREPARED FOODS, AND SERVICES IS A PERMITTED USE WITHIN THIS ZONING DISTRICT.

ZONING INFORMATION WAS OBTAINED FROM: BOROUGH OF SAINT CLAIR 16 SOUTH THIRD STREET SAINT CLAIR, PA 17970 (570) 429-0640 ROLAND PRICE

DESCRIPTION	REQUIRED	PROPOSED
MINIMUM LOT AREA	10,000 SF	37,581 SF (TOTAL)
MINIMUM LOT WIDTH	50'	220.83'
MINIMUM FRONT YARD SETBACK	20'-0"	83'-4"
MINIMUM SIDE YARD SETBACK	10'-0" EACH SIDE	25'-1"
MINIMUM REAR YARD SETBACK	20'-0"	N/A
MINIMUM PAVED AREA SETBACK	10'-0" ARTERIAL OR COLLECTOR <2 ACRES	4'-11" MIN. 14'-0" MAX.
MAXIMUM BUILDING HEIGHT	35'-0" OR 2.5 STORIES	19'-0"
MAXIMUM BUILDING COVERAGE	35%	N/A
MAXIMUM IMPERVIOUS COVERAGE	35%	N/A
MINIMUM SIGN SETBACK	50% OF FRONT YARD SETBACK = 10'-0"	12'-8"

TOWNSHIP OF EAST NORWEGIAN ZONING DISTRICT: C-3 (HIGHWAY COMMERCIAL DISTRICT) A RETAIL STORE IS A PERMITTED USE WITHIN THIS ZONING DISTRICT.

ZONING INFORMATION WAS OBTAINED FROM: SCHUYLKILL COUNTY PLANNING & ZONING DEPT. 401 NORTH SECOND STREET POTTSVILLE, PA 17901 (570) 628-1416 **ZONING OFFICER**

DESCRIPTION	REQUIRED	PROPOSED
MINIMUM LOT AREA	10,000 SF	37,581 SF (TOTAL)
MINIMUM LOT WIDTH	75'-0"	220.83'
MINIMUM FRONT YARD SETBACK	35'-0"	80'-2"
MINIMUM SIDE YARD SETBACK	25'-0"	25'-1"
MINIMUM REAR YARD SETBACK	25'-0"	N/A
MINIMUM PAVED AREA SETBACK	10'-0" (20-99 PARKING SPACES)	2'-9" MIN. 7'-7" MAX.
MAXIMUM BUILDING HEIGHT	100'-0"	19'-0"
MAXIMUM BUILDING COVERAGE	60%	19.6%
MAXIMUM IMPERVIOUS COVERAGE	90%	70.8%
MINIMUM SIGN SETBACK	25'-0"	N/A

KEYNOTES

- 4 ASPHALT PAVING SEE DETAILS 2 & 4/C1.A.
- SPACING FOR CONTROL JOINTS IS 15' O.C. EACH WAY.
- G.C. TO PROVIDE ALTERNATE BID FOR CONCRETE PAVING, WHERE NOTED WHERE NOTED.

- (11) BOLLARD PLAN SEE DETAIL 9/C1.A.
- (13) 4" WIDE PARKING STRIPE PAINTED WHITE (TYP.).
- ACCESSIBLE PARKING SIGN SEE DETAIL 8/C1.A. G.C. TO
- CONCRETE SIDEWALK SEE DETAILS 19 & 25/C1.A FOR SIDEWALKS AROUND BUILDING.
- TO BE A CONTRASTING COLOR.

- GRATE FLUSH TO NEW SIDEWALK, FOR ACCESS, IF REQUIRED.
- NEW CONCRETE DEPRESSED CURB, PER PennDOT SPECIFICATIONS. NEW PROPANE TANK ON CONCRETE PAD FOR GAS SERVICE TO

- "STOP" SIGN (K1-1) MODINIES OF PER PennDOT SPECIFICATIONS.


REVISIONS 1 11-30-21 PER BOROUGH & COUNTY COMMEN

SCALE: 1" = 20'-0"

ARCHITECT: LE

DRAFTSMAN: CWT CHECKED BY: CAD





South Front Street, 3rd Floor phis, Tennessee 38103 901) 495-8709 Fax: (901) 495-8969 idding & Contractor Information Contact: Dodge Plan Room Tel: (615) 884-1017

Auto 123 South Memphis, Tel: (901) For Biddir F.W. Dode

UGH OF ST. CLAIR

Store No.: 2800

Store No.: 2800

489 POTTSVILLE ST. CLAIR HIGHWAY

TOWNSHIP OF EAST NORWEGIAN & BOROUG

SCALE: AS NOTED

REVISIONS

1. 11-30-21 PER BOROUGH & COUNTY COMMENT

1-30-21 COUNTY COMMENTS


ARCHITECT: LE
DRAFTSMAN: CWT
CHECKED BY: CAD

DATE 6-25-2021 PROTOTYPE SIZE

PROTOTYPE SIZE
7n2-R




C1.A
SHEET 4 of 16



GRADING & DRAINAGE NOTES

- 1. SEE SITE PLAN FOR ADDITIONAL GENERAL NOTES.
- 2. ALL SITE WORK, MATERIALS OF CONSTRUCTION, AND CONSTRUCTION METHODS SHALL COMPLY WITH LOCAL MUNICIPALITY, LOCAL COUNTY, AND DEPARTMENT OF TRANSPORTATION MATERIAL AND CONSTRUCTION SPECIFICATIONS.
- 3. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES, INCLUDING SERVICES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONTACT THE PA ONE CALL SYSTEM AT 1-800-242-1776 AT LEAST THREE (3) WORKING DAYS BEFORE START OF WORK AND VERIFY ALL EXISTING UTILITY LOCATIONS.
- 4. ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER ACCURATE METHOD.
- 5. THE CONTRACTOR SHALL COMPACT PIPE BACKFILL IN MAX. 8" LOOSE LIFTS TO 95% OF THE MAXIMUM DRY DENSITY PER ASTM D1557, ACCORDING TO THE PIPE BEDDING DETAILS. TRENCH BOTTOM SHALL BE STABLE IN HIGH GROUNDWATER AREAS. A PIPE FOUNDATION SHALL BE USED IN AREAS OF ROCK EXCAVATION.
- 6. CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC., AS REQUIRED FOR PIPE CONNECTIONS TO BUILDING/CANOPY STUB-OUTS, INCLUDING ROOF/FOOTING DRAIN CONNECTIONS TO ROOF LEADERS AND TO STORM
- DRAINAGE SYSTEM.TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING.
- 8. MANHOLE RIMS AND STORM INLET GRATES SHALL BE SET TO ELEVATIONS SHOWN. SET ALL EXISTING MANHOLE FRAMES AND COVERS, STORM INLET GRATES, VALVE BOXES, ETC., TO BE RAISED OR LOWERED, TO PROPOSED FINISHED GRADE, FLUSH WITH THE ADJACENT GRADE.
- 9. UNDERDRAINS MAY BE ADDED, IF DETERMINED NECESSARY BY THE ENGINEER OR CONSTRUCTION MANAGER, AFTER SUBGRADE IS ROUGH GRADED.
- 10. ALL EXISTING TOPOGRAPHICAL FEATURES (SPOT ELEVATIONS, CONTOURS, INVERTS, ETC.) CAN HAVE A TOLERANCE DIFFERENCE OF 6"± DEPENDING ON FIELD CONDITIONS AT THE TIME OF THE FIELD SURVEY. CONTRACTOR TO VERIFY ALL EXISTING TOPOGRAPHICAL FEATURES PRIOR TO CONSTRUCTION, AND ADVISE OWNER OF ANY DISCREPANCIES.
- 11. THE CONTRACTOR SHALL RESTORE ANY STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS, ETC. DISTURBED DURING CONSTRUCTION TO THE ORIGINAL CONDITION OR BETTER.
- 12. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF MATERIALS AND STRUCTURES TO THE CONSTRUCTION MANAGER FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
- 13. THE CONTRACTOR SHALL PRESERVE EXISTING VEGETATION WHERE POSSIBLE AND/OR AS NOTED ON DRAWINGS. REFER TO EROSION AND SEDIMENTATION PLAN FOR LIMIT OF DISTURBANCE AND NOTES.
- 14. THE CONTRACTOR SHALL COMPACT FILL IN 8" MAXIMUM LIFTS UNDER ALL PARKING, BUILDING, AND DRIVE AREAS TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D1557 (MODIFIED PROCTOR TEST), OR AS DIRECTED BY THE GEOTECHNICAL ENGINEER.
- 15. THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL AND DISPOSAL OF ALL RUBBISH, TRASH, DEBRIS, AND ORGANIC MATERIAL IN A LAWFUL MANNER.
- 16. THE CONTRACTOR SHALL BE ADVISED THAT ALL EXCAVATION IS CONSIDERED UNCLASSIFIED AND THAT IT SHALL BE RESPONSIBLE FOR ALL MEANS, METHODS, AND MATERIALS OF CONSTRUCTION TO COMPLETE CONSTRUCTION AS DESIGNED. ADDITIONALLY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OFF-SITE DISPOSAL OF ANY AND ALL EXCESS OR UNSUITABLE MATERIAL UNABLE TO BE PLACED ON SITE AND THE IMPORTATION OF ANY BORROW MATERIAL NECESSARY TO COMPLETE THE JOB.
- 17. ALL EXCAVATION AND GRADING CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEERING REPORT.
- 18. SITE GRADING SHALL BE PERFORMED TO PROVIDE POSITIVE DRAINAGE TO STORM INLETS AND TO PRECLUDE THE PONDING OF WATER ON SITE.
- 19. VERIFY REQUIRED SPOT ELEVATIONS/GRADING IN THE VICINITY OF THE BUILDINGS WITH THE ARCHITECTURAL PLANS.
- 20. ALL ACCESSIBLE PARKING SPACES TO HAVE A MAXIMUM SLOPE OF 2% IN ANY
- 21. ALL SIDEWALKS, PATIO AREAS, AND ACCESSIBLE ROUTES TO THE BUILDING ARE TO HAVE A MAXIMUM CROSS SLOPE OF 2%, AND A MAXIMUM LONGITUDINAL SLOPE OF 5%.
- 22. CONTRACTOR TO FIELD VERIFY PROPOSED AND EXISTING GRADES, SLOPES, ETC., FOR PROPOSED ACCESSIBLE PARKING AREAS, RAMPS, ETC., WITH ARCHITECT, PRIOR TO CONSTRUCTION.
- 23. LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE TAKEN FROM FIELD OBSERVATION, UTILITY MAPS, ETC., AND ARE NOT ASSUMED TO BE ACCURATE. PRIOR TO ANY CONSTRUCTION ACTIVITIES, CONTRACTOR TO DIG TEST PITS AT ALL PROPOSED UTILITY CROSSINGS, TO VERIFY LOCATION, DEPTH, SIZE, ETC. OF EXISTING UNDERGROUND UTILITIES, AND CONFIRM NEW UTILITY LINES CAN BE INSTALLED AS PROPOSED. ADVISE CONSTRUCTION MANAGER IMMEDIATELY OF ANY CONFLICTS OR DISCREPANCIES.
- 24. INSTALL PERFORATED FINGER DRAINS AT INLETS, PER GEOTECHNICAL REPORT RECOMMENDATIONS. SEE DETAIL ON SHEET C1.1.



lopment, LL

Journal Developiner

Journal Street, 3rd Floor

his, Tennessee 38103

101) 495-8709 Fax: (901) 495-8969

dding & Contractor Information Contractor

AUTC 123 So Memph Tel: (90 For Bid

OUGH OF ST. CLAIR
TH OF PENNSYLVANIA

TTSVILLE ST. CLAIR HIGHWAY SHIP OF EAST NORWEGIAN & Y OF SCHUYLKILL, COMMONY

> 489 PC 489 PC TOWN COUN

SCALE: 1" = 20'-0"

REVISIONS

1. 11-30-21 PER BOROUGH & COUNTY COMMEN

2. 3. 4. 5. 6. 7

ARCHITECT: LE

DRAFTSMAN: CWT


CHECKED BY: CAD

DATE
6-25-2021
PROTOTYPE SIZE

PROTOTYPE SIZE 7n2-R



C1.1
SHEET 5 of 15



SCALE: 1" = 20'-0"

REVISIONS 1 11-30-21 PER BOROUGH & COUNTY COMMENT

ARCHITECT: LE DRAFTSMAN: CWT

CHECKED BY: CAD

6-25-2021 PROTOTYPE SIZE

7n2-R



SHEET 6 of 16

EUGENE S. DVORCHAK, PE, PA LIC. No. PE052940E

THE OVERALL SITE-WORK GENERALLY CONSISTS OF EARTHMOVING ACTIVITIES FOR APPROXIMATELY 1.000± ACRES OF DISTURBED AREA TO PERFORM THE Proposed grading and construction for the project. It is proposed to approximately proceed with the project in the following sequence:

- STAKE OUT THE LIMIT OF DISTURBANCE (LOD) FOR THE ACTIVE PORTION OF THE PROJECT. FLAG THE LOD PRIOR TO ANY EARTH DISTURBANCE.
- INSTALL ALL COMPOST FILTER SOCKS (SILTSOXX™) PERIMETER PROTECTION AS SHOWN ON THE EROSION AND SEDIMENTATION CONTROL PLAN
- CLEAR AREA FOR ROCK CONSTRUCTION ENTRANCE AND CONSTRUCT TEMPORARY ROCK CONSTRUCTION ENTRANCE ALONG POTTSVILLE ST. CLAIR HIGHWAY, AS SHOWN ON THE PLAN. ANN STREET DRIVEWAY IS NOT TO BE USED AS A CONSTRUCTION ENTRANCE.
- CLEAR AND GRUB WORK AREA WITHIN THE IDENTIFIED LIMITS OF DISTURBANCE.
- PROCEED WITH DEMOLITION OF SITE IMPROVEMENTS NOT TO REMAIN FOR THE ACTIVE PORTION OF THE PROJECT
- STRIP AND STOCKPILE SPOIL MATERIAL IN LOCATION IDENTIFIED ON THE EROSION AND SEDIMENTATION CONTROL PLAN. PLACE PERIMETER PROTECTION ON DOWNSLOPE SIDE OF THE SPOIL STOCKPILE AND COMPLETE PLACEMENT OF COMPOST FILTER SOCKS (SILTSOXX™) PROTECTING THE STOCKPILE AREA IMMEDIATELY AFTER STOCKPILING MATERIAL. PROVIDE ANY ADDITIONAL EROSION AND SEDIMENTATION CONTROL AS NEEDED.
- PROCEED WITH GRADING OPERATIONS. GRADED SLOPES SHOULD BE SEEDED AND MULCHED, AS SOON AS PRACTICAL, IN REGULAR, 10-FOOT VERTICAL INCREMENTS. EROSION CONTROL BLANKETS (ECB) MUST BE INSTALLED ON SLOPES AS SOON AS THE SLOPE IS AT GRADE. CESSATION OF ACTIVITY FOR FOLIR (4) DAYS OR LONGER REQUIRES STABILIZATION. IN NO CASE SHOULD AN AREA EXCEPTING 15,000 SE, WHICH IS TO BE STABILIZED BY VEGETATION REACH FINAL GRADE WITHOUT BEING SEEDED AND MULCHED

PLACE STONE SUBBASE FOR AREAS TO BE PAVED.

- CONSTRUCT STORMWATER CONVEYANCE SYSTEMS. LIMIT DAILY TRENCH EXCAVATION AND STORM LINE INSTALLATION TO THE LENGTH OF PIPE PLACEMENT, BEDDING, AND BACKFILLING THAT CAN BE COMPLETED THE SAME DAY (WEATHER PERMITTING), NOTE THAT ALL STORM LINES MUST BE INSTALLED FROM DOWNSTREAM TO UPSTREAM. IF REQUIRED, TRENCH PLUGS AS PER DETAIL ARE TO BE INSTALLED PER PADEP CHAPTER 102 REQUIREMENTS. IMPORTANT: STORMWATER RUNOFF IS NOT TO BE DIRECTED TO UNPROTECTED STORMWATER CONVEYANCE SYSTEMS UNTIL THE
- PLACE INLET PROTECTION ON ALL INSTALLED ONSITE INLETS WITHIN THE WORK LIMITS. IMPORTANT: STORMWATER RUNOFF IS NOT TO BE DIRECTED
- TO UNPROTECTED STORMWATER CONVEYANCE SYSTEMS UNTIL THE SITE IS AT FINAL GRADE AND STABILIZED BRING SITE TO FINAL GRADE AND PAVE ALL PARKING AREAS AND ACCESS DRIVES RECEIVING INITIAL PAVING. ALL REMAINING AREAS SHALL RECEIVE
- TEMPORARY OR PERMANENT SEEDING OR LANDSCAPING IMPROVEMENTS. . UTILITIES SERVICING THE SITE THAT ARE WITHIN THE DEVELOPMENT AREA CAN BE CONSTRUCTED WITHIN THE LOCATION THEY ARE TO BE INSTALLED
- . STRUCTURAL AND BUILDING CONSTRUCTION MAY COMMENCE AFTER AREAS REACH FINAL GRADE ELEVATION.
- . BRING THE SITE TO FINAL GRADE AND PAVE REMAINING PARKING AREAS AND ACCESS DRIVES. ALL REMAINING AREAS THAT WILL NOT RECEIVE LANDSCAPING IMPROVEMENTS SHALL RECEIVE PERMANENT SEEDING AND ALL SEEDED AREAS ARE TO BE MULCHED.
- AFTER MINIMUM UNIFORM 70% PERFUNIAL VEGETATIVE COVER STABILIZATION IS ACHIEVED. TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING THE REMOVAL OF THE CONTROLS MUST BE IMMEDIATELY STABILIZED. FINAL STABILIZATION IS DEFINED AS THE ACHIEVEMENT OF A MINIMUM 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES ON ALL CONTRIBUTORY

CONSTRUCTION SEQUENCE NOTES:

IN ADDITION TO THE PERMIT APPLICANT, ANYONE PERFORMING ACTIVITIES RESULTING IN ANY EARTH DISTURBANCE IS REQUIRED TO BE ADDED TO THE NPDES PERMIT AS A CO-PERMITTEE. ALL PARTIES RESPONSIBLE FOR THE EXCAVATION OF SITE MATERIALS OR THE IMPORT OF FILL MATERIALS ARE RESPONSIBLE TO ENSURE THAT "ENVIRONMENTAL DUE DILIGENCE" IN THE DETERMINATION OF CLEAN FILL MATERIAL IS EITHER REMOVED FROM THE SITE OR USED AS FILL FOR THE SITE. ANY MATERIAL IDENTIFIED AS HAZARDOUS MUST BE DISPOSED IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL GUIDELINES AND

- A. ENVIRONMENTAL DUE DILIGENCE INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, LECTRONIC DATA BASE SEARCHES, REVIEW OF OWNERSHIP AND USE HISTORY OF PROPERTY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS.
- NO BUILDING MATERIALS, WASTES, OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED OR DISCHARGED AT THE SITE. THE FOLLOWING DEFINE WHAT SHOULD BE CONSIDERED "CONSTRUCTION WASTE" AND "CLEAN FILL A. CONSTRUCTION WASTE - INCLUDES BUT IS NOT LIMITED TO, EXCESS SOIL MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER,
- SANITARY WASTES, ETC. THAT COULD ADVERSELY IMPACT WATER QUALITY. B. CLEAN FILL - UNCONTAMINATED, NON-WATER-SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THIS INCLUDES SOIL ROCK STONE REDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK, OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. IT DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE SURFACE WATERS UNLESS OTHERWISE AUTHORIZED, MILLED ASPHALT, OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.
- COMPOST FILTER SOCKS (FILTREXX SILTSOXX™) AND ANY OTHER FILTREXX BMPS EMPLOYED AS PART OF THE EROSION AND SEDIMENTATION CONTROL PLAN FOR THE PROJECT MUST FOLLOW THE MANUFACTURER'S DISPOSAL/RECYCLING INSTRUCTIONS FOR EACH SPECIFIC BMP UTILIZED THROUGHOUT THE PROJECT'S CONSTRUCTION AND EARTHMOVING OPERATIONS. EROSION AND SEDIMENTATION CONTROLS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE WITHIN THE
- CONTRIBUTORY DRAINAGE AREAS OF THOSE CONTROLS . AFTER FINAL SITE STABILIZATION IS ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS MUST BE IMMEDIATELY STABILIZED. FINAL STABILIZATION IS DEFINED AS THE ACHIEVEMENT OF A MINIMUM LINIFORM
- 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES HAS BEEN ACHIEVED ON ALL CONTRIBUTORY DRAINAGE AREAS. ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 4 DAYS MUST BE TEMPORARILY STABILIZED. DISTURBED AREAS THAT ARE EITHER AT FINISHED GRADE, OR ANY GRADED AREA OF 15,000 FT2 OR MORE REACHES FINAL GRADE, OR WILL NOT BE DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

PA DEP STANDARD E&S PLAN NOTES

ALL EARTH DISTURBANCES. INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION. AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES. INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED

PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL

- CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING. AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA
- ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES. ALL FARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SECUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT
- SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE
- CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS
- SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN. AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN MAP(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR
- IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION
- . ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET. SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED
- BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED.

AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT.

- . THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO
- 3. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED
- EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEANOUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED

. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL

- 5. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION. THE INSPECTIONS AND MAINTENANCE DATA SHALL BE LOGGED ONTO THE DEPARTMENT FORM 3150-FM-BWEW0083 (MOST CURRENT VERSION TO BE USED).
- . SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH,
- STORM SEWER, OR SURFACE WATER. . ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS.
- 3. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES 6 TO 12 INCHES ON COMPACTED SOILS PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL
- 9. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDING, STRUCTURES, AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES. 0. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN THICKNESS.
- 1. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE
- WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS.
- 2. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.
- 24. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED METHOD.
- 5. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.
- 5. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS

PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER

- WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
- 8. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT. 9. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS. THE OWNER AND/OR OPERATOR
- SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS.). AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE
- . UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION.
- . FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND OR/CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES

CONCRETE WASH WATER SHALL BE HANDLED IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. IN NO CASE SHALL IT BE ALLOWED TO ENTER ANY SURFACE WATERS OR GROUNDWATER SYSTEMS

EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS.

GENERAL SEEDING SPECIFICATIONS

THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION RECOMMENDS LISING THE PENN STATE "EROSION CONTROL AND CONSERVATION PLANTINGS ON NONCROPLAND" MANUAL AS A REFERENCE FOR SELECTION OF SPECIES, SEED SPECIFICATIONS, MIXTURES, LIMING AND ERTILIZING, TIME OF SEEDING, AND SEEDING METHODS. SPECIFICATIONS FOR THESE ITEMS MAY ALSO BE OBTAINED FROM THE PENNSYLVANIA DEPARTMENT OF TRANSPORTATION PUBLICATION 408, SECTION 804 OR BY CONTACTING THE APPLICABLE COUNTY CONSERVATION

VEGETATED AREAS WILL BE CONSIDERED PERMANENTLY STABILIZED WHEN A UNIFORM 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES IS ACHIEVED, OR THE DISTURBED AREA IS COVERED WITH AN ACCEPTABLE BEST MANAGEMENT PRACTICE ("BMP") VHICH PERMANENTLY MINIMIZES ACCELERATED EROSION AND SEDIMENTATION. UNTIL SUCH TIME AS THIS STANDARD IS ACHIEVED. INTERIM STABILIZATION MEASURES AND TEMPORARY EROSION AND SEDIMENT CONTROL BMPs THAT ARE USED TO TREAT PROJECT RUNOFF MAY NOT BE REMOVED.

TEMPORARY SEEDING SPECIFICATIONS

PRELIMINARY PREPARATION: ALL AREAS THAT WILL BE SEFDED MUST BE LOOSENED LISTING MECHANICAL MEANS. SOIL MUST BE LOOSENED TO A DEPTH OF AT LEAST TWO-INCHES.

IME AND FERTILIZER: APPLY 1 TON OF AGRICULTURAL GRADE LIMESTONE PER ACRE AND RTILIZER AS INDICATED BY THE SOIL TEST. IN THE ABSENCE OF A SOIL TEST, APPLY AGRICULTURAL GRADE LIMESTONE AT A RATE OF 1 TON PER ACRE, AND APPLY FERTILIZER AT 500 POUNDS OF 10-10-10 FERTILIZER PER ACRE (F.G., 166.67 POUNDS NITROGEN (N), 166.67 POLINDS PHOSPHOROUS (P.O.) AND 166 67 POLINDS POTASSTUM (K.O.) PER ACRE WORK LIME AND FERTILIZER INTO SOIL WHERE POSSIBLE. LIME AND FERTILIZER DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP)

SED: ALL SEED MUST BEAR A GUARANTEED STATEMENT OF ANALYSIS AND MUST BE ROPORTIONED BY WEIGHT WITH THE MINIMUM PURITY, READY GERMINATION, AND TOTAL GERMINATION OUTLINED BELOW. SEED DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.3 AND 11.4.

SPECIES	PURITY (%)	READY GERMINATION (%)	TOTAL GERMINATION (%)	PURE LIVE SEED ¹ SEEDING RATE (LBS/ACRE)	
SPRING-SUMMER					С
SPRING OATS, OR	98	85	85	64	(5
ANNUAL RYEGRASS	95	85	85	10	
SUMMER-FALL					IN
ANNUAL RYEGRASS, OR	95	85	85	10	FI FI
WINTER RYE, OR	98	85	85	56	1
WINTER WHEAT	98	85	85	90	1
1- PURE LIVE SEED (PLS) IS THE PERCENTAGE GERMINATION DIVI PLANTING RATE FOR ANNUAL RYI THE PLS AS SHOWN ON THE SEEI	IDED BY 10 EGRASS, D	00. FOR EXAMPLE, IVIDE THE PLS SE	, TO SECURE THE EDING RATE OF 1	ACTUAL 0 LBS/ACRE BY	

PERMANENT SEEDING SPECIFICATIONS

LOPE PARALLEL TO AND SIX INCHES BELOW FINISH GRADE (I.E., 8 INCHES FOR BASIN MBANKMENTS WHEN APPLICABLE). PLACE TOPSOIL OVER SPECIFIED AREAS. TOPSOIL SHOULD BE AT A GREATER THICKNESS (I.E., GENERALLY 6 TO 8 INCHES) THAN THE FINISHED GRADE TO ALLOW FOR SETTLEMENT AND LIGHT ROLLING. THE FINAL COVER MUST CONFORM TO THE PROPOSED LINES, GRADES AND ELEVATIONS.

IME AND FERTILIZER: APPLY AGRICULTURAL-GRADE LIMESTONE AND FERTILIZER AS PER THE COMMENDATIONS INDICATED BY THE SOIL TEST. IN THE ABSENCE OF A SOIL TEST, APPLY AGRICULTURAL GRADE LIMESTONE AT A RATE OF 6 TONS PER ACRE, AND APPLY 1,000 POUNDS OF | IN ADDITION TO THE PERMIT APPLICANT, ANYONE PERFORMING ACTIVITIES RESULTING IN ANY EARTH DISTURBANCE IS REQUIRED TO BE ADDED TO THE NPDES 10-20-20 FERTILIZER (E.G., 200 POUNDS NITROGEN (N), 400 POUNDS PHOSPHORUS (P₂O_E), AND 400 POUNDS POTASSIUM (K₂O) PER ACRE.) WORK LIME AND FERTILIZER INTO SOIL WHERE POSSIBLE LIME AND FERTILIZER DATA WAS OBTAINED FROM THE PADEP FROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLE 11.2. NOTE: A COMPOST BLANKET WHICH MEETS THE STANDARDS OF CHAPTER 11 OF THE PADEP EROSION *ND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL MARCH 2012* (BMP MANUAL) MAY BE JBSTITUTED FOR THE SOIL AMENDMENTS SHOWN IN TABLE 11.2.

THE FERTILIZER AND LIMESTONE MUST BE THOROUGHLY INCORPORATED INTO THE SOIL BY MECHANICAL MEANS (E.G., ROTOTILLING) TO A MINIMUM DEPTH OF 4 INCHES.

THE ENTIRE SURFACE MUST THEN BE REGRADED AND ROLLED. ALL AREAS THAT WILL BE SEEDEL MUST BE LOOSENED USING MECHANICAL MEANS. SOIL MUST BE LOOSENED TO A DEPTH OF AT LEAST TWO INCHES.

D: SEEDING MUST BE CONDUCTED AS TWO SEPARATE OPERATIONS. THE FIRST SEEDING

OPERATION MUST BE COMPLETED PRIOR TO STARTING THE SECOND SEEDING OPERATION. THE SECOND SEEDING MUST BE CONDUCTED IMMEDIATELY AFTER THE FIRST SEEDING AND AT RIGHT ANGLES TO THE FIRST SEEDING. THE SEEDS MUST BE LIGHTLY RAKED INTO THE SOIL.

BY WEIGHT WITH THE MINIMUM PURITY, READY GERMINATION, AND TOTAL GERMINATION DUTLINED BELOW. SEED DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT ONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.3 AND 11.4.

SPECIES	(%)	GERMINATION (%)	GERMINATION (%)	SEEDING RATE (LBS/ACRE)
SPRING-SUMMER				
REDTOP	92	80	80	3
TALL RYEGRASS ²	95	80	80	60
ANNUAL RYEGRASS	95	85	85	10
SUMMER-FALL				
REDTOP	92	80	80	3
TALL FESCUE ²	95	80	80	60
WINTER RYE	98	85	85	56

1- PLIRE LIVE SEED (PLS) IS THE PRODUCT OF THE PERCENTAGE OF PLIRE SEED TIMES. PERCENTAGE GERMINATION DIVIDED BY 100. FOR EXAMPLE, TO SECURE THE ACTUAL PLANTING RATE FOR REDTOP, DIVIDE THE PLS SEEDING RATE OF 3 LBS/ACRE BY THE PLS SHOWN ON THE SEED TAG. THUS, IF THE PLS CONTENT OF A GIVEN SEEDLOT IS 60%, DIVIDE 3 PLS BY 0.60 TO OBTAIN 5.0 LBS OF SEED REQUIRED TO PLANT ONE ACRE. ALL MIXTURES IN THIS TABLE ARE SHOWN IN TERMS OF PLS, LBS/ACRE.

2- USE KENTUCKY 31 TALL FESCUE FOR LOW MAINTENANCE SITES OR TURF-TYPE TALL FESCUE FOR HIGH MAINTENANCE SITES.

MULCH: ALL SEEDED AREAS MUST BE IMMEDIATELY MULCHED TO PROMOTE ADEQUATE /EGETATIVE COVER. USE CLEAN OAT OR WHEAT STRAW, FREE OF WEEDS, NOT CHOPPED OR FINELY BROKEN. THE STRAW MUST BE FREE FROM MATURE SEED-BEARING STALKS OR ROOTS OF ROHIBITED OR NOXIOUS WEEDS AS DEFINED BY THE PENNSYLVANIA SEED ACT OF 1947.

APPLY MULCH AT A RATE OF 3 TONS PER ACRE (I.E., 140 POUNDS PER 1,000 SOUARE FEET OR ,240 POUNDS PER 1,000 SQUARE YARDS). THE MULCH MUST BE ANCHORED IMMEDIATELY AFTER APPLICATION. A TRACTOR-DRAWN IMPLEMENT MAY BE USED TO ANCHOR THE MULCH INTO THE SOIL. THIS METHOD IS LIMITED TO SLOPES SHALLOWER THAN OR EQUAL TO 3:1 AND THE EOUIPMENT MUST BE OPERATED ON THE CONTOUR.

STEEP SLOPE SEEDING SPECIFICATIONS

TEEP SLOPE SEEDING MIXTURE (FOR USE ON GRADES AT 3:1 OR GREATER SLOPES): ALL SLOPES REATER THAN 3:1 SHALL BE COVERED WITH AN EROSION CONTROL BLANKET IN ADDITION TO RECEIVING A GRASS SEEDING MIXTURE.

VHEN CONDITIONS PERMIT. THE FOLLOWING SEEDING MIXTURE CAN BE UTILIZED ON STEEP SLOPES. SEED DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.4 AND 11.5.

SPECIES	PURITY (%)	READY GERMINATION (%)	TOTAL GERMINATION (%)	PURE LIVE SEED ¹ SEEDING RATE (LBS/ACRE)
ANNUAL RYEGRASS	95	85	85	10
BIRDSFOOT TREFOIL	98	60	80	6
TALL FECUE	95	80	80	30

- PURE LIVE SEED (PLS) IS THE PRODUCT OF THE PERCENTAGE OF PURE SEED TIMES PERCENTAGE GERMINATION DIVIDED BY 100. FOR EXAMPLE, TO SECURE THE ACTUAL PLANTING RATE FOR ANNUAL RYEGRASS, DIVIDE THE PLS SEEDING RATE OF 10 LBS/ACRE B THE PLS AS SHOWN ON THE SEED TAG. THUS, IF THE PLS CONTENT OF A GIVEN SEEDLOT IS 60%. DIVIDE 10 PLS (LBS/ACRE) BY 0.60 TO OBTAIN 16.7 LBS OF SEED REQUIRED TO PLANT

ONE ACRE. ALL MIXTURES IN THIS TABLE ARE SHOWN IN TERMS OF PLS, LBS/ACRE.

MAINTENANCE PROGRAM

MAINTAIN TEMPORARY CONTROL MEASURES THROUGHOUT THE PROJECT PERIOD AS OUTLINED IN THE "MAINTENANCE SCHEDULE" SHOWN ON THE EROSION AND SEDIMENTATION CONTROL PLANS AND NARRATIVE.

T SHALL BE THE RESPONSIBILITY OF THE PERMITTEE TO PERFORM INSPECTIONS OF ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL MEASURES TO ENSURE THAT THEY ARE WORKING PROPERLY. THESE INSPECTIONS MUST BE CONDUCTED WEEKLY, AND DURING OR IMMEDIATELY AFTER EVERY RUNOFF EVENT. INSPECTIONS WILL BE LOGGED ONTO DEPARTMENT FORM 3150-FMBWEW0083 (MOST RECENT VERSION) AND WILL BE KEPT ON SITE AT ALL TIMES. THE INSPECTION WILL INCLUDE, BUT NOT BE LIMITED TO

1) INSPECT ALL CONTROLS (INCLUDING COMPOST FILTER SOCKS) AND REPAIR OR REPLACE AS NEEDED. 2) INSPECT ALL SLOPES FOR SIGNS OF EROSION AND/OR SEDIMENTATION, AND REPAIR AS NEEDED.

3) INSPECTION OF ALL SEEDED AREAS FOR SIGNS OF EROSION. $m \acute{t}$) inspection of all inlet protection until the contributory drainage area to the corresponding inlet is stabilized. 5) THE CLEANING AND REPAIR OF THE ROCK CONSTRUCTION ENTRANCE.

REPAIRS AND MAINTENANCE FOR ANY EROSION AND SEDIMENTATION CONTROL DEVICES MUST BE PERFORMED AS SOON AS THE OPERATIONS CAN BE SAFELY AND PRACTICALLY CARRIED OUT.

AN ADEQUATE SUPPLY OF ADDITIONAL EROSION/SEDIMENTATION CONTROL MATERIALS (E.G., STRAW BALES, EROSION NETTING, PLASTIC COVERING, WIRE MESH, SAND AND BURLAP, SANDBAGS, ROCKS AND GRAVEL) MUST BE STOCKPILED ON-SITE. THESE SUPPLIES MUST BE USED FOR EMERGENCY REPAIRS TO/OR REPAIRS OF EXISTING SOIL EROSION AND SEDIMENTATION CONTROLS.

MAINTENANCE OF PERMANENT CONTROLS THE OWNER/DEVELOPER WILL MAINTAIN PERMANENT CONTROL FACILITIES.

EANING FREQUENCIES ARE SPECIFIED WITHIN THE MAINTENANCE SCHEDULE. SILT AND SEDIMENT REMOVED FROM ALL CONTROL MEASURES SHOULD BE MIXED WITH SOIL DURING EARTHWORK AND PROPERLY DISPOSED OF ON-SITE.

ON-SITE SEDIMENT CONTROL PLAN MAINTENANCE SCHEDULE CONTROL MEASURE WITHIN 24 HOURS OR AS SOON AS SAFELY PRACTICAL.)

SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.3 AND 11.4.					T			
READY TOTAL PURE LIVE SEED ¹		VEGETATION	ONCE A WEEK AND AFTER	SEDIMENT AT TOE OF SLOPE	CHECK FOR TOE OF SLOPE DIVERSION AND INSTALL IF NEEDED.			
SPECIES	PURITY	READY GERMINATION	TOTAL GERMINATION	SEEDING RATE		EVERY RUNOFF EVENT	RILLS AND GULLIES FORMING	FILL RILLS AND REGRADE GULLIED SLOPES.
Si ECIES	(%)	(%)	(%)	(LBS/ACRE)			BARE SOIL PATCHES	RESEED, FERTILIZE AND MULCH BARE AREAS.
SPRING-SUMMER			COMPOST FILTER SOCK	ONCE A WEEK AND AFTER EVERY RUNOFF EVENT	RUNOFF ESCAPING AROUND BARRIER	SECURELY ANCHOR WITH PROPER STAPLES. EXTEND BARRIER AS NEEDED.		
SPRING OATS, OR	98	85	85	64	(SILTSOXX [™])	EVERT RONOTT EVERT	SEDIMENT LEVEL BUILDUP	REMOVE SEDIMENT WHEN LEVEL REACHES HALF (1/2) THE HEIGHT OF THE
ANNUAL RYEGRASS	ASS 95 85 85 10		10	1		SEDIMENT LEVEL BUILDOP	BARRIER.	
SUMMER-FALL					INLET PROTECTION -	ONCE A WEEK AND AFTER	SEDIMENT BUILD-UP	REMOVE ACCUMULATED SEDIMENT, IF FLOW CAPACITY IS STILL REDUCED OR
ANNUAL RYEGRASS, OR	95	85	85	10	FOR BLACKHAWK INLET FILTER MAT	EVERY RUNOFF EVENT	REDUCING FLOW CAPACITY RESULTING IN FLOODING	MAT REMAINS COMPRESSED, REPLACEMENT OF FILTER MAT IS REQUIRED.
WINTER RYE, OR	98	85	85	56			AROUND OR BELOW INLET -OR- COMPRESSION OF	
WINTER WHEAT	WINTER WHEAT 98 85		85	90			FILTER MAT	
1. DUDE LIVE CEED (DLC) IC THE DODUKT OF THE DEDCEMBACE OF DUDE CEED TIMES						MISSING MATERIAL	REPAIR OR REPLACE PROTECTION MATERIALS AS NEEDED.	
1- PURE LIVE SEED (PLS) IS THE PRODUCT OF THE PERCENTAGE OF PURE SEED TIMES PERCENTAGE GERMINATION DIVIDED BY 100. FOR EXAMPLE, TO SECURE THE ACTUAL PLANTING RATE FOR ANNUAL RYEGRASS, DIVIDE THE PLS SEEDING RATE OF 10 LBS/ACRE BY							GENERAL MAINTENANCE	AS NEEDED, INLET FILTER MATS SHALL BE LIFTED AND RINSED OR REPLACED IF DAMAGED.
THE PLS AS SHOWN ON THE SEE 60%, DIVIDE 10 PLS (LBS/ACRE)	D TAG. TH BY 0.60 TO	IUS, IF THE PLS CO O OBTAIN 16.7 LBS	ONTENT OF A GIV S OF SEED REQUIF	EN SEEDLOT IS RED TO PLANT	("SILT SACK" - ONLY)		WATER BY-PASSING INLET AND GRATE	REMOVE "SILT SACK" AND REMOVE SILT OR REPLACE WITH NEW "SILT SACK" OR INSTALL BLOCK AND GRAVEL PROTECTION.
ONE ACRE. ALL MIXTURES IN TH	IS TABLE /	ARE SHOWN IN TE	RMS OF PLS, LBS/	ACRE.	PUMPED WATER FILTER	DAILY AND AFTER EACH	BAG IS HALF FULL	REPLACE BAG.
MULCH: ALL SEEDED AREAS MUST VEGETATIVE COVER. USE CLEAN OF THE STRAW MUST	OAT OR WI	HEAT STRAW, FREI	E OF WEEDS, NOT	CHOPPED OR	BAG	USE	BAG IS CLOGGED OR FLOW IS REDUCED	REPLACE BAG.
FINELY BROKEN. THE STRAW MUST BE FREE FROM MATURE SEED-BEARING STALKS OR ROOTS OF PROHIBITED OR NOXIOUS WEEDS AS DEFINED BY THE PENNSYLVANIA SEED ACT OF 1947.					ROCK CONSTRUCTION ENTRANCE	DAILY AND AFTER EACH RUNOFF EVENT	LOST AND/OR DISLODGED STONES	REPLACE MISSING STONES SO AS TO MAINTAIN SPECIFIED DIMENSIONS.
APPLY MULCH AT A RATE OF 3 TO 1,240 POUNDS PER 1,000 SQUARE AFTER APPLICATION. A TRACTOR	YARDS). T -DRAWN IN	THE MULCH MUST IPLEMENT MAY BE	BE ANCHORED IM USED TO ANCHO	IMEDIATELY OR THE MULCH			SEDIMENT DEPOSITED IN PAVED ROADWAYS	AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE RETURNED TO THE CONSTRUCTION SITE.
INTO THE SOIL. THIS METHOD IS LIMITED TO SLOPES SHALLOWER THAN OR EQUAL TO 3:1 AND THE EQUIPMENT MUST BE OPERATED ON THE CONTOUR.					EROSION CONTROL BLANKETS (ECB)	ONCE A WEEK AND AFTER EVERY RUNOFF EVENT	SCOUR BENEATH NETTING	RE-INSTALL PROPER ECB MATERIAL AND RE-GRADE BEDDING. MAKE SURE MATERIAL IS INSTALLED AND ANCHORED AS PER THE MANUFACTURER'S
PERMANENT	SEED	ING SPE	CIFICAT	IONS			1	RECOMMENDATIONS. RE-SEED IF NECESSARY.
PRELIMINARY PREPARATION: GRADE AS NECESSARY TO BRING SUBGRADE TO A TRUE, SMOOTH SLOPE PARALLEL TO AND SIX INCHES BELOW FINISH GRADE (I.E., 8 INCHES FOR BASIN					COMPOST SOCK CONCRETE WASHOUT	DAILY AND AFTER EACH USE	DAMAGED OR LEAKING	DEACTIVATE WASHOUT AND REPAIR OR REPLACE IMMEDIATELY.

GENERAL NOTES - NPDES PERMIT REQUIREMENTS

ACCUMULATED MATERIALS REMOVE EXCESS ACCUMULATED MATERIALS WHEN 75% CAPACITY IS REACHED.

ARE > 75% CAPACITY REPLACE PLASTIC LINING WITH EACH CLEANING OF THE WASHOUT FACILITY

PERMIT AS A CO-PERMITTED MPORTANT - POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM) INSTRUMENT FILING NOTICE: THE PERMITTEE OR CO-PERMITTEE SHALL RECORD, WITH THE RECORDER OF DEEDS OFFICE, THE INSTRUMENT WITHIN 45 DAYS FROM THE DATE OF THE NPDES PERMIT ISSUANCE OR AUTHORIZATION, AND SHALL PROVIDE THE CONSERVATION DISTRICT AND THE PADEP WRITTEN DOCUMENTATION CONTAINING THE DATE AND PLACE OF RECORDING ALONG WITH A REFERENCE TO THE

DOCKET, DEED BOOK OR OTHER RECORD, WITHIN 90 DAYS FROM THE DATE OF THE NPDES PERMIT ISSUANCE OR AUTHORIZATION

ANY PROJECT WHICH RESULTS IN EARTH DISTURBANCE ACTIVITIES THAT DISTURB EQUAL TO OR GREATER THAN ONE (1) ACRE IS SUBJECT TO PADEP APPROVAL O COVERAGE UNDER THE GENERAL OR INDIVIDUAL NPDES PERMIT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES. ANY AND ALL CONSTRUCTION ENGAGED IN EARTH DISTURBANCES ACTIVITIES, INCLUDING DEMOLITION, UTILITY LINE CONSTRUCTION, GRADING ACTIVITIES, INSTALLATION OF STORMWATER MANAGEMENT SYSTEMS, ETC., SHALL SECURE A COPY OF THE NPDES PERMIT FOR THIS PROJECT, AND FAMILIARIZE THEMSELVES

UPON AWARD OF CONTRACT FOR ANY EARTH DISTURBANCE ACTIVITIES NOTED ABOVE, THAT CONTRACTOR SHALL BE DESIGNATED AS A CO-PERMITEE, IN ACCORDANCE WITH THE REQUIREMENTS OF PADEP, AND SHALL COMPLETE AND SUBMIT ALL APPROPRIATE FORMS AND NOTIFICATIONS, ALONG WITH THE OWNER,

THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT), AS CO-PERMITEE, IS RESPONSIBLE FOR RECORD KEEPING AND THE RETENTION OF RECORDS OF ALL MONITORING INFORMATION, AS MAY BE REQUIRED TO COMPLETE THE NOTICE OF TERMINATION (NOT), AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS ALL SEED MUST BEAR A GUARANTEED STATEMENT OF ANALYSIS AND MUST BE 100% PROPORTION DESIGNATED BY THE OWNER AND/OR ARCHITECT), AS CO-PERMITEE, IS RESPONSIBLE FOR ENSURING THAT A LICENSED PROFESSIONAL HAVE OVERSIGHT RESPONSIBILITIES FOR THE PROPER INSTALLATION OF BMPS IDENTIFIED IN THE PCSM PLAN PRIOR TO THE SUBMISSION OF THE NOTICE OF TERMINATION, AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT

> AS NOTED IN THE OTHER SECTIONS OF THESE PLANS AND DOCUMENTS, THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES. AS DESIGNATED BY THE OWNER AND/OR ARCHITECT), AS CO-PERMITEE, IS RESPONSIBLE FOR READY TOTAL PURE LIVE SEED¹ CONTACTING THE AUTHORIZED CONSERVATION DISTRICT AT LEAST SEVEN (7) DAYS BEFORE CONSTRUCTION IS TO BEGIN, TO SCHEDULE A PRECONSTRUCTION CONFERENCE, AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT.

THE GENERAL CONTRACTOR (OR IE NO GENERAL CONTRACTOR IS ASSIGNED. THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES. AS DESIGNATED BY THE OWNER AND/OR ARCHITECT) SHALL COMPLETE THE NOTICE OF TERMINATION (NOT), AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT. COMPLETE THE "VISUAL INSPECTION CHECKLIST FOR GENERAL NPDES PERMIT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES" DURING THE WEEKLY INSPECTIONS. COPIES OF THE INSPECTION REPORT MUST BE KEPT ONSITE DURING CONSTRUCTION ACTIVITIES AND AVAILABLE

IMPORTANT - AS PART OF THE COMPLETION OF THE NOTICE OF TERMINATION (NOT), AN AS-BUILT RECORD DRAWING MUST BE GENERATED. THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT) SHALL SECURE THE AS-BUILT RECORD DRAWINGS THROUGH THE SERVICES OF A LICENSED SURVEYOR. THE AS-BUILT RECORD DRAWING SHALL ACCURATELY DEPICT THE AS-BUILT/AS-CONSTRUCTED CONDITIONS FOR ALL STORMWATER/PCSM BMP(S), RELATED STRUCTURES, AND STORMWATER CONVEYANCES IDENTIFIED IN THE PCSM PLAN AND DRAWINGS IN ADDITION TO THE AS-CONSTRUCTED GRADES AND OTHER SITE IMPROVEMENTS THE COMPLETED AS-BUILT RECORD DRAWING MUST BE SUBMITTED BY THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT) TO THE RECORDER OF DEEDS AND PLACED WITH THE POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM) INSTRUMENT FILING NOTICE. A COPY OF THE PROJECT'S AS-BUILT RECORD DRAWING SHALL BE ATTACHED TO THE NOTICE OF TERMINATION (NOT). THE PERMITTEE SHALL RETAIN A COPY OF THE AS-BUILT RECORD DRAWINGS AND SHALL ALSO PROVIDE A COPY, AS PART OF THE APPROVED PCSM PLAN, TO THE PERSON(S) IDENTIFIED IN THE NOTICE OF TERMINATION (NOT), AS BEING RESPONSIBLE FOR THE ONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP(S). ADDITIONAL COPIES OF THE NOTICE OF TERMINATION (NOT) AND AS-BUILT RECORD DRAWING SHALL ALSO BE PROVIDED TO THE LOCAL MUNICIPALITY.

FURTHER NOTES

. THE PURPOSE OF THIS EROSION AND SEDIMENTATION CONTROL PLAN IS TO MINIMIZE EXTENT AND DURATION OF EARTH DISTURBANCE, MAXIMIZE PROTECTION OF EXISTING DRAINAGE FEATURES AND VEGETATION, AND MINIMIZE SOIL COMPACTION

OR INFILTRATION BED AREAS UNTIL THE SITE IS AT FINAL GRADE AND STABILIZED. 3. ALL PARTIES RESPONSIBLE FOR THE EXCAVATION OF SITE MATERIALS OR THE IMPORT OF FILL MATERIALS ARE RESPONSIBLE TO ENSURE THAT "ENVIRONMENTAL DUE DILIGENCE" IN THE DETERMINATION OF CLEAN FILL MATERIAL IS EITHER REMOVED FROM THE SITE OR USED AS FILL FOR THE SITE. ANY MATERIAL IDENTIFIED AS HAZARDOUS MUST BE DISPOSED IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL GUIDELINES AND REGULATIONS.

. IMPORTANT: STORMWATER RUNOFF IS NOT TO BE DIRECTED TO UNPROTECTED STORMWATER MANAGEMENT SYSTEM, STORMWATER CONVEYANCE SYSTEMS.

A) ENVIRONMENTAL DUE DILIGENCE - INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES. REVIEW OF OWNERSHIP AND USE HISTORY OF PROPERTY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. 4. NO BUILDING MATERIALS, WASTES, OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCARDED ON THE SITE. THE FOLLOWING DEFINE WHAT SHOULD BE CONSIDERED "CONSTRUCTION WASTES" AND "CLEAN FILL"

A) CONSTRUCTION WASTES - INCLUDES BUT IS NOT LIMITED TO, EXCESS SOIL MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER, SANITARY WASTES, ETC. THAT COULD ADVERSELY IMPACT WATER QUALITY. B) CLEAN FILL - UNCONTAMINATED, NON-WATER-SOLUBLE, NON-DECOMPOSTABLE, INERT SOLID MATERIAL. THIS INCLUDES SOIL, ROCK, STONE DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK, OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. IT DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE SURFACE WATERS UNLESS OTHERWISE AUTHORIZED, MILLED ASPHALT, OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE. . DURING UTILITY LINE CONSTRUCTION, EXCAVATE UTILITY LINE TRENCHES ONLY AS REQUIRED. LIMIT ADVANCE EXCAVATION TO A DISTANCE EQUAL TO TWO

TIMES THE LENGTH OF PIPE INSTALLATION THAT CAN BE COMPLETED IN ONE DAY. LIMIT DAILY TRENCH EXCAVATION TO THE LENGTH OF PIPE PLACEMENT, PLUG INSTALLATION AND BACKFILLING THAT CAN BE COMPLETED THE SAME DAY. IF REOUIRED, TRENCH PLUGS, AS SHOWN PER DETAIL, ARE TO BE INSTALLED PER PADEP CHAPTER 102 REQUIREMENTS. WATER, WHICH ACCUMULATES IN THE OPEN TRENCH, WILL BE COMPLETELY REMOVED BY PUMPING WATER INTO A FILTER BAG IN ACCORDANCE WITH PADEP CHAPTER 102 REQUIREMENTS. ON THE DAY FOLLOWING PIPE PLACEMENT AND TRENCH BACKFILLING, THE DISTURBED AREA WILL BE GRADED TO FINAL GRADE, AND SEEDED AND MULCHED PER THE PERMANENT SEEDING SCHEDULE.

6. COMPOST FILTER SOCKS (FILTREXX SILTSOXX™). SEDIMENTATION TRAPPÄ, INLETSOXXÄ, RUNOFF DIVERSION SOXXÄ, AND ANY OTHER FILTREXX BMP'S EMPLOYED AS PART OF THE EROSION AND SEDIMENTATION CONTROL PLAN FOR THE PROJECT MUST FOLLOW THE MANUFACTURER'S DISPOSAL/RECYCLING INSTRUCTIONS FOR EACH SPECIFIC BMP UTILIZED THROUGHOUT THE PROJECT'S CONSTRUCTION AND EARTHMOVING OPERATIONS.

REQUIREMENTS. REFER TO DETAIL. WHEN FILTER BAG IS $\frac{1}{2}$ FULL IT SHOULD BE REPLACED. ANY ACCUMULATED SEDIMENTATION WILL BE MIXED WITH SOIL and properly disposed of on the site if possible or disposed of at an offsite area. The contractor shall be responsible for disposing OF ALL EXCESS MATERIAL OFF-SITE TO AN APPROVED FACILITY. B. EROSION AND SEDIMENTATION CONTROLS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE WITHIN THE CONTRIBUTORY

9. AFTER FINAL SITE STABILIZATION IS ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING

DURING FOUNDATION CONSTRUCTION, PUMP WATER ACCUMULATED IN OPEN TRENCHES INTO FILTER BAGS IN ACCORDANCE WITH PADEP CHAPTER 102

REMOVAL OF THE CONTROLS MUST BE IMMEDIATELY STABILIZED. FINAL STABILIZATION IS DEFINED AS THE ACHIEVEMENT OF A MINIMUM UNIFORM 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES HAS BEEN ACHIEVED ON ALL CONTRIBUTORY DRAINAGE AREAS.

10. SEDIMENT MUST BE REMOVED FROM INLET PROTECTION AFTER EACH RUNOFF EVENT.

DRAINAGE AREAS OF THOSE CONTROLS.

11. ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 4 DAYS MUST BE TEMPORARILY STABILIZED. DISTURBED AREAS THAT ARE EITHER AT FINISHED GRADE, OR ANY GRADED AREA OF 15,000 FT2 OR MORE REACHES FINAL GRADE, OR WILL NOT BE DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

OPERATION & MAINTENANCE

REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.

RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED. MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING

DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK, WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE. PUMPED WATER FILTER BAG

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS

١,	PROPERTY	TEST METHOD	MINIMUM STANDARD
	AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 lb/in
	GRAB TENSILE	ASTM D-4632	205 lb
D	PUNCTURE	ASTM D-4833	110 lb
	MULLEN BURST	ASTM D-3786	350 psi
	UV RESISTANCE	ASTM D-4355	70%
	AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REOUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW

PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%. CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

FOR ANY PROJECT ON WHICH CONCRETE WILL BE POURED OR OTHERWISE FORMED ON SITE, A SUITABLE WASHOUT FACILITY MUST BE PROVIDED FOR THE CLEANING OF CHUTES, MIXERS, AND HOPPERS OF THE DELIVERY VEHICLES UNLESS SUCH A FACILITY WILL BE USED AT THE SOURCE OF THE CONCRETE. UNDER NO CIRCUMSTANCES MAY WASH WATER FROM THESE VEHICLES BE ALLOWED TO ENTER any surface waters. Make sure that proper signage is provided to drivers so that they are aware of the presence of washout facilities. WASHOUT FACILITIES SHOULD NOT BE PLACED WITHIN 50 FEET OF STORM DRAINS, OPEN DITCHES OR SURFACE WATERS. THEY SHOULD BE IN A CONVENIENT LOCATION FOR THE TRUCKS, PREFERABLY

NEAR THE PLACE WHERE THE CONCRETE IS BEING POURED, BUT FAR ENOUGH FROM OTHER VEHICULAR TRAFFIC TO MINIMIZE THE POTENTIAL FOR ACCIDENTAL DAMAGE OR SPILLS. WHEREVER POSSIBLE, THEY SHOULD BE LOCATED ON SLOPES NOT EXCEEDING A 2% GRADE. ADDITIONAL INFORMATION ON WASHOUTS MAY BE OBTAINED FROM EPA'S STORMWATER WEBSITE AT: HTTP://CFPUB.EPA.GOV/NPDES/STORMWATER/MENUOFBMPS/INDEX.CFM?ACTION=BROWSE&RBUTTON=DETAIL&BMP=117&MINMEASURE=4 COMPOST SOCK WASHOUT - WHEREVER COMPOST SOCK WASHOUTS ARE USED, A SUITABLE IMPERVIOUS GEOMEMBRANE SHOULD BE PLACED AT THE LOCATION OF THE WASHOUT. COMPOST SOCKS

SHOULD BE STAKED IN THE MANNER RECOMMENDED BY THE MANUFACTURER AROUND PERIMETER OF THE GEOMEMBRANE SO AS TO FORM A RING WITH THE ENDS OF THE SOCK LOCATED AT THE UPSLOPE CORNER. CARE SHOULD BE TAKEN TO ENSURE CONTINUOUS CONTACT OF THE SOCK WITH THE GEOMEMBRANE AT ALL LOCATIONS. WHERE NECESSARY, SOCKS MAY BE STACKED AND STAKED A SUITABLE IMPERVIOUS GEOMEMBRANE SHALL BE PLACED AT THE LOCATION OF THE WASHOUT PRIOR TO INSTALLING THE SOCKS.

PREFABRICATED WASHOUT CONTAINERS - CARE SHOULD BE TAKEN TO ENSURE THAT THE CONTAINERS ARE INTENDED BY THE MANUFACTURER FOR USE AS CONCRETE WASHOUT BMPS, THAT THEY ARE WATERTIGHT. AND APPROPRIATELY SIZED. ACCUMULATED MATERIALS MUST BE PROPERLY DISPOSED OF (PREFERABLY RECYCLED) WHEN THEY REACH THE CLEANOUT LEVEL SELF-INSTALLED WASHOUTS - THESE TYPES OF WASHOUTS SHOULD BE EXCAVATED BELOW GRADE TO PREVENT RUNOFF OF THE WASH WATER AND MINIMITE THE POTENTIAL FOR BREACHING. THEY SHOULD BE SIZED TO HANDLE SOLIDS, WASH WATER, AND RAINFALL. A GOOD RULE OF THUMB IS THAT 7 GALLONS OF WASH WATER ARE REQUIRED TO WASH ONE TRUCK CHUTE AND 50 GALLONS FOR THE HOPPER OF A CONCRETE PUMP TRUCK

FOR LARGER SITES, A BELOW-GRADE WASHOUT SHOULD BE A MINIMUM OF 10 FEET WIDE AND PROVIDE AT LEAST 12 INCHES OF FREEBOARD ABOVE THE LIQUID AND SOLID WASTE ANTICIPATED

BETWEEN CLEANOUT INTERVALS. THE PIT SHOULD BE LINED WITH PLASTIC SHEETING OF AT LEAST 10-MIL THICKNESS (WITH NO HOLES OR TEARS) TO PREVENT LEACHING OF LIQUIDS INTO THE

WASHWATER RECYCLING SYSTEMS - WASHWATER RECYCLING SYSTEMS HAVE ALSO BEEN DEVELOPED WHICH SEPARATE THE SOLIDS FROM THE WASHWATER, CAPTURING BOTH IN IMPERMEABLE BAGS AND ALLOWING THEM TO BE RECYCLED. THESE SYSTEMS MAY BE USED IN LIEU OF WASHOUTS IF MANUFACTURERS' SPECIFICATIONS ARE FOLLOWED. CARE MUST BE TAKEN TO PREVENT THE FILTERED WATER FROM ENTERING ANY SURFACE WATERS

HIS DISCHARGE WOULD HAVE AN ADVERSE EFFECT UPON THE RECEIVING WATER. IN ADDITION, CONTINUED USE OF A BASIN OR TRAP AS A WASHOUT FACILITY WOULD SIGNIFICANTLY REDUCE THE STORAGE CAPACITY OF THE BASIN OR TRAP. MAINTENANCE - ALL CONCRETE WASHOUT FACILITIES SHOULD BE INSPECTED DAILY. DAMAGED OR LEAKING WASHOUTS SHOULD BE DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY.

SEDIMENT BASINS AND SEDIMENT TRAPS - SEDIMENT BASINS AND SEDIMENT TRAPS MAY NOT BE USED AS CONCRETE WASHOUT DEVICES, SINCE THEY DISCHARGE DIRECTLY TO SURFACE WATERS.

PLASTIC LINERS SHOULD BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY. COMPOST FILTER SOCH

COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN SOCK ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY SOCK SHALL NOT EXCEED THAT SHOWN ON TABLE 4.2 ON DETAIL 5 ON SHEET C203. STAKES MAY BE INSTALLED IMMEDIATELY DOWNSLOPE OF THE SOCK IF SO SPECIFIED BY

SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 ON DETAIL 5 ON SHEET C203. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 ON DETAIL 5 ON SHEET C203

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVEGROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN. SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS O

BIODEGRADABLE FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S

UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE

CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS.

ACCUMULATED MATERIALS SHOULD BE REMOVED WHEN THEY REACH 75% CAPACITY

STABILIZATION METHODS AND STANDARDS: **EROSION CONTROL BLANKETS**

SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET. PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.

SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.

THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

PCSM BMP INSTALLATION SEQUENCE & MAINTENANCE

FLEXSTORM INLET FILTER BMP INSTALLATION SEQUENCE BMPs #1-3

. REMOVE THE GRATE FROM THE CASTING OR CONCRETE DRAINAGE STRUCTURE

3. DROP IN THE FLEXSTORM INLET FILTER THROUGH THE CLEAR OPENING AND BE SURE THE SUSPENSION HANGERS REST FIRMLY ON THE INSIDE LEDGE (LIP) OF THE CASTING. 4. REPLACE THE GRATE AND CONFIRM IT IS ELEVATED NO MORE THAN 1/8", WHICH IS THE THICKNESS OF THE STEEL

. CLEAN THE LEDGE (LIP) OF THE CASTING FRAME OR DRAINAGE STRUCTURE TO ENSURE IT IS FREE OF STONE AND DIRT.

- FLEXSTORM INLET FILTER BMP MAINTENANCE BMPs #1-3 FREQUENCY OF INSPECTIONS: CONSTRUCTION SITE INSPECTION SHOULD OCCUR FOLLOWING EACH 1/2" OR MORE RAIN EVENT. POST CONSTRUCTION INSPECTIONS SHOULD OCCUR THREE TIMES PER YEAR (EVERY FOUR MONTHS) IN AREAS WITH YEAR-ROUND RAINFALL AND THREE TIMES PER YEAR (EVERY THREE MONTHS) IN AREAS WITH RAINY SEASONS BEFORE AND AFTER SNOWFALL SEASON. INDUSTRIAL APPLICATION SITE INSPECTIONS (LOADING RAMPS, WASH RACKS.
- FILLED WITH SEDIMENT AND DEBRIS, OR AS DIRECTED BY THE LOCAL CONSERVATION DISTRICT OR MUNICIPAL • REMOVE THE GRATE, ENGAGE THE LIFTING BARS OR HANDLES WITH THE FLEXSTORM REMOVAL TOOL, AND LIFT THE
- FLEXSTORM INLET FILTER FROM THE DRAINAGE STRUCTURE. MACHINE ASSISTANCE IS NOT REQUIRED. DISPOSE OF THE SEDIMENT OR DEBRIS AS DIRECTED BY THE LOCAL CONSERVATION DISTRICT OR MUNICIPAL INSPECTOR. (AS AN ALTERNATIVE, AN INDUSTRIAL VACUUM MAY BE USED TO COLLECT THE ACCUMULATED SEDIMENT IF

MAINTENANCE FACILITIES) SHOULD OCCUR ON A REGULARLY SCHEDULED BASIS NO LESS THAN THREE TIMES PER YEAR.

UPON INSPECTION, THE FLEXSTORM INLET FILTER SHOULD BE EMPTIED IF THE SEDIMENT BAG IS MORE THAN HALF

• REPLACE THE BAG IF THE GEOTEXTILE IS TORN OR PUNCTURED TO ½" DIAMETER OR GREATER ON THE LOWER HALF OF NOTE: IF PROPERLY MAINTAINED, THE WOVEN SEDIMENT BAG SHOULD LAST A MINIMUM OF 4 YEARS IN THE FIELD. SEDIMENT BAG REPLACEMENT: WHEN REPLACING A SEDIMENT BAG, REMOVE THE BAG BY LOOSENING OR CUTTING OFF

THE CLAMPING BAND, TAKE THE NEW SEDIMENT BAG, WHICH IS EQUIPPED WITH A STAINLESS-STEEL WORM DRIVE

CLAMPING BAND, AND USE A DRILL OR SCREW DRIVER TO TIGHTEN THE BAG AROUND THE FRAME CHANNEL. ENSURE THE

REMOVE ANY CAKED-ON SILT FROM THE SEDIMENT BAG AND REVERSE FLUSH THE BAG FOR OPTIMAL FILTRATION.

- BAG IS SECURE AND THAT THERE IS NO SLACK AROUND THE PERIMETER OF THE BAND. VEGETATED SWALE BMP INSTALLATION SEQUENCE BMP #4
- BEGIN VEGETATED SWALE CONSTRUCTION ONLY WHEN UPGRADIENT EROSION AND SEDIMENTATION CONTROL MEASURES ARE IN PLACE AND BEFORE PLACEMENT OF PAVING 2. ROUGH GRADE THE VEGETATED SWALE. EQUIPMENT SHALL AVOID EXCESSIVE COMPACTION AND/OR LAND

DAMAGED AREAS SHOULD BE FULLY RESTORED TO ENSURE FUTURE FUNCTIONALITY OF THE SWALE.

- DISTURBANCE, OPERATING FROM THE SIDE OF THE SWALE AND NEVER ON THE BOTTOM. EXCAVATE THE BOTTOM OF THE SWALE AND INSTALL INLET, GRAVEL & UNDERDRAIN, AND SOIL/PLANTING MIX PER DETAIL. 3. FINE GRADE THE VEGETATED SWALE. 4. SEED VEGETATE AND INSTALL PROTECTIVE LINING PER PLANS AND DETAILS. PLANT SWALE AT A TIME OF THE YEAR
- WHEN SUCCESSFUL ESTABLISHMENT WITHOUT IRRIGATION IS MOST LIKELY. VEGETATION SHOULD BE ESTABLISHED AS SOON AS POSSIBLE TO PREVENT EROSION AND SCOUR. ONCE ALL TRIBUTARY AREAS REACH FINAL STABILIZATION, REMOVE TEMPORARY EROSION AND SEDIMENTATION CONTROLS. REGRADE AND RESEED IMMEDIATELY AFTER CONSTRUCTION AND STABILIZATION HAVE OCCURRED. ANY

NOTE: IF A VEGETATED SWALE IS USED FOR RUNOFF CONVEYANCE DURING CONSTRUCTION. IT SHOULD BE REGRADED AND RESEEDED IMMEDIATELY AFTER CONSTRUCTION AND STABILIZATION HAS OCCURRED. ANY DAMAGED AREAS SHOULD BE FULLY RESTORED TO ENSURE FUTURE FUNCTIONALITY OF THE SWALE.

VEGETATED SWALE BMP MAINTENANCE BMP #4 (TO BE DONE AS NEEDED)

ROTOTILL AND REPLANT SWALE IF DRAW DOWN TIME IS MORE THAN 48 HOURS.

- PLANT ALTERNATIVE GRASS SPECIES IN THE EVENT OF UNSUCCESSFUL ESTABLISHMENT. RESEED BARE AREAS; INSTALL APPROPRIATE EROSION CONTROL MEASURES WHEN NATIVE SOIL IS EXPOSED OR EROSION CHANNELS ARE FORMING.
- INSPECT SWALE IMMEDIATELY AFTER THE SPRING MELT, REMOVE RESIDUALS (E.G. SAND, ROOF RUNOFF, ETC.) AND REPLACE DAMAGED VEGETATION WITHOUT DISTURBING REMAINING VEGETATION

SCALE: AS NOTED

ARCHITECT: LE

DRAFTSMAN: CWT

CHECKED BY: CAD

REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE. RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION

MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED. MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR

INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY

BLACKHAWK HIGH-FLOW HOLES (2"\$) **INLET FILTER MAT** PLUGS (RED) 0 0 0 PROVIDES INCREASEI SURFACE AREA FOR SEDIMENT CAPTURE - PRIOR TO INSTALLATION, INLET GRATE SURFACE AND SURROUNDING AREA SHALL BE CLEANED AND CLEARED OF DEBRIS. INLET FILTER MAT SHALL BE INSTALLED WITH A MINIMUM 2" OVERLAP FROM EDGE OF GRATE TO EDGE OF MAT. ADJUST MAT BY HAND UNTIL PLACEMENT ALLOWS FOR OPTIMAL MAGNETIC ADHESION TO GRATE SURFACE.

- PRE-INSTALLED RED EMERGENCY DEWATERING PLUGS CAN BE REMOVED IN THE EVENT OF FLOODING TO ALLOW FOR RAPID DEWATERING. AFTER DEWATERING, THE INLET FILTER MAT SHALL BE LIFTED AND THOROUGHLY CLEANED OR REPLACED AND THE EMERGENCY DEWATERING PLUGS SHALL BE REINSTALLED. IF GRATE IS AT LOWEST POINT OF STREET, REMOVAL OF ONE PLUG WILL ALLOW FOR EXPEDITED DEWATERING AT ALL TIMES. INLET FILTER MATS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. AS NEEEDED, INLET FILTER MATS

SHALL BE LIFTED AND RINSED OR REPLACED. WHEN FLOW CAPACITY HAS BEEN HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET OR THE INLET FILTER MAT BECOMES COMPRESSED DUE TO HEAVY TRAFFIC, REPLACEMENT IS REQUIRED. - A SUPPLY OF SPARE INLET FILTER MATS SHALL BE MAINTAINED ON SITE. ALL NECESSARY REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED MATS ACCORDING TO THE PLAN - INLET FILTER MATS ARE MADE FROM A COMPOSTABLE COCONUT COIR. MAGNETS ARE RUBBER WITH FERROUS OXIDE SIZES OF

> 100 CEMENT FILLED BAGS (WETTED) OR MORTARED STONE

CONCRETE-FILLED


1,000

500


200

100

*TOPSOIL MAY NOT BE USED TO FILL SACKS IMPERVIOUS TRENCH PLUGS ARE REQUIRED FOR ALL STREAM, RIVER, WETLAND, OR OTHER WATER BODY CROSSINGS.



NOT TO SCALE



NOT TO SCALE

DRAINAGE COURSES IS NOT ACCEPTABLE. 1 ROCK CONSTRUCTION ENTRANCE

2 BLACKHAWK INLET FILTER MAT

GRATES CAN VARY. INLET FILTER MAT CAN BE CUSTOM FIT ACCORDING TO APPLICATION.

NOT TO SCALE

3 TRENCH PLUG

SECTION VIEW

TRENCH SLOPE (%)

< 5

5 - 15

15 - 25

25 - 35

35 - 100

NOT TO SCALE

TRENCH BOTTOM

TRENCH PLUG SPACING (L)

ELEVATION

PIPE INVERT -

PLUG MATERIAL


* CLAY, BENTONITE, OR CONCRETE FILLED SACKS

BEDDING

MAXIMUM SPACING AND MATERIALS FOR TRENCH PLUGS

4 COMPOST SOCK CONCRETE WASHOUT

5 FILTER SOCK INLET PROTECTION @ SQUARE STORM INLET



SEDIMENT BARRIER ALIGNMENT

SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2. (PA DEP EROSION & SEDIMENT CONTROL MANUAL.)

COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN SOCK ALIGNMENT (FIGURE4.1). MAXIMUM SLOPE LENGTH ABOVE ANY SOCK SHALL NOT EXCEED THAT SHOWN ON FIGURE 4.2. STAKES MAY BE INSTALLED IMMEDIATELY DOWNSLOPE OF THE SOCK IF SO SPECIFIED BY THE MANUFACTURER.

TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS.

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVE GROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.

SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.

BIODEGRADABLE FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.


UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS SOIL SUPPLEMENT.


TABLE 4.1 COMPOST SOCK FABRIC MINIMUM SPECIFICATIONS

	TABLE 4.1 COM OST SOCK FABRIC MINIMON SI EGIT CATTONS						
MATERIAL TYPE	3 mil HDPE	5 mil HDPE	5 mil HDPE	MULTI-FILAMENT POLYPROPYLENE (MFPP)	HEAVY DUTY MULTI-FILAMEN' POLYPROPYLENI (HDMFPP)		
MATERIAL CHARACTERISTICS	PHOTO- DEGRADABLE	PHOTO- DEGRADABLE	BIO- DEGRADABLE	PHOTO- DEGRADABLE	PHOTO- DEGRADABLE		
SOCK DIAMETERS	12" 18"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"		
MESH OPENING	3/8"	3/8"	3/8"	3/8"	1/8"		
TENSILE STRENGTH		26 PSI	26 PSI	44 PSI	202 PSI		
ULTRAVIOLET STABILITY % ORIGINAL STRENGTH (ASTM G-155)	23% AT 1000 HR.	23% AT 1000 HR.		100% AT 1000 HR.	100% AT 1000 HR.		
MINIMUM FUNCTIONAL LONGEVITY	6 MONTHS	9 MONTHS	6 MONTHS	1 YEAR	2 YEARS		
		TWO-PLY	SYSTEMS				
				HDPE BIAXIAL NET	=		

	HDPE BIAXIAL NET			
INNER CONTAINMENT NETTING	CONTINUOUSLY WOUND			
	FUSION-WELDED JUNCTURES			
	3/4" x 3/4" MAX. APERTURE SIZE			
OUTER FILTRATION MESH	COMPOSITE POLYPROPYLENE FABRIC (WOVEN LAYER AND NON-WOVEN FLEECE MECHANICALLY FUSED VIA NEEDLE PUNCH)			
	3/16" MAX. APERTURE SIZE			
SOCK EARRICS COMPOSED OF BURLAP MAY BE U	SED ON PROJECTS LASTING 6 MONTHS OR LESS			

 CONCRETE BLOCK ON COMPOST FILTER SOCK · CONCRETE BLOCK 10' LINEAL SPACING BLOWN/PLACED FILTER MEDIA -**PROTECTED** COMPOST FILTER SOCK SECTION VIEW AREA TO BE PROTECTED COMPOST FILTER SOCK IN PAVEMENT AREA* * WHERE SOCKS ARE PLACED ON PAVED SURFACES, CONCRETE — COMPOST FILTER SOCK BLOCKS SHALL BE USED IMMEDIATELY DOWNSLOPE OF THE SOCKS WORK AREA (AT THE SAME INTERVALS RECOMMENDED FOR THE STAKES) TO HELP HOLD THE SOCK IN PLACE. COMPOST FILTER SOCK PLAN VIEW





COMPOST SHOULD BE A WELL DECOMPOSED, WEED-FREE ORGANIC MATTER DERIVED FROM AGRICULTURE, FOOD, STUMP GRINDINGS, AND YARD OR WOOD/BARK ORGANIC MATTER SOURCES. THE COMPOST SHOULD BE AEROBICALLY COMPOSTED. THE COMPOST SHOULD POSSESS NO OBJECTIONABLE ODORS AND SHOULD BE REASONABLY FREE (<1% BY DRY WEIGHT) OF MAN-MADE FOREIGN MATTER. THE COMPOST PRODUCT SHOULD NOT RESEMBLE THE RAW MATERIAL FROM WHICH IT WAS DERIVED. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS ARE NOT ACCEPTABLE AS THE ORGANIC COMPONENT

THE PHYSICAL PARAMETERS OF THE COMPOST SHOULD COMPLY WITH THE STANDARDS IN TABLE 4.2. THE STANDARDS CONTAINED IN THE PennDOT PUBLICATION 408 ARE AN ACCEPTABLE ALTERNATIVE.

TABLE 4.2 COMPOST STANDARDS

TABLE 4.2 COM OST STANDARDS					
ORGANIC MATTER CONTENT	25% - 100% (DRY WEIGHT BASIS)				
ORGANIC PORTION	FIBROUS AND ELONGATED				
рН	5.5 - 8.5				
MOISTURE CONTENT	30% -60%				
PARTICLE SIZE	30% - 50% PASS THROUGH 3/8" SIEVE				
SOLUBLE SALT CONCENTRATION	5.0 dS/m (mmhos/cm) MAXIMUM				
FILTREXX					

WELL VEGETATED, GRASSY AREA INTAKE HOSE - HEAVY DUTY LIFTING STRAPS INTAKE HOSE ·

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS, THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D4884	60 LB/IN
GRAB TENSILE	ASTM D4632	205 LB
PUNCTURE	ASTM D4833	110 LB
MULLEN BURST	ASTM D3786	350 PSI
UV RESISTANCE	ASTM D4355	70%
AOS % RETAINED	ASTM D4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME ½ FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY

ATTACHED. BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR ½ THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE

4. 2"-5"	SLOPE INSTALLATION NORTH AMERICAN GREEN 5.	12"
38.	(3A)	
PREPARE SOIL BEFORE INSTALLING BLANK AND SEED. NOTE: WHEN USING CELL-O-SEE		

AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED


2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" (15cm) DEEP X 6" (15cm) WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30cm) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30cm) PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30cm) APART ACROSS THE WIDTH

3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.

DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET. (FOR NA GREEN "S75" USE STAPLE PATTERN 'C'.)

4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" (5cm-12.5cm) OVERLAP

5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5cm) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30cm) APART ACROSS ENTIRE BLANKET WIDTH.



STAPLE PATTERN 'B'

NOT TO SCALE

SCALE: AS NOTED REVISIONS 1 11-30-21 PER BOROUGH & COUNTY COMMEN

ARCHITECT: LE DRAFTSMAN: CWT

7n2-R

CHECKED BY: CAD



6 COMPOST FILTER SOCK

FILTREXX & JMD

IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

NOT TO SCALE

8 EROSION CONTROL BLANKET (SLOPE)

7 PUMPED WATER FILTER BAG

NOT TO SCALE


SITE LOCATION MAP SCALE: 1"=2,000'

SYMBOUS

MONUMENT FOUND	Q _{WP}	POWERPOLE	S	SEWER MANHOLE
MONUMENT SET	(GUY WIRE	c/O	CLEAN OUT
P.K. NAIL FOUND	**	LIGHT POLE		STORM DRAIN MANHOLE
D P.K. NAIL SET	$ \swarrow $	STREET LIGHT POLE	SI	STORM INLET
X FND X MARK	\bowtie	ELEC. TRANSFORMER		CURB INLET
✓ SET X MARK	A/C	AIR CONDITIONER	A	PAY PHONE
R.R. SPIKE FOUND	— E —	BURIED ELECTRIC	I	TELEPHONE BOX
\triangle R.R. SPIKE SET	−0H− ©	OVERHEAD ELECTRIC ELEC. MANHOLE		TELEPHONE MANHOLE
BENCHMARK	E	ELECTRIC METER	$Q_{\rm tr}$	TELEPHONE POLE
(R) RECORD DATA	w	WATER LINE -	— T —	TELEPHONE LINE
(M) MEASURED DATA	(W)	WATER MANHOLE	UT	UNDERGROUND
(S) SURVEYED DATA	W	WATER VALVE	_c_	TELEPHONE MARKER CABLE TELEVISION
R/W RIGHT OF WAY	W	WATER METER		
BSL BACK SET LINE	\triangle	HYDRANT	luci	CABLE BOX UNDERGROUND
RCP REINFORCED CONC PIPE	₽F	BACK FLOW PREVENTOR		CABLE MARKER
CMP CORRUGATED METAL PIPE	. □ G	GAS VALVE	TS	TRAFFIC POLES
PVC PLASTIC PIPE	G	GAS METER	•	TRAFFIC SIGNAL
MTL METAL	UG	UNDERGROUND GAS MARKER		TRAFFIC MANHOLE
AGL ABOVE GROUND LEVEL L/S LANDSCAPING	©	GAS MANHOLE	T-S	TRAFFIC SIGNAL BOX
	— G —	GAS LINE BOLLARD	STOP	STOP SIGN
TREE	B.H	BORE HOLE	<u> </u>	SIGN
MC METAL TANK COVER	MW	MONITORING WELL	Ц	
	MB	MAIL BOX		
		UNKNOWN MANHOLE		
	♦	SQUARE METAL LID		
	₩ F.P.	FUEL TANK LID		
	O	FLAG POLE		

DEMOLITION NOTES

- 1. CONTRACTOR TO REVIEW PHASE II REPORT FOR SITE AND TO BE FAMILIAR WITH ANY AND ALL MATERIALS THAT MAY BE ENCOUNTERED OR OUTLINED IN PHASE II REPORT.
- 2. ALL WORK TO BE ACCOMPLISHED IN STRICT ACCORDANCE WITH ALL LOCAL ORDINANCES, CITY OR STATE.
- 3. WITHIN THE SUBJECT PROPERTY, THE INTENT IS TO HAVE A CLEAN, CLEAR SITE, FREE OF ALL EXISTING ITEMS NOTED TO BE REMOVED IN ORDER TO PERMIT THE CONSTRUCTION OF THE NEW PROJECT.
- 4. ALL ITEMS NOTED TO BE REMOVED BY THE SELLER SHALL BE ACCOMPLISHED PRIOR TO THE CLOSING OF THE REAL ESTATE TRANSACTION. ALL OTHER ITEMS NOTED TO BE REMOVED SHALL BE DONE SO AS PART OF THE CONTRACT FOR GENERAL CONSTRUCTION.
- REMOVE ALL UTILITIES TO EXISTING STRUCTURES WHETHER SHOWN OR NOT. CUT AND CAP ALL UNDERGROUND LINES AT THE PROPERTY LINE UNLESS OTHERWISE NOTED.
- 6. FOR ALL ITEMS NOTED TO BE REMOVED REMOVE NOT ONLY THE ABOVE GROUND ELEMENTS, BUT ALL UNDERGROUND ELEMENTS AS WELL, INCLUDING BUT NOT NECESSARILY LIMITED TO: FOUNDATIONS, GRAVEL FILLS, TREE ROOTS, OLD PIPE, ETC.
- BACKFILL ALL EXCAVATIONS RESULTING FROM THE DEMOLITION WORK TO MEET THE REQUIREMENTS FOR FILL OUTLINED IN THE SOILS REPORT.
- GENERAL CONTRACTOR IS RESPONSIBLE TO VERIFY, PRIOR TO THE FINAL CONTRACT EXECUTION, IF ANY BUILDING STRUCTURE THAT IS NOTED TO BE REMOVED HAS A BASEMENT. IF SO THE BUILDING STRUCTURE, BOTH FLOOR STRUCTURES, BASEMENT, FOUNDATION, ETC. ARE TO BE REMOVED AND BACKFILLED TO EXISTING GRADE ELEVATIONS SURROUNDING THE EXISTING STRUCTURE.
- 9. DEMOLITION SHOULD NOT BEGIN UNTIL E&S CONTROLS HAVE BEEN COMPLETED.
- 10. GENERAL CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNAGE, ETC. TO PROVIDE A SECURE WORK SITE, AND PROTECT PEDESTRIANS AND VEHICLES DURING CONSTRUCTION OPERATIONS. COORDINATE INSTALLATION OF FENCING, BARRICADES, SIGNS, ETC., WITH LAND OWNER, LOCAL MUNICIPALITY AND AUTOZONE CONSTRUCTION MANAGER.
- 11. GENERAL CONTRACTOR TO CONFIRM LOCATION, SIZE, ETC., OF SANITARY LATERAL SERVICES TO ALL STRUCTURES PROPOSED TO BE DEMOLISHED, AND COORDINATE REMOVAL WITH SANITARY AUTHORITY. REMOVE ALL LATERALS, CLEANOUTS, ETC., AND PLUG AND CAP LATERALS IN ACCORDANCE WITH SANITARY AUTHORITY REQUIREMENTS.
- 12. GENERAL CONTRACTOR TO DETERMINE LOCATION, SIZE, CONNECTION, ETC., OF ANY STORM DOWNSPOUTS AND STORM LATERALS TO ALL STRUCTURES PROPOSED TO BE DEMOLISHED, AND REMOVE AS REQUIRED. PLUG AND CAP ANY STORM LATERAL CONNECTIONS TO CITY STORM/SANITARY MAINS IN ACCORDANCE WITH MUNICIPAL REQUIREMENTS.
- 13. EXCAVATED SOIL FROM UNDERGROUND STORAGE TANK REMOVAL TO BE TESTED PER PaDEP REQUIREMENTS, AND REMOVED TO AN APPROVED FACILITY. IF CONTAMINATION IS PRESENT, SITE MUST BE CLEANED UP IN ACCORDANCE WITH REQUIRED CORRECTIVE ACTION PROCEDURES. SEE PaDEP CLOSURE REQUIREMENTS FOR UNDERGROUND STORAGE TANK SYSTEMS, TECHNICAL GUIDANCE NO. 263-4500-601, AND PaDEP BUREAU OF ENVIRONMENTAL CLEAN-UP AND BROWNFIELDS, DIVISION OF STORAGE TANKS, 2630-BK-DEP 4699, REV. 9/2020 OR MOST CURRENT VERSION.



1 inch = 20 ft.

SHEET 9 of 16

SCALE: 1" = 20'-0"


REVISIONS

1 11-30-21 PER BOROUGH & COUNTY COMMENT

ARCHITECT: LE

DRAFTSMAN: CWT

CHECKED BY: CAD



LANDSCAPE REQUIREMENTS - SCHUYLKILL COUNTY

- DESCRIPTION ZONING § 804 (A) LANDSCAPING
 - ANY PART OF A COMMERCIAL, INDUSTRIAL, INSTITUTIONAL OR APARTMENT LOT NOT USED FOR STRUCTURES, LOADING AREAS, PARKING SPACES, AISLES OR SIDEWALKS, SHALL BE PROVIDED WITH AN ALL-SEASON, WELL MAINTAINED VEGETATIVE GROUND COVER, AND SHALL BE LANDSCAPED WITH TREES AND SHRUBS.
 - ZONING § 804 (C)(1) PARKING LOT LANDSCAPING A MINIMUM OF ONE (1) DECIDUOUS TREE SHALL BE REQUIRED FOR 2 TREES 2 TREES EVERY TWENTY (20) NEW OFF-STREET PARKING SPACES. $37 \div 20 = 1.85$ (2) TREES REQUIRED
 - LANDSCAPED ISLANDS SHALL BE PROVIDED WITHIN AUTO PARKING AREAS. OTHERWISE, THE TREES MAY BE PLANTED AROUND THE PARKING AREA. ZONING § 804 (C)(5) YES YES THE TRUNK DIAMETER (MEASURED AT HEIGHT OF SIX (6) INCHES

ABOVE THE FINISHED GRADE LEVEL) SHALL BE A MINIMUM OF TWO (2) INCHES OR GREATER.

ANY NEW OR EXPANDED VEHICLE PARKING STORAGE AREA SHALL BE SEPARATED FROM A PUBLIC STREET BY A PLANTING STRIP. THE PLANTING STRIP SHALL BE A MINIMUM WIDTH OF FIVE (5) FEET AND BE MAINTAINED IN GRASS OR OTHER ATTRACTIVE VEGETATIVE GROUNDCOVER. THIS FIVE (5) FEET WIDTH SHALL BE INCREASED TO TEN (10) FEET FOR A LOT INCLUDING 20 TO 99 PARKING SPACES. ANN STREET: | 10' PLANTING | 10' PLANTING STRIP STRIP

(MODIFICATION REQUESTED) STRIP MAX. 7'-7" PLANTING STRIP SALDO § 1128.C.5.A-H STREET TREES STREET TREES SHALL BE PROVIDED IN ALL COMMERCIAL 4 TREES 4 TREES DEVELOPMENTS. TREES SHALL BE PLANTED BETWEEN THE STREET LINE AND THE BUILDING SETBACK LINE EXCEPT WHERE THE PLANNING

POTTSVILLE ST. CLAIR HIGHWAY:

COMMISSION HAS AUTHORIZED PLACEMENT OF TREES WITHIN THE STREET RIGHT-OF-WAY. A MINIMUM OF TWO (2) CANOPY TREES SHALL BE PROVIDED FOR EVERY ONE HUNDRED (100) FEET OF PUBLIC RIGHT-OF-WAY. STREET TREES SHALL BE PLACED A MINIMUM OF FORTY (40) FEET APART ALONG THE RIGHT-OF-WAY. TRUNK CALIPER MIN. 40' APART MIN. 40' APART SHALL BE A MINIMUM OF 2". 173 LINEAL FEET / 100 = 1.73 X 2 = 3.46 TREES REQUIRED

LANDSCAPE LEGEND

SEE SPECIFICATIONS

DECIDUOUS TREE 'AR'

SEE SPECIFICATIONS QUANTITY ——

DECIDUOUS TREE 'GT'

DECIDUOUS SHRUB 'VD'

PLANT LIST

<u>FLANT LIST</u>						
QTY.	KEY	BOTANICAL/COMMON NAME	MATURE SIZE	ROOT TYPE	REMARKS	
4	AR	ACER RUBRUM	2" CAL.	B & B		
	AK	AMERICAN RED MAPLE	Z CAL.			
2	GT	GLEDITSIA TRIACANTHOS	2" CAL.	B & B		
	Gi	THORNLESS HONEY LOCUST	Z CAL.			
24 IG	īC	ILEX GLABRA 'NORDIC'	48" MIN. HGT.	B & B		
	10	INKBERRY	40 MIN. HUI.			
24	70	VIBURNUM DENTATUM	48" MIN. HGT.	B & B		
	VD -	ARROWOOD VIBURNUM	1 40 MIN. HGI.			

GENERAL NOTES

- . ALL LANDSCAPE AREAS TO BE GRASS COMMON TO REGION EXCEPT WHERE OTHER PLANT MATERIAL IS CALLED FOR.
- 2. ALL HEAVILY PLANTED AREAS TO RECEIVE AUTOMATIC PERMANENT IRRIGATION. CONTRACTOR TO PROVIDE DESIGN DRAWINGS FOR APPROVAL PRIOR TO INSTALLATION.
- . ALL TREES AND SHRUBS TO BE PLANTED IN MULCH BEDS WITH EDGE STRIPS TO SEPARATE TURF GRASS
- 4. GRASS & IRRIGATION TO EXTEND FROM PROPERTY LINES TO BACK OF LOCAL SIDEWALKS AND/OR
- INSTALL 1 1/2" DIA. PVC PIPE SLEEVES WHERE IRRIGATION LINES CROSS OR ARE UNDER PAVEMENT.
- FOR ANY LANDSCAPE AREA SO DESIGNATED TO REMAIN WHETHER ON OR OFF SITE, REMOVE WEEDS, ROCKS, CONSTRUCTION ITEMS, ETC., THEN SCARIFY AREA, RESEED, AND FERTILIZE. R.O.W., CURB AND GUTTERS ARE TO BE CLEANED OF DEBRIS.
- FINISHED GRADES IN LANDSCAPE ISLANDS SHALL BE INSTALLED SO THAT THEY ARE 1" LOWER THAN THE TOP OF THE SURROUNDING CURB.
- 8. PROVIDE A WEED MAT FOR ALL PLANTING AREAS.
- . FOR ANY TREE LOCATED NEAR A DRIVEWAY, PRUNE LOWER BRANCHES TO PROVIDE A MINIMUM 10'-0" HIGH CLEAR SIGHT LINE FROM GRADE.
- 10. FOR EXISTING VEGETATION TO BE REMOVED, SEE DEMOLITION PLAN (D1.0).

*Velopme

PROVIDED

YES


YES

MIN. 2'-9";

REQUIRED

YES

10' PLANTING



SCALE: 1" = 20'-0" **REVISIONS** 1 11-30-21 PER BOROUGH & COUNTY COMMEN

ARCHITECT: LE DRAFTSMAN: CWT

CHECKED BY: CAD 7n2-R



SHEET 10 of 16




SITE LOCATION MAP SCALE: 1"=2,000'

LEGEND PROPOSED CONTOUR ---- 773 ---- EXISTING CONTOUR LIMIT OF DISTURBED AREA NPDES PERMIT BOUNDARY AREA SOIL BOUNDARY HARLETON CHANNERY SILT LOAM, 3 TO 8 PERCENT SLOPES URBAN LAND-UDULTS COMPLEX SOIL BORING

STORMWATER FACILITIES: OWNER: LEEMILTS PETROLEUM, INC. RESPONSIBLE PARTY: AUTOZONE DEVELOPMENT, LLC SEE STORMWATER FACILITY OPERATION AND MAINTENANCE PLAN ON THIS SHEET.

31,504 Sq.Ft. WORK AREA EXISTING IMPERVIOUS AREA: 26,597 Sq.Ft. PROPOSED IMPERVIOUS AREA: TOTAL PROPERTY AREA: 37,581 Sq.Ft. 0.9 ACRES 42,275 Sq.Ft. LIMITS OF DISTURBANCE: 1.0 ACRES NPDES PERMIT BOUNDARY: 45,690 Sq.Ft.



1.0 ACRES

MAINTENANCE NOTE: AS PER THE APPROVED STORMWATER MANAGEMENT PLAN, ALL STORMWATER MANAGEMENT SYSTEMS ARE CONSIDERED A "CRITICAL STAGE" ELEMENT AND THE THE MUNICIPALITY SHALL HAVE THE RIGHT OF ACCESS TO THE IMPLEMENTATION/CONSTRUCTION OF THE SYSTEM SHALL BE MONITORED BY A LICENSED PROFESSIONAL OR DESIGNEE. **GRAPHIC SCALE** ON-SITE STORMWATER MANAGEMENT FACILITIES FOR THE GENERAL CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT (RECORD DRAWINGS), AS PREPARED BY A PA-LICENSED LAND RIGHT OF INSPECTION AND MAINTENANCE. IN THE EVENT THAT SURVEYOR, OF ALL STORMWATER MANAGEMENT FACILITIES INCLUDED IN THE APPROVED STORMWATER MANAGEMENT PLAN. THE OWNER, ASSIGNS OR HEIRS DO NOT ADEQUATELY MAINTAIN COST IS TO BE INCLUDED IN THE BID THE FACILITY, THE OWNER, ASSIGNS OR HEIRS SHALL REIMBURSE A PA-REGISTERED PROFESSIONAL ENGINEER IS TO PROVIDE A CERTIFICATE OF COMPLETION, VERIFYING THAT ALL PERMANENT THE MUNICIPALITY FOR ALL COSTS ASSOCIATED WITH SAID (IN FEET STORMWATER FACILITIES HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS. MAINTENANCE. THE AFOREMENTIONED RIGHTS GRANTED TO 1 inch = 20 ft.AS-BUILT (RECORD DRAWINGS), CERTIFICATE OF COMPLIANCE, AND AN EXPLANATION OF ANY DISCREPANCIES WITH THE THE MUNICIPALITY IN NO WAY DIMINISH THE RESPONSIBILITY OF THE OWNER, ASSIGNS OR HEIRS OF SAID MAINTENANCE, APPROVED DESIGN ARE TO BE SUBMITTED TO THE TOWNSHIP FOR REVIEW, APPROVAL, AND THE RELEASE OF POSTED FINANCIAL AND NO LIABILITY WILL BE ASSUMED BY THE MUNICIPALITY OR SECURITY (PERFORMANCE GUARANTEE). OUTLINED BELOW. ITS REPRESENTATIVES ASSOCIATED WITH THE REQUIRED ACCESS ST. CLAIR: 20202272148 FOR MAINTENANCE AND INSPECTION PURPOSES. EAST NORWEGIAN: 20202272149 **CALL BEFORE YOU DIG!** STORMWATER MANAGEMENT SYSTEMS: PENNSYLVANIA LAW REQUIRES OWNER: LEEMILTS PETROLEUM, INC. 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING RESPONSIBLE PARTY: AUTOZONE DEVELOPMENT, LLC DAYS IN DESIGN STAGE - STOP CALL PENNSYLVANIA ONE CALL SYSTEM, INC DEVICES. 1-800-242-1776 AND/OR OUTLET STRUCTURES. OWNER GRANTS A BLANKET EASEMENT FOR ACCESS TO SITE FOR STORMWATER INSPECTION & MAINTENANCE. WORKING ORDER: INV. (A)=770.39 INV. (B)=770.34 INV. (C) & (D)=769.8 INTENDED. TOP: 773.78 (MATCH EXIST.) INV.: 771.15 (15"Ø IN-NEW) INV.: 770.98 (MATCH EXIST.) PennDOT TYPE 'M' INLET, SEE DETAIL ON SHEET PCSM2 LIMIT SIGN INV.: 773.71 (15" OUT) DISCHARGE POINT #001 BOROUGH OF ST. CLAIR ZONED "A-1" w/ADS FLEXSTORM PURE NLET FILTER, BMP #3 SEE DETAIL ON SHEET PCSM2 50 LF OF 15"Ø RCP PIPE @ 1.7% SLOPE PIPE Q 1.0% SLOPE BENCHMARK UTLET STRUCTURE BMP #5 MAG NAIL ST. CLAIR ELÈV.=784.82 INV.: 773.20 (15" IN) INV.: 773.20 (15" IN) INV.: 772.00 (15" OUT) SUMP: 771.80 PennDOT TYPE 'M' INLET, SEE DETAIL ON SHEET PCSM2 \ 61 LF OF 15"Ø HDPE 30° ELBOW 84 LF OF 15"Ø HDPE INV.: 773.51 (15" IN) PIPE @ 1.0% SLOPE INV.: 773.51 (15" OUT) ennDOT TYPE 'C' INLET w/ADS FLEXSTORM PURE INLET FILTER, BMP #2 BOROUGH OF ST. CLAIR SEE DETAIL ON SHEET PCSM2 ZONED "C-2" 57 LF OF 15"Ø HDPE FACILITIES. PIPE @ 0.5% SLOPE YARD INLET No. 1 TOP: 776.75 INV.: 774.58 (15" OUT) 2'x2' YARD INLET, SEE DETAIL ON SHEET PCSM2 BERKSHIRE CONSTR CO INC PID 62-05-0038.000 INV.: 773.80 (15" OUT) N/F SKAD SOLUTIONS LLC PennDOT TYPE 'M' INLET, DBV 2528 PG 1452 w/ADS FLEXSTORM PURE 51 ANN STREET INLET FILTER, BMP #1 BLDG. AREA = 7,382 SF SEE DETAIL ON SHEET PCSM2 TOWNSHIP OF EAST NORWEGIAN PARKING SPACES = 37 ZONED "C-3" FINISH FLOOR ELEV. = 779.30 303 HAYCOCK VIEW DRIVE PERKASIE, PA 18944 VEGETATED SWALE BMP #4 SEE DETAIL ON SHEET PCSM DISCHARGE POINT #002 INV.(A)=772.38 INV.(B)=771.93 INV.(C)= 771.73 SEE PLANS PREPARED BY WOOSTER & ASSOCIATES FOR ∼ PPL UP# INFORMATION REGARDING WORK 43281S50568 WITHIN PennDOT RIGHT-OF-WAY PID 08-02-001.001 N/F LOWE'S HOME CENTERS, INC FINGERDRAIN (TYP.), OWNER: JOANN T. & THOMAS SEE DETAIL ON SHEET C1.1 DBV 0093 PG 104 391 POTTSVILLE ST CLAIR HWY 56 N. SECOND STREET ST. CLAIR, PA 17970 TOWNSHIP OF EAST NORWEGIAN PID 08-07-0015.001 ZONED "C-3" N/F JOANN BRENNAN & THOMAS P BRENNAN DBV 2507 PG 1460 OWNER: ROBERT SEITZINGER LOWES HOME CENTERS, INC. 435 POTTSVILLE-ST CLAIR HIGHWAY TAX DEPT. 1000 LOWES BOULEVARD TOWNSHIP OF EAST NORWEGIAN MOORESVILLE, NC 28117

ZONED "C-3"

STORMWATER FACILITY OPERATION **& MAINTENANCE PLAN**

THIS STORMWATER FACILITY MAINTENANCE PLAN WAS DEVELOPED TO ENSURE CONTINUED OPERATION OF ALL STORMWATER MANAGEMENT FACILITIES. THE CORRECTIVE ACTIONS ARE NOT LIMITED TO THOSE

RESPONSIBLE PARTY REFERS TO THE INDIVIDUAL/ENTITY ULTIMATELY RESPONSIBLE FOR THE STORMWATER FACILITIES CONDITIONS AND FUNCTIONS. FOR THE REFERENCED PROJECT, AUTOZONE DEVELOPMENT, LLC WILL BE CONSIDERED AS THE RESPONSIBLE PARTY FOR MAINTENANCE OF THE STORMWATER FACILITIES.

THE FOLLOWING IS A LIST OF ITEMS THAT SHALL BE INSPECTED AND CORRECTIVE ACTION TAKEN BY THE OWNER:

- STORM SEWERS, GUTTERS, SWALES, AND OTHER CONVEYANCE
- VEGETATED SWALE, INLETS AND OTHER STORMWATER CATCHMENTS
- ACCESSES FOR MAINTENANCE.

THE FOLLOWING ACTIONS WILL BE TAKEN BY THE OWNER TO ENSURE THE FACILITIES ILLUSTRATED ON THE PLAN AND IDENTIFIED ABOVE REMAIN IN

- REPLACE AND/OR REPAIR FACILITIES TO REMAIN FUNCTIONING AS
- REMOVE SILT TRASH AND OTHER DEBRIS IN THE INLETS, STORM SEWERS, STORMWATER MANAGEMENT OUTLET STRUCTURE AND ALL
- OTHER CONVEYANCE, CATCHMENTS AND OUTLET STRUCTURES. • REPAIR AND/OR REPLACE THE INLETS, STORM SEWERS AND ALL OTHER
- CONVEYANCE, CATCHMENTS AND OUTLET STRUCTURES.
- DISPOSE SILT, DEBRIS AND TRASH IN A MANNER WHICH WILL NOT ADVERSELY AFFECT THE ENVIRONMENT.
- REPLACE ERODED MATERIAL AND REVEGETATE ERODED AREAS. SEED AND/OR MULCH DISTURBED AREAS.

SEMI-ANNUAL INSPECTIONS WILL BE CONDUCTED BY AT LEAST TWO (2) PEOPLE ON OR BEFORE MARCH 1 AND OCTOBER 1 EACH YEAR. ADDITIONAL INSPECTIONS WILL BE REQUIRED IF THE STORMWATER FACILITIES APPEAR TO MALFUNCTION OR DO NOT FUNCTION PROPERLY. COPIES OF ALL INSPECTION REPORTS SHALL BE FILED WITH THE MUNICIPALITY WITHIN FOURTEEN (14) CALENDAR DAYS AFTER SAID INSPECTIONS ARE PERFORMED. CORRECTIVE ACTIONS MUST BE UNDERTAKEN WITHIN THIRTY (30) DAYS OF DISCOVERING DEFICIENCIES. THESE CORRECTIVE ACTIONS ARE REQUIRED TO ENSURE CONTINUED OPERATION OF THE STORMWATER FACILITIES. ANY DEFICIENCIES NOTED IN THE ITEMS INSPECTED BY THE OWNER MUST BE DOCUMENTED AND THE APPROPRIATE CORRECTIVE ACTIONS UNDERTAKEN TO REMEDIATE THE DEFICIENCIES. ANY AND ALL CORRECTIVE ACTIONS TAKEN SHALL BE PROPERLY DOCUMENTED AND A REPORT ON SAID CORRECTIONS MADE SHALL BE FILED WITH THE MUNICIPALITY WITHIN FOURTEEN (14) CALENDAR DAYS OF THE COMPLETED CORRECTIVE ACTIONS INDICATING ACTIONS TAKEN AND THAT THE STORMWATER MANAGEMENT SYSTEM IS PROPERLY OPERATING IN ACCORDANCE WITH ITS ORIGINAL DESIGN INTENT. THIS STORMWATER FACILITY MAINTENANCE PLAN IS NOT A GUARANTEE FOR THE CONTINUED FUNCTIONING OF THE STORMWATER FACILITIES NOW OR IN THE FUTURE.

THE MUNICIPALITY MAY REQUIRE THAT OTHER ITEMS BE INCLUDED IN AN AGREEMENT. THESE ITEMS WILL BE DETERMINED TO BE NECESSARY TO GUARANTEE SATISFACTORY PERFORMANCE FOR THE STORMWATER FACILITIES. THE OWNER SHALL MAINTAIN ALL STORMWATER FACILITIES IN ACCORDANCE WITH THE APPROVED MAINTENANCE SCHEDULE AND SHALL KEEP ALL STORMWATER FACILITIES MAINTAINED IN A SAFE AND ATTRACTIVE MANNER. THE OWNER SHALL CONVEY TO THE MUNICIPALITY EASEMENTS AND/OR RIGHTS-OF-WAY TO ASSURE ACCESS FOR PERIODIC INSPECTIONS. THE OWNER SHALL KEEP ON FILE WITH THE MUNICIPALITY THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE PERSON, COMPANY OR AGENT RESPONSIBLE FOR MAINTENANCE ACTIVITIES. THE OWNER SHALL ALSO KEEP ON FILE WITH THE MUNICIPALITY AS-BUILT DRAWINGS OF ALL STORMWATER FACILITIES. IN THE EVENT OF ANY CHANGES, THE NEW INFORMATION MUST BE SUBMITTED TO THE MUNICIPALITY WITHIN FOURTEEN (14) CALENDAR DAYS OF THE CHANGE. THE OWNER SHALL ESTABLISH ANY SPECIAL MAINTENANCE FUNDS OR OTHER FINANCING RESOURCES IN ACCORDANCE WITH THE APPROVED MAINTENANCE PLAN. IF THE OWNER FAILS TO MAINTAIN THE STORMWATER FACILITIES, FOLLOWING DUE NOTICE (I.E. 30 DAYS) BY THE LOCAL MUNICIPALITY TO CORRECT ANY DEFICIENCIES, THE MUNICIPALITY MAY PERFORM THE NECESSARY MAINTENANCE OR CORRECTIVE ACTION. THE OWNER MUST REIMBURSE THE MUNICIPALITY FOR ALL COSTS ASSOCIATED WITH THE REQUIRED MAINTENANCE AND/OR CORRECTIVE ACTION OF THE STORMWATER

LAND OWNER:

LEEMILTS PETROLEUM, INC. 292 MADISON AVENUE, 9th FLOOR NEW YORK, NY 10017-6318 (646) 349-0721 JASON OLSEN, SR. DIRECTOR REAL ESTATE

LESSEE/DEVELOPER:


AUTOZONE DEVELOPMENT, LLC PROPERTY MANAGEMENT DEPT. 8700 123 SOUTH FRONT STREET P.O. BOX 2198 MEMPHIS, TN 38103 (901) 495-7625 KEVIN MURPHY, PRE-CONSTRUCTION SPECIALIST

SURVEYOR:

VALLEY LAND SERVICES, LLC 4383 HECKTOWN ROAD BETHLEHEM, PA 18020 (610) 365-2907 GREGORY C. NOLL, PLS, PA LIC. No. SU075048

ENGINEER:

MDM SURVEYORS & ENGINEERS, LLC 375 NORTHGATE DRIVE WARRENDALE, PA 15086 (724) 934-2810 EUGENE S. DVORCHAK, PE, PA LIC. No. PE052940E




SCALE: 1" = 20'-0" REVISIONS 1 11-30-21 PER BOROUGH & COUNTY COMMEN

ARCHITECT: LE DRAFTSMAN: CWT

CHECKED BY: CAD

6-25-2021 PROTOTYPE SIZE 7n2-R







SCALE: AS NOTED REVISIONS 11-30-21 PER BOROUGH & COUNTY COMMENT

ARCHITECT: LE DRAFTSMAN: CWT

> DATE 6-25-2021



THE OVERALL SITE-WORK GENERALLY CONSISTS OF EARTHMOVING ACTIVITIES FOR APPROXIMATELY 1.0± ACRES OF DISTURBED AREA TO PERFORM THE Proposed grading and construction for the project. It is proposed to approximately proceed with the project in the following sequence:

- STAKE OUT THE LIMIT OF DISTURBANCE (LOD) FOR THE ACTIVE PORTION OF THE PROJECT. FLAG THE LOD PRIOR TO ANY EARTH DISTURBANCE.
- INSTALL ALL COMPOST FILTER SOCKS (SILTSOXX™) PERIMETER PROTECTION AS SHOWN ON THE EROSION AND SEDIMENTATION CONTROL PLAN
- CLEAR AREA FOR ROCK CONSTRUCTION ENTRANCE AND CONSTRUCT TEMPORARY ROCK CONSTRUCTION ENTRANCE ALONG POTTSVILLE ST. CLAIR HIGHWAY, AS SHOWN ON THE PLAN. ANN STREET DRIVEWAY IS NOT TO BE USED AS A CONSTRUCTION ENTRANCE.
- CLEAR AND GRUB WORK AREA WITHIN THE IDENTIFIED LIMITS OF DISTURBANCE.
- PROCEED WITH DEMOLITION OF SITE IMPROVEMENTS NOT TO REMAIN FOR THE ACTIVE PORTION OF THE PROJECT.
- STRIP AND STOCKPILE SPOIL MATERIAL IN LOCATION IDENTIFIED ON THE EROSION AND SEDIMENTATION CONTROL PLAN. PLACE PERIMETER PROTECTION ON DOWNSLOPE SIDE OF THE SPOIL STOCKPILE AND COMPLETE PLACEMENT OF COMPOST FILTER SOCKS (SILTSOXX™) PROTECTING THE STOCKPILE AREA IMMEDIATELY AFTER STOCKPILING MATERIAL. PROVIDE ANY ADDITIONAL EROSION AND SEDIMENTATION CONTROL AS NEEDED.
- PROCEED WITH GRADING OPERATIONS. GRADED SLOPES SHOULD BE SEEDED AND MULCHED, AS SOON AS PRACTICAL, IN REGULAR, 10-FOOT VERTICAL INCREMENTS, EROSION CONTROL BLANKETS (ECB) MUST BE INSTALLED ON SLOPES AS SOON AS THE SLOPE IS AT GRADE. CESSATION OF ACTIVITY FOR FOLIR (4) DAYS OR LONGER REQUIRES STABILIZATION. IN NO CASE SHOULD AN AREA EXCEPTING 15,000 SE, WHICH IS TO BE STABILIZED BY VEGETATION, REACH FINAL GRADE WITHOUT BEING SEEDED AND MULCHED.
- PLACE STONE SUBBASE FOR AREAS TO BE PAVED.
- CONSTRUCT STORMWATER CONVEYANCE SYSTEMS. LIMIT DAILY TRENCH EXCAVATION AND STORM LINE INSTALLATION TO THE LENGTH OF PIPE PLACEMENT, BEDDING, AND BACKFILLING THAT CAN BE COMPLETED THE SAME DAY (WEATHER PERMITTING). NOTE THAT ALL STORM LINES MUST BE INSTALLED FROM DOWNSTREAM TO UPSTREAM. IF REQUIRED, TRENCH PLUGS AS PER DETAIL ARE TO BE INSTALLED PER PADEP CHAPTER 102 REQUIREMENTS. IMPORTANT: STORMWATER RUNOFF IS NOT TO BE DIRECTED TO UNPROTECTED STORMWATER CONVEYANCE SYSTEMS UNTIL THE
- PLACE INLET PROTECTION ON ALL INSTALLED ONSITE INLETS WITHIN THE WORK LIMITS. IMPORTANT: STORMWATER RUNOFF IS NOT TO BE DIRECTED.
- TO UNPROTECTED STORMWATER CONVEYANCE SYSTEMS UNTIL THE SITE IS AT FINAL GRADE AND STABILIZED BRING SITE TO FINAL GRADE AND PAVE ALL PARKING AREAS AND ACCESS DRIVES RECEIVING INITIAL PAVING. ALL REMAINING AREAS SHALL RECEIVE
- TEMPORARY OR PERMANENT SEEDING OR LANDSCAPING IMPROVEMENTS. . UTILITIES SERVICING THE SITE THAT ARE WITHIN THE DEVELOPMENT AREA CAN BE CONSTRUCTED WITHIN THE LOCATION THEY ARE TO BE INSTALLED.
- STRUCTURAL AND BUILDING CONSTRUCTION MAY COMMENCE AFTER AREAS REACH FINAL GRADE ELEVATION.
- . BRING THE SITE TO FINAL GRADE AND PAVE REMAINING PARKING AREAS AND ACCESS DRIVES. ALL REMAINING AREAS THAT WILL NOT RECEIVE LANDSCAPING IMPROVEMENTS SHALL RECEIVE PERMANENT SEEDING AND ALL SEEDED AREAS ARE TO BE MULCHED.
- AFTER MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER STABILIZATION IS ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING THE REMOVAL OF THE CONTROLS MUST BE IMMEDIATELY STABILIZED. FINAL STABILIZATION IS DEFINED AS THE ACHIEVEMENT OF A MINIMUM 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES ON ALL CONTRIBUTORY

CONSTRUCTION SEQUENCE NOTES:

- IN ADDITION TO THE PERMIT APPLICANT, ANYONE PERFORMING ACTIVITIES RESULTING IN ANY EARTH DISTURBANCE IS REQUIRED TO BE ADDED TO THE NPDES PERMIT AS A CO-PERMITTEE. ALL PARTIES RESPONSIBLE FOR THE EXCAVATION OF SITE MATERIALS OR THE IMPORT OF FILL MATERIALS ARE RESPONSIBLE TO ENSURE THAT "ENVIRONMENTAL DUE DILIGENCE" IN THE DETERMINATION OF CLEAN FILL MATERIAL IS EITHER REMOVED FROM THE SITE OR USED AS FILL FOR THE SITE. ANY MATERIAL IDENTIFIED AS HAZARDOUS MUST BE DISPOSED IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL GUIDELINES AND
- A. ENVIRONMENTAL DUE DILIGENCE INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS ELECTRONIC DATA BASE SEARCHES, REVIEW OF OWNERSHIP AND USE HISTORY OF PROPERTY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS.
- NO BUILDING MATERIALS, WASTES, OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED OR DISCHARGED AT THE SITE. THE FOLLOWING DEFINE WHAT SHOULD BE CONSIDERED "CONSTRUCTION WASTE" AND "CLEAN FILL": A. CONSTRUCTION WASTE - INCLUDES BUT IS NOT LIMITED TO, EXCESS SOIL MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER,
- SANITARY WASTES, ETC. THAT COULD ADVERSELY IMPACT WATER QUALITY. B. CLEAN FILL - UNCONTAMINATED, NON-WATER-SOLUBLE, NON-DECOMPOSABLE, INERT. SOLID MATERIAL. THIS INCLUDES SOIL ROCK STONE DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK, OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. IT DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE SURFACE WATERS UNLESS OTHERWISE AUTHORIZED, MILLED ASPHALT, OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.
- COMPOST FILTER SOCKS (FILTREXX SILTSOXX™) AND ANY OTHER FILTREXX BMPS EMPLOYED AS PART OF THE EROSION AND SEDIMENTATION CONTROL PLAN FOR THE PROJECT MUST FOLLOW THE MANUFACTURER'S DISPOSAL/RECYCLING INSTRUCTIONS FOR EACH SPECIFIC BMP UTILIZED THROUGHOUT THE PROJECT'S CONSTRUCTION AND EARTHMOVING OPERATIONS. EROSION AND SEDIMENTATION CONTROLS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE WITHIN THE
- CONTRIBUTORY DRAINAGE AREAS OF THOSE CONTROLS. AFTER FINAL SITE STABILIZATION IS ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS MUST BE IMMEDIATELY STABILIZED. FINAL STABILIZATION IS DEFINED AS THE ACHIEVEMENT OF A MINIMUM UNIFORM
- 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES HAS BEEN ACHIEVED ON ALL CONTRIBUTORY DRAINAGE AREAS. ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 4 DAYS MUST BE TEMPORARILY STABILIZED. DISTURBED AREAS THAT ARE EITHER AT FINISHED GRADE, OR ANY GRADED AREA OF 15,000 FT2 OR MORE REACHES FINAL GRADE, OR WILL NOT BE DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

PA DEP STANDARD E&S PLAN NOTES

- ALL EARTH DISTURBANCES. INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.
- AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION DISTRICT TO AN ON-SITE PRECONSTRUCTION MEETING.
- AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED. THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPLEMENTATION AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS AND OTHER OBJECTIONABLE
- CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE
- GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN.
- AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN MAP(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR
- IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION. THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT.
- . ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET. SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.
- ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED. . THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE
- PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO 3. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED
- I. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEANOUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL
- TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED. 5. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION. THE INSPECTIONS AND
- MAINTENANCE DATA SHALL BE LOGGED ONTO THE DEPARTMENT FORM 3150-FM-BWEW0083 (MOST CURRENT VERSION TO BE USED).
- . SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- 3. AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES 6 TO 12 INCHES ON COMPACTED SOILS PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL
- TO SUPPORT BUILDING, STRUCTURES, AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES. 20. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN THICKNESS.

9. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED

- 1. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE
- WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS.
- 2. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILLS. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.

. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS.

- 24. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR
- SUBSURFACE DRAIN OR OTHER APPROVED METHOD. 5. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN.
- 6. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT
- PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
- 8. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT. 9. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR
- SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS.). AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED MMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE
- . UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR
- SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION. . FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND OR/CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES

CONCRETE WASH WATER SHALL BE HANDLED IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. IN NO CASE SHALL IT BE ALLOWED TO ENTER ANY SURFACE WATERS OR GROUNDWATER SYSTEMS.

EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS.

GENERAL SEEDING SPECIFICATIONS

THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION RECOMMENDS LISING THE PENN STATE "EROSION CONTROL AND CONSERVATION PLANTINGS ON NONCROPLAND" MANUAL AS A REFERENCE FOR SELECTION OF SPECIES, SEED SPECIFICATIONS, MIXTURES, LIMING AND ERTILIZING, TIME OF SEEDING, AND SEEDING METHODS. SPECIFICATIONS FOR THESE ITEMS MAY ALSO BE OBTAINED FROM THE PENNSYLVANIA DEPARTMENT OF TRANSPORTATION PUBLICATION 408, SECTION 804 OR BY CONTACTING THE APPLICABLE COUNTY CONSERVATION

VEGETATED AREAS WILL BE CONSIDERED PERMANENTLY STABILIZED WHEN A UNIFORM 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES IS ACHIEVED, OR THE DISTURBED AREA IS COVERED WITH AN ACCEPTABLE BEST MANAGEMENT PRACTICE ("BMP") VHICH PERMANENTLY MINIMIZES ACCELERATED EROSION AND SEDIMENTATION. UNTIL SUCH TIME AS THIS STANDARD IS ACHIEVED. INTERIM STABILIZATION MEASURES AND TEMPORARY EROSION AND SEDIMENT CONTROL BMPs THAT ARE USED TO TREAT PROJECT RUNOFF MAY NOT BE REMOVED.

TEMPORARY SEEDING SPECIFICATIONS

RELIMINARY PREPARATION: ALL AREAS THAT WILL BE SEEDED MUST BE LOOSENED USING MECHANICAL MEANS. SOIL MUST BE LOOSENED TO A DEPTH OF AT LEAST TWO-INCHES.

IME AND FERTILIZER: APPLY 1 TON OF AGRICULTURAL GRADE LIMESTONE PER ACRE AND RTILIZER AS INDICATED BY THE SOIL TEST. IN THE ABSENCE OF A SOIL TEST, APPLY AGRICULTURAL GRADE LIMESTONE AT A RATE OF 1 TON PER ACRE, AND APPLY FERTILIZER AT 500 POUNDS OF 10-10-10 FERTILIZER PER ACRE (E.G., 166.67 POUNDS NITROGEN (N), 166.67 POLINDS PHOSPHOROUS (P-O-) AND 166 67 POLINDS POTASSIUM (K-O) PER ACRE WORK LIME AND FERTILIZER INTO SOIL WHERE POSSIBLE. LIME AND FERTILIZER DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP)

FED: ALL SEED MUST BEAR A GUARANTEED STATEMENT OF ANALYSIS AND MUST BE ROPORTIONED BY WEIGHT WITH THE MINIMUM PURITY. READY GERMINATION. AND TOTAL GERMINATION OUTLINED BELOW. SEED DATA WAS OBTAINED FROM THE PADEP EROSION AND

SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.3 AND 11.4.

SPECIES	PURITY (%)	READY GERMINATION (%)	TOTAL GERMINATIO N (%)	PURE LIVE SEED ¹ SEEDING RATE (LBS/ACRE)
SPRING-SUMMER				
SPRING OATS, OR	98	85	85	64
ANNUAL RYEGRASS	95	85	85	10
SUMMER-FALL				
ANNUAL RYEGRASS, OR	95	85	85	10
WINTER RYE, OR	98	85	85	56
WINTER WHEAT	98	85	85	90
1- PURE LIVE SEED (PLS) IS THE PRODUCT OF THE PERCENTAGE OF PURE SEED TIMES				

PERCENTAGE GERMINATION DIVIDED BY 100. FOR EXAMPLE, TO SECURE THE ACTUAL PLANTING RATE FOR ANNUAL RYEGRASS, DIVIDE THE PLS SEEDING RATE OF 10 LBS/ACRE B THE PLS AS SHOWN ON THE SEED TAG. THUS, IF THE PLS CONTENT OF A GIVEN SEEDLOT IS 60%, DIVIDE 10 PLS (LBS/ACRE) BY 0.60 TO OBTAIN 16.7 LBS OF SEED REQUIRED TO PLANT ONE ACRE. ALL MIXTURES IN THIS TABLE ARE SHOWN IN TERMS OF PLS, LBS/ACRE.

MULCH: ALL SEEDED AREAS MUST BE IMMEDIATELY MULCHED TO PROMOTE ADEQUATE

FINELY BROKEN. THE STRAW MUST BE FREE FROM MATURE SEED-BEARING STALKS OR ROOTS OF PROHIBITED OR NOXIOUS WEEDS AS DEFINED BY THE PENNSYLVANIA SEED ACT OF 1947. APPLY MULCH AT A RATE OF 3 TONS PER ACRE (I.E., 140 POUNDS PER 1,000 SQUARE FEET OR 1,240 POUNDS PER 1,000 SQUARE YARDS). THE MULCH MUST BE ANCHORED IMMEDIATELY AFTER APPLICATION. A TRACTOR-DRAWN IMPLEMENT MAY BE USED TO ANCHOR THE MULCH INTO THE SOIL. THIS METHOD IS LIMITED TO SLOPES SHALLOWER THAN OR EQUAL TO 3:1 AND

ÆGETATIVE COVER. USE CLEAN OAT OR WHEAT STRAW, FREE OF WEEDS, NOT CHOPPED OF

PERMANENT SEEDING SPECIFICATIONS

THE EQUIPMENT MUST BE OPERATED ON THE CONTOUR.

RELIMINARY PREPARATION: GRADE AS NECESSARY TO BRING SUBGRADE TO A TRUE. SMOOTH LOPE PARALLEL TO AND SIX INCHES BELOW FINISH GRADE (I.E., 8 INCHES FOR BASIN MBANKMENTS WHEN APPLICABLE). PLACE TOPSOIL OVER SPECIFIED AREAS. TOPSOIL SHOULD E AT A GREATER THICKNESS (I.E., GENERALLY 6 TO 8 INCHES) THAN THE FINISHED GRADE TO ALLOW FOR SETTLEMENT AND LIGHT ROLLING. THE FINAL COVER MUST CONFORM TO THE PROPOSED LINES, GRADES AND ELEVATIONS.

IME AND FERTILIZER: APPLY AGRICULTURAL-GRADE LIMESTONE AND FERTILIZER AS PER THE COMMENDATIONS INDICATED BY THE SOIL TEST. IN THE ABSENCE OF A SOIL TEST, APPLY AGRICULTURAL GRADE LIMESTONE AT A RATE OF 6 TONS PER ACRE, AND APPLY 1,000 POUNDS OF | PERMIT AS A CO-PERMITTEE 10-20-20 FERTILIZER (E.G., 200 POUNDS NITROGEN (N), 400 POUNDS PHOSPHORUS (P₂O₅), AND 400 POLINDS POTASSILIM (K.O.) PER ACRE) WORK LIME AND FERTILIZER INTO SOIL WHERE POSSIBLE LIME AND FERTILIZER DATA WAS OBTAINED FROM THE PADEP FROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLE 11.2. NOTE: A OMPOST BLANKET WHICH MEETS THE STANDARDS OF CHAPTER 11 OF THE *PADEP EROSION ND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL MARCH 2012* (BMP MANUAL) MAY BE

THE FERTILIZER AND LIMESTONE MUST BE THOROUGHLY INCORPORATED INTO THE SOIL BY 4ECHANICAL MEANS (E.G., ROTOTILLING) TO A MINIMUM DEPTH OF 4 INCHES.

UBSTITUTED FOR THE SOIL AMENDMENTS SHOWN IN TABLE 11.2.

THE ENTIRE SURFACE MUST THEN BE REGRADED AND ROLLED. ALL AREAS THAT WILL BE SEEDED MUST BE LOOSENED USING MECHANICAL MEANS. SOIL MUST BE LOOSENED TO A DEPTH OF AT LEAST TWO INCHES.

EED: SEEDING MUST BE CONDUCTED AS TWO SEPARATE OPERATIONS. THE FIRST SEEDING PERATION MUST BE COMPLETED PRIOR TO STARTING THE SECOND SEEDING OPERATION. THE SECOND SEEDING MUST BE CONDUCTED IMMEDIATELY AFTER THE FIRST SEEDING AND AT RIGHT ANGLES TO THE FIRST SEEDING. THE SEEDS MUST BE LIGHTLY RAKED INTO THE SOIL.

BY WEIGHT WITH THE MINIMUM PURITY, READY GERMINATION, AND TOTAL GERMINATION

OUTLINED BELOW. SEED DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.3 AND 11.4.					
SPECIES	PURITY (%)	READY GERMINATION (%)	TOTAL GERMINATIO N (%)	PURE LIVE SEED ¹ SEEDING RATE (LBS/ACRE)	

31 20123	(%)	(%)	N (%)	(LBS/ACRE)			
SPRING-SUMMER	SPRING-SUMMER						
REDTOP	92	80	80	3			
TALL RYEGRASS ²	95	80	80	60			
ANNUAL RYEGRASS	95	85	85	10			
SUMMER-FALL	SUMMER-FALL						
REDTOP	92	80	80	3			
TALL FESCUE ²	95	80	80	60			
WINTER RYE	98	85	85	56			

- I- PURE LIVE SEED (PLS) IS THE PRODUCT OF THE PERCENTAGE OF PURE SEED TIMES PERCENTAGE GERMINATION DIVIDED BY 100. FOR EXAMPLE, TO SECURE THE ACTUAL PLANTING RATE FOR REDTOP, DIVIDE THE PLS SEEDING RATE OF 3 LBS/ACRE BY THE PLS SHOWN ON THE SEED TAG. THUS, IF THE PLS CONTENT OF A GIVEN SEEDLOT IS 60%, DIVIDE 3 PLS BY 0.60 TO OBTAIN 5.0 LBS OF SEED REQUIRED TO PLANT ONE ACRE. ALL MIXTURES IN THIS TABLE ARE SHOWN IN TERMS OF PLS, LBS/ACRE.
- 2- USE KENTUCKY 31 TALL FESCUE FOR LOW MAINTENANCE SITES OR TURF-TYPE TALL FESCUE FOR HIGH MAINTENANCE SITES.
- ULCH: ALL SEEDED AREAS MUST BE IMMEDIATELY MULCHED TO PROMOTE ADEQUATE ÆGETATIVE COVER、USE CLEAN OAT OR WHEAT STRAW, FREE OF WEEDS, NOT CHOPPED OR FINELY BROKEN. THE STRAW MUST BE FREE FROM MATURE SEED-BEARING STALKS OR ROOTS OF PROHIBITED OR NOXIOUS WEEDS AS DEFINED BY THE PENNSYLVANIA SEED ACT OF 1947.

APPLY MULCH AT A RATE OF 3 TONS PER ACRE (I.E., 140 POUNDS PER 1,000 SQUARE FEET OR 1,240 POUNDS PER 1,000 SQUARE YARDS). THE MULCH MUST BE ANCHORED IMMEDIATELY AFTER APPLICATION. A TRACTOR-DRAWN IMPLEMENT MAY BE USED TO ANCHOR THE MULCH INTO THE SOIL. THIS METHOD IS LIMITED TO SLOPES SHALLOWER THAN OR EQUAL TO 3:1 AND THE EQUIPMENT MUST BE OPERATED ON THE CONTOUR.

STEEP SLOPE SEEDING SPECIFICATIONS FEEP SLOPE SEEDING MIXTURE (FOR USE ON GRADES AT 3:1 OR GREATER SLOPES): ALL SLOPES REATER THAN 3:1 SHALL BE COVERED WITH AN EROSION CONTROL BLANKET IN ADDITION TO

WHEN CONDITIONS PERMIT, THE FOLLOWING SEEDING MIXTURE CAN BE UTILIZED ON STEEP SLOPES. SEED DATA WAS OBTAINED FROM THE PADEP EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP) MANUAL, TABLES 11.4 AND 11.5.

ECEIVING A GRASS SEEDING MIXTURE.

SPECIES	PURITY (%)	READY GERMINATION (%)	TOTAL GERMINATIO N (%)	PURE LIVE SEED ¹ SEEDING RATE (LBS/ACRE)
ANNUAL RYEGRASS	95	85	85	10
BIRDSFOOT TREFOIL	98	60	80	6
TALL FECUE	95	80	80	30

 PURE LIVE SEED (PLS) IS THE PRODUCT OF THE PERCENTAGE OF PURE SEED TIME PERCENTAGE GERMINATION DIVIDED BY 100. FOR EXAMPLE, TO SECURE THE ACTUAL PLANTING RATE FOR ANNUAL RYEGRASS, DIVIDE THE PLS SEEDING RATE OF 10 LBS/ACRE BY THE PLS AS SHOWN ON THE SEED TAG. THUS, IF THE PLS CONTENT OF A GIVEN SEEDLOT IS 60%, DIVIDE 10 PLS (LBS/ACRE) BY 0.60 TO OBTAIN 16.7 LBS OF SEED REQUIRED TO PLANT ONE ACRE. ALL MIXTURES IN THIS TABLE ARE SHOWN IN TERMS OF PLS. LBS/ACRE.

MAINTENANCE PROGRAM

MAINTAIN TEMPORARY CONTROL MEASURES THROUGHOUT THE PROJECT PERIOD AS OUTLINED IN THE "MAINTENANCE SCHEDULE" SHOWN ON THE EROSION AND SEDIMENTATION CONTROL PLANS AND NARRATIVE.

T SHALL BE THE RESPONSIBILITY OF THE PERMITTEE TO PERFORM INSPECTIONS OF ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL MEASURES TO ENSURE THAT THEY ARE WORKING PROPERLY. THESE INSPECTIONS MUST BE CONDUCTED WEEKLY, AND DURING OR IMMEDIATELY AFTER EVERY RUNOFF EVENT. INSPECTIONS WILL BE LOGGED ONTO DEPARTMENT FORM 3150-FMBWEW0083 (MOST RECENT VERSION) AND WILL BE KEPT ON SITE AT ALL TIMES. THE INSPECTION WILL INCLUDE, BUT NOT BE LIMITED TO

1) INSPECT ALL CONTROLS (INCLUDING COMPOST FILTER SOCKS) AND REPAIR OR REPLACE AS NEEDED. 2) INSPECT ALL SLOPES FOR SIGNS OF EROSION AND/OR SEDIMENTATION, AND REPAIR AS NEEDED. 3) INSPECTION OF ALL SEEDED AREAS FOR SIGNS OF EROSION.

- $\acute{ ext{P}}$) inspection of all inlet protection until the contributory drainage area to the corresponding inlet is stabilized. 5) THE CLEANING AND REPAIR OF THE ROCK CONSTRUCTION ENTRANCE.
- REPAIRS AND MAINTENANCE FOR ANY EROSION AND SEDIMENTATION CONTROL DEVICES MUST BE PERFORMED AS SOON AS THE OPERATIONS CAN BE SAFELY AND PRACTICALLY CARRIED OUT.

AN ADEQUATE SUPPLY OF ADDITIONAL EROSION/SEDIMENTATION CONTROL MATERIALS (E.G., STRAW BALES, EROSION NETTING, PLASTIC COVERING, WIRE MESH, SAND AND BURLAP, SANDBAGS, ROCKS AND GRAVEL) MUST BE STOCKPILED ON-SITE. THESE SUPPLIES MUST BE USED FOR EMERGENCY REPAIRS TO/OR REPAIRS OF EXISTING SOIL EROSION AND SEDIMENTATION CONTROLS.

MAINTENANCE OF PERMANENT CONTROLS THE OWNER/DEVELOPER WILL MAINTAIN PERMANENT CONTROL FACILITIES.

EANING FREQUENCIES ARE SPECIFIED WITHIN THE MAINTENANCE SCHEDULE. SILT AND SEDIMENT REMOVED FROM ALL CONTROL MEASURES SHOULD BE MIXEI WITH SOIL DURING EARTHWORK AND PROPERLY DISPOSED OF ON-SITE.

ON-SITE SEDIMENT CONTROL PLAN MAINTENANCE SCHEDULE

CONTROL MEASURE	INSPECT	PROBLEMS	POSSIBLE REMEDIES (TO BE PERFORMED WITHIN 24 HOURS OR AS SOON AS SAFELY PRACTICAL.)
VEGETATION	ONCE A WEEK AND AFTER	SEDIMENT AT TOE OF SLOPE	CHECK FOR TOE OF SLOPE DIVERSION AND INSTALL IF NEEDED.
	EVERY RUNOFF EVENT	RILLS AND GULLIES FORMING	FILL RILLS AND REGRADE GULLIED SLOPES.
		BARE SOIL PATCHES	RESEED, FERTILIZE AND MULCH BARE AREAS.
COMPOST FILTER SOCK (SILTSOXX TM)	ONCE A WEEK AND AFTER EVERY RUNOFF EVENT	RUNOFF ESCAPING AROUND BARRIER	SECURELY ANCHOR WITH PROPER STAPLES. EXTEND BARRIER AS NEEDED.
		SEDIMENT LEVEL BUILDUP	REMOVE SEDIMENT WHEN LEVEL REACHES HALF (1/2) THE HEIGHT OF THE BARRIER.
INLET PROTECTION - FOR BLACKHAWK INLET FILTER MAT	ONCE A WEEK AND AFTER EVERY RUNOFF EVENT	SEDIMENT BUILD-UP REDUCING FLOW CAPACITY RESULTING IN FLOODING AROUND OR BELOW INLET -OR- COMPRESSION OF FILTER MAT	REMOVE ACCUMULATED SEDIMENT, IF FLOW CAPACITY IS STILL REDUCED OR MAT REMAINS COMPRESSED, REPLACEMENT OF FILTER MAT IS REQUIRED.
		MISSING MATERIAL	REPAIR OR REPLACE PROTECTION MATERIALS AS NEEDED.

		GENERAL MAINTENANCE	AS NEEDED, INLET FILTER MATS SHALL BE LIFTED AND RINSED OR REPLACED IF DAMAGED.
("SILT SACK" - ONLY)		WATER BY-PASSING INLET AND GRATE	REMOVE "SILT SACK" AND REMOVE SILT OR REPLACE WITH NEW "SILT SACK" OR INSTALL BLOCK AND GRAVEL PROTECTION.
PUMPED WATER FILTER	DAILY AND AFTER EACH	BAG IS HALF FULL	REPLACE BAG.
BAG	USE	BAG IS CLOGGED OR FLOW IS REDUCED	REPLACE BAG.
ROCK CONSTRUCTION ENTRANCE	DAILY AND AFTER EACH RUNOFF EVENT	LOST AND/OR DISLODGED STONES	REPLACE MISSING STONES SO AS TO MAINTAIN SPECIFIED DIMENSIONS.
		SEDIMENT DEPOSITED IN PAVED ROADWAYS	AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE RETURNED TO THE CONSTRUCTION SITE.
EROSION CONTROL	ONCE A WEEK AND AFTER	SCOUR BENEATH NETTING	RE-INSTALL PROPER ECB MATERIAL AND RE-GRADE BEDDING. MAKE SURE

BLANKETS (ECB) EVERY RUNOFF EVENT MATERIAL IS INSTALLED AND ANCHORED AS PER THE MANUFACTURER'S RECOMMENDATIONS. RE-SEED IF NECESSARY. DAILY AND AFTER EACH DAMAGED OR LEAKING DEACTIVATE WASHOUT AND REPAIR OR REPLACE IMMEDIATELY COMPOST SOCK CONCRETE WASHOUT ACCUMULATED MATERIALS | REMOVE EXCESS ACCUMULATED MATERIALS WHEN 75% CAPACITY IS REACHED.

REPLACE PLASTIC LINING WITH EACH CLEANING OF THE WASHOUT FACILITY

IN ADDITION TO THE PERMIT APPLICANT, ANYONE PERFORMING ACTIVITIES RESULTING IN ANY EARTH DISTURBANCE IS REQUIRED TO BE ADDED TO THE NPDES IMPORTANT - POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM) INSTRUMENT FILING NOTICE: THE PERMITTEE OR CO-PERMITTEE SHALL RECORD, WITH THE RECORDER OF DEEDS OFFICE, THE INSTRUMENT WITHIN 45 DAYS FROM THE DATE OF THE NPDES PERMIT ISSUANCE OR AUTHORIZATION, AND SHALL PROVIDE

THE CONSERVATION DISTRICT AND THE PADEP WRITTEN DOCUMENTATION CONTAINING THE DATE AND PLACE OF RECORDING ALONG WITH A REFERENCE TO THE

GENERAL NOTES - NPDES PERMIT REQUIREMENTS

DOCKET, DEED BOOK OR OTHER RECORD, WITHIN 90 DAYS FROM THE DATE OF THE NPDES PERMIT ISSUANCE OR AUTHORIZATION ANY PROJECT WHICH RESULTS IN EARTH DISTURBANCE ACTIVITIES THAT DISTURB EQUAL TO OR GREATER THAN ONE (1) ACRE IS SUBJECT TO PADEP APPROVAL OF COVERAGE UNDER THE GENERAL OR INDIVIDUAL NPDES PERMIT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES. ANY AND ALL CONSTRUCTION ENGAGED IN EARTH DISTURBANCES ACTIVITIES, INCLUDING DEMOLITION, UTILITY LINE CONSTRUCTION, GRADING ACTIVITIES, INSTALLATION OF STORMWATER MANAGEMENT SYSTEMS, ETC., SHALL SECURE A COPY OF THE NPDES PERMIT FOR THIS PROJECT, AND FAMILIARIZE THEMSELVES

UPON AWARD OF CONTRACT FOR ANY EARTH DISTURBANCE ACTIVITIES NOTED ABOVE, THAT CONTRACTOR SHALL BE DESIGNATED AS A CO-PERMITEE, IN ACCORDANCE WITH THE REQUIREMENTS OF PADEP, AND SHALL COMPLETE AND SUBMIT ALL APPROPRIATE FORMS AND NOTIFICATIONS, ALONG WITH THE OWNER, PRIOR TO ANY SITE MOBILIZATION

THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT), AS CO-PERMITEE, IS RESPONSIBLE FOR RECORD KEEPING AND THE RETENTION OF RECORDS OF ALL MONITORING INFORMATION, AS MAY BE REQUIRED TO COMPLETE THE NOTICE OF TERMINATION (NOT), AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT. THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED. THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT). AS CO-PERMITEE, IS RESPONSIBLE FOR ENSURING THAT A LICENSED PROFESSIONAL HAVE OVERSIGHT ALL SEED MUST BEAR A GUARANTEED STATEMENT OF ANALYSIS AND MUST BE 100% PROPORTION RESPONSIBILITIES FOR THE PROPER INSTALLATION OF BMPS IDENTIFIED IN THE PCSM PLAN PRIOR TO THE SUBMISSION OF THE NOTICE OF TERMINATION, AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT

AS NOTED IN THE OTHER SECTIONS OF THESE PLANS AND DOCUMENTS, THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT), AS CO-PERMITEE, IS RESPONSIBLE FOR CONTACTING THE AUTHORIZED CONSERVATION DISTRICT AT LEAST SEVEN (7) DAYS BEFORE CONSTRUCTION IS TO BEGIN, TO SCHEDULE A PRECONSTRUCTION CONFERENCE, AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT

THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED. THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT) SHALL COMPLETE THE NOTICE OF TERMINATION (NOT). AS REQUIRED BY THE CONDITIONS OF THE NPDES PERMIT. COMPLETE THE "VISUAL INSPECTION CHECKLIST FOR GENERAL NPDES PERMIT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES" DURING THE WEEKLY INSPECTIONS. COPIES OF THE INSPECTION REPORT MUST BE KEPT ONSITE DURING CONSTRUCTION ACTIVITIES AND AVAILABLE

IMPORTANT - AS PART OF THE COMPLETION OF THE NOTICE OF TERMINATION (NOT), AN AS-BUILT RECORD DRAWING MUST BE GENERATED. THE GENERAL CONTRACTOR (OR IF NO GENERAL CONTRACTOR IS ASSIGNED, THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT) SHALL SECURE THE AS-BUILT RECORD DRAWINGS THROUGH THE SERVICES OF A LICENSED SURVEYOR. THE AS-BUILT RECORD DRAWING SHALL ACCURATELY DEPICT THE AS-BUILT/AS-CONSTRUCTED CONDITIONS FOR ALL STORMWATER/PCSM BMP(S), RELATED STRUCTURES, AND STORMWATER CONVEYANCES IDENTIFIED IN THE PCSM PLAN AND DRAWINGS IN ADDITION TO THE AS-CONSTRUCTED GRADES AND OTHER SITE IMPROVEMENTS THE COMPLETED AS-BUILT RECORD DRAWING MUST BE SUBMITTED BY THE GENERAL CONTRACTOR (OR IE NO GENERAL CONTRACTOR IS ASSIGNED. THE PRIME CONTRACTOR RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES, AS DESIGNATED BY THE OWNER AND/OR ARCHITECT) TO THE RECORDER OF DEEDS AND PLACED WITH THE POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM) INSTRUMENT FILING NOTICE, A COPY OF THE PROJECT'S AS-BUILT RECORD DRAWING SHALL BE ATTACHED TO THE NOTICE OF TERMINATION (NOT). THE PERMITTEE SHALL RETAIN A COPY OF THE AS-BUILT RECORD DRAWINGS AND SHALL ALSO PROVIDE A COPY, AS PART OF THE APPROVED PCSM PLAN, TO THE PERSON(S) IDENTIFIED IN THE NOTICE OF TERMINATION (NOT), AS BEING RESPONSIBLE FOR THE ONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP(S). ADDITIONAL COPIES OF THE NOTICE OF TERMINATION (NOT) AND AS-BUILT RECORD DRAWING SHALL ALSO BE PROVIDED TO THE LOCAL MUNICIPALITY.

FURTHER NOTES

. IMPORTANT: STORMWATER RUNOFF IS NOT TO BE DIRECTED TO UNPROTECTED STORMWATER MANAGEMENT SYSTEM, STORMWATER CONVEYANCE SYSTEMS,

I. THE PURPOSE OF THIS EROSION AND SEDIMENTATION CONTROL PLAN IS TO MINIMIZE EXTENT AND DURATION OF EARTH DISTURBANCE, MAXIMIZE PROTECTION OF EXISTING DRAINAGE FEATURES AND VEGETATION, AND MINIMIZE SOIL COMPACTION

3. ALL PARTIES RESPONSIBLE FOR THE EXCAVATION OF SITE MATERIALS OR THE IMPORT OF FILL MATERIALS ARE RESPONSIBLE TO ENSURE THAT "ENVIRONMENTAL DUE DILIGENCE" IN THE DETERMINATION OF CLEAN FILL MATERIAL IS EITHER REMOVED FROM THE SITE OR USED AS FILL FOR THE SITE. ANY MATERIAL IDENTIFIED AS HAZARDOUS MUST BE DISPOSED IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL GUIDELINES AND REGULATIONS. A) ENVIRONMENTAL DUE DILIGENCE - INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC

OR INFILTRATION BED AREAS UNTIL THE SITE IS AT FINAL GRADE AND STABILIZED.

DRAINAGE AREAS OF THOSE CONTROLS.

DATA BASE SEARCHES, REVIEW OF OWNERSHIP AND USE HISTORY OF PROPERTY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. . NO BUILDING MATERIALS, WASTES, OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCARDED ON THE SITE. THE FOLLOWING DEFINE WHAT SHOULD BE CONSIDERED "CONSTRUCTION WASTES" AND "CLEAN FILL" A) CONSTRUCTION WASTES - INCLUDES BUT IS NOT LIMITED TO, EXCESS SOIL MATERIALS, BUILDING MATERIALS, CONCRETE WASH WATER, SANITARY WASTES, ETC. THAT COULD ADVERSELY IMPACT WATER QUALITY. B) CLEAN FILL - UNCONTAMINATED, NON-WATER-SOLUBLE, NON-DECOMPOSTABLE, INERT SOLID MATERIAL. THIS INCLUDES SOIL, ROCK, STONE DREDGED

AND IS RECOGNIZABLE AS SUCH. IT DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE SURFACE WATERS UNLESS OTHERWISE AUTHORIZED, MILLED ASPHALT, OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE. DURING UTILITY LINE CONSTRUCTION, EXCAVATE UTILITY LINE TRENCHES ONLY AS REQUIRED. LIMIT ADVANCE EXCAVATION TO A DISTANCE FOUAL TO TWO TIMES THE LENGTH OF PIPE INSTALLATION THAT CAN BE COMPLETED IN ONE DAY. LIMIT DAILY TRENCH EXCAVATION TO THE LENGTH OF PIPE PLACEMENT. PLUG INSTALLATION AND BACKFILLING THAT CAN BE COMPLETED THE SAME DAY. IF REOUIRED, TRENCH PLUGS, AS SHOWN PER DETAIL, ARE TO BE INSTALLED PER PADEP CHAPTER 102 REQUIREMENTS. WATER, WHICH ACCUMULATES IN THE OPEN TRENCH, WILL BE COMPLETELY REMOVED BY PUMPING WATER INTO A FILTER BAG IN ACCORDANCE WITH PADEP CHAPTER 102 REQUIREMENTS. ON THE DAY FOLLOWING PIPE PLACEMENT AND TRENCH

MATERIAL, USED ASPHALT, AND BRICK, BLOCK, OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE

6. COMPOST FILTER SOCKS (FILTREXX SILTSOXX™). SEDIMENTATION TRAPPä. INLETSOXXä. RUNOFF DIVERSION SOXXä. AND ANY OTHER FILTREXX BMP'S EMPLOYED AS PART OF THE EROSION AND SEDIMENTATION CONTROL PLAN FOR THE PROJECT MUST FOLLOW THE MANUFACTURER'S DISPOSAL/RECYCLING INSTRUCTIONS FOR EACH SPECIFIC BMP UTILIZED THROUGHOUT THE PROJECT'S CONSTRUCTION AND EARTHMOVING OPERATIONS.

BACKFILLING, THE DISTURBED AREA WILL BE GRADED TO FINAL GRADE, AND SEEDED AND MULCHED PER THE PERMANENT SEEDING SCHEDULE.

DURING FOUNDATION CONSTRUCTION, PUMP WATER ACCUMULATED IN OPEN TRENCHES INTO FILTER BAGS IN ACCORDANCE WITH PADEP CHAPTER 102 REQUIREMENTS. REFER TO DETAIL. WHEN FILTER BAG IS $\frac{1}{2}$ FULL IT SHOULD BE REPLACED. ANY ACCUMULATED SEDIMENTATION WILL BE MIXED WITH SOIL and properly disposed of on the site if possible or disposed of at an offsite area. The contractor shall be responsible for disposing OF ALL EXCESS MATERIAL OFF-SITE TO AN APPROVED FACILITY.

B. EROSION AND SEDIMENTATION CONTROLS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE WITHIN THE CONTRIBUTORY

9. AFTER FINAL SITE STABILIZATION IS ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS MUST BE IMMEDIATELY STABILIZED. FINAL STABILIZATION IS DEFINED AS THE ACHIEVEMENT OF A MINIMUM UNIFORM 70% VEGETATIVE COVER OF EROSION RESISTANT PERENNIAL SPECIES HAS BEEN ACHIEVED ON ALL CONTRIBUTORY DRAINAGE AREAS. 10. SEDIMENT MUST BE REMOVED FROM INLET PROTECTION AFTER EACH RUNOFF EVENT.

 ANY DISTURBED AREA ON WHICH ACTIVITY HAS CEASED AND WHICH WILL REMAIN EXPOSED FOR MORE THAN 4 DAYS MUST BE TEMPORARILY STABILIZED. DISTURBED AREAS THAT ARE EITHER AT FINISHED GRADE, OR ANY GRADED AREA OF 15,000 FT2 OR MORE REACHES FINAL GRADE, OR WILL NOT BE DISTURBED WITHIN ONE YEAR MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

OPERATION & MAINTENANCE

ROCK CONSTRUCTION ENTRANCE

REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.

RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE. PUMPED WATER FILTER BAG

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS

SH,	PROPERTY	TEST METHOD	MINIMUM STANDARD
	AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 lb/in
	GRAB TENSILE	ASTM D-4632	205 lb
ŒD	PUNCTURE	ASTM D-4833	110 lb
	MULLEN BURST	ASTM D-3786	350 psi
	UV RESISTANCE	ASTM D-4355	70%
	AOS % RETAINED	ASTM D-4751	80 SIEVE

• A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME ½ FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW.

PATH SHALL BE PROVIDED, BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEPTING 5% CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS,

WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE. • THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS

• THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR ½ THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED. FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED. PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

OF THE DELIVERY VEHICLES UNLESS SUCH A FACILITY WILL BE USED AT THE SOURCE OF THE CONCRETE. UNDER NO CIRCUMSTANCES MAY WASH WATER FROM THESE VEHICLES BE ALLOWED TO ENTER. ANY SURFACE WATERS. MAKE SURE THAT PROPER SIGNAGE IS PROVIDED TO DRIVERS SO THAT THEY ARE AWARE OF THE PRESENCE OF WASHOUT FACILITIES. WASHOUT FACILITIES SHOULD NOT BE PLACED WITHIN 50 FEET OF STORM DRAINS, OPEN DITCHES OR SURFACE WATERS. THEY SHOULD BE IN A CONVENIENT LOCATION FOR THE TRUCKS, PREFERABLY NEAR THE PLACE WHERE THE CONCRETE IS BEING POURED, BUT FAR ENOUGH FROM OTHER VEHICULAR TRAFFIC TO MINIMIZE THE POTENTIAL FOR ACCIDENTAL DAMAGE OR SPILLS. WHEREVER POSSIBLE THEY SHOULD BE LOCATED ON SLOPES NOT EXCEEDING A 2% GRADE. ADDITIONAL INFORMATION ON WASHOUTS MAY BE OBTAINED FROM EPA'S STORMWATER WERSITE AT:

FOR ANY PROJECT ON WHICH CONCRETE WILL BE POURED OR OTHERWISE FORMED ON SITE, A SUITABLE WASHOUT FACILITY MUST BE PROVIDED FOR THE CLEANING OF CHUTES, MIXERS, AND HOPPERS

HTTP://CEPLIR EPA GOV/NPDES/STORMWATER/MENLIOERMPS/INDEX CEM?ACTION=BROWSE&RBLITTON=DETAIL&BMP=117&MINMEASLIRE=4 COMPOST SOCK WASHOUT - WHEREVER COMPOST SOCK WASHOUTS ARE USED, A SUITABLE IMPERVIOUS GEOMEMBRANE SHOULD BE PLACED AT THE LOCATION OF THE WASHOUT. COMPOST SOCKS SHOULD BE STAKED IN THE MANNER RECOMMENDED BY THE MANUFACTURER AROUND PERIMETER OF THE GEOMEMBRANE SO AS TO FORM A RING WITH THE ENDS OF THE SOCK LOCATED AT THE UPSLOPE CORNER. CARE SHOULD BE TAKEN TO ENSURE CONTINUOUS CONTACT OF THE SOCK WITH THE GEOMEMBRANE AT ALL LOCATIONS. WHERE NECESSARY, SOCKS MAY BE STACKED AND STAKED

A SUITABLE IMPERVIOUS GEOMEMBRANE SHALL BE PLACED AT THE LOCATION OF THE WASHOUT PRIOR TO INSTALLING THE SOCKS. PREFABRICATED WASHOUT CONTAINERS - CARE SHOULD BE TAKEN TO ENSURE THAT THE CONTAINERS ARE INTENDED BY THE MANUFACTURER FOR USE AS CONCRETE WASHOUT BMPS, THAT THEY ARE WATERTIGHT, AND APPROPRIATELY SIZED. ACCUMULATED MATERIALS MUST BE PROPERLY DISPOSED OF (PREFERABLY RECYCLED) WHEN THEY REACH THE CLEANOUT LEVEL. SELF-INSTALLED WASHOUTS - THESE TYPES OF WASHOUTS SHOULD BE EXCAVATED BELOW GRADE TO PREVENT RUNOFF OF THE WASH WATER AND MINIMIZE THE POTENTIAL FOR BREACHING. THEY SHOULD BE SIZED TO HANDLE SOLIDS, WASH WATER, AND RAINFALL. A GOOD RULE OF THUMB IS THAT 7 GALLONS OF WASH WATER ARE REQUIRED TO WASH ONE TRUCK CHUTE AND 50 GALLONS FOR THE HOPPER OF A CONCRETE PUMP TRUCK

BETWEEN CLEANOUT INTERVALS. THE PIT SHOULD BE LINED WITH PLASTIC SHEETING OF AT LEAST 10-MIL THICKNESS (WITH NO HOLES OR TEARS) TO PREVENT LEACHING OF LIQUIDS INTO THE WASHWATER RECYCLING SYSTEMS - WASHWATER RECYCLING SYSTEMS HAVE ALSO BEEN DEVELOPED WHICH SEPARATE THE SOLIDS FROM THE WASHWATER, CAPTURING BOTH IN IMPERMEABLE BAGS AND ALLOWING THEM TO BE RECYCLED. THESE SYSTEMS MAY BE USED IN LIEU OF WASHOUTS IF MANUFACTURERS' SPECIFICATIONS ARE FOLLOWED. CARE MUST BE TAKEN TO PREVENT THE FILTERED WATER FROM ENTERING ANY SURFACE WATERS

FOR LARGER SITES, A BELOW-GRADE WASHOUT SHOULD BE A MINIMUM OF 10 FEET WIDE AND PROVIDE AT LEAST 12 INCHES OF FREEBOARD ABOVE THE LIQUID AND SOLID WASTE ANTICIPATED

HIS DISCHARGE WOULD HAVE AN ADVERSE EFFECT UPON THE RECEIVING WATER. IN ADDITION, CONTINUED USE OF A BASIN OR TRAP AS A WASHOUT FACILITY WOULD SIGNIFICANTLY REDUCE THE STORAGE CAPACITY OF THE BASIN OR TRAP. MAINTENANCE - ALL CONCRETE WASHOUT FACILITIES SHOULD BE INSPECTED DAILY. DAMAGED OR LEAKING WASHOUTS SHOULD BE DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY.

SEDIMENT BASINS AND SEDIMENT TRAPS - SEDIMENT BASINS AND SEDIMENT TRAPS MAY NOT BE USED AS CONCRETE WASHOUT DEVICES, SINCE THEY DISCHARGE DIRECTLY TO SURFACE WATERS.

PLASTIC LINERS SHOULD BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY.

OMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN SOCK ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY SOCK SHALL NOT EXCEED THAT SHOWN ON TABLE 4.2 ON DETAIL 5 ON SHEET C203. STAKES MAY BE INSTALLED IMMEDIATELY DOWNSLOPE OF THE SOCK IF SO SPECIFIED BY

SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 ON DETAIL 5 ON SHEET C203. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 ON DETAIL 5 ON SHEET C203

TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVEGROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN. OCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS O

BIODEGRADABLE FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S

UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE

STABILIZATION METHODS AND STANDARDS:

CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

EROSION CONTROL BLANKETS SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING THE BLANKET.

PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.

HE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

ACCUMULATED MATERIALS SHOULD BE REMOVED WHEN THEY REACH 75% CAPACITY

SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS. BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.

BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

PCSM BMP INSTALLATION SEQUENCE & MAINTENANCE

FLEXSTORM INLET FILTER BMP INSTALLATION SEQUENCE BMPs #1-3

FLEXSTORM INLET FILTER BMP MAINTENANCE BMPs #1-3

3. FINE GRADE THE VEGETATED SWALE.

REMOVE THE GRATE FROM THE CASTING OR CONCRETE DRAINAGE STRUCTURE

FIRMLY ON THE INSIDE LEDGE (LIP) OF THE CASTING. 4. REPLACE THE GRATE AND CONFIRM IT IS ELEVATED NO MORE THAN 1/8", WHICH IS THE THICKNESS OF THE STEEL

FREQUENCY OF INSPECTIONS: CONSTRUCTION SITE INSPECTION SHOULD OCCUR FOLLOWING EACH ½" OR MORE RAIN

2. CLEAN THE LEDGE (LIP) OF THE CASTING FRAME OR DRAINAGE STRUCTURE TO ENSURE IT IS FREE OF STONE AND DIRT

3. DROP IN THE FLEXSTORM INLET FILTER THROUGH THE CLEAR OPENING AND BE SURE THE SUSPENSION HANGERS REST

- EVENT. POST CONSTRUCTION INSPECTIONS SHOULD OCCUR THREE TIMES PER YEAR (EVERY FOUR MONTHS) IN AREAS WITH YEAR-ROUND RAINFALL AND THREE TIMES PER YEAR (EVERY THREE MONTHS) IN AREAS WITH RAINY SEASONS BEFORE AND AFTER SNOWFALL SEASON, INDUSTRIAL APPLICATION SITE INSPECTIONS (LOADING RAMPS, WASH RACKS MAINTENANCE FACILITIES) SHOULD OCCUR ON A REGULARLY SCHEDULED BASIS NO LESS THAN THREE TIMES PER YEAR
- UPON INSPECTION, THE FLEXSTORM INLET FILTER SHOULD BE EMPTIED IF THE SEDIMENT BAG IS MORE THAN HALF FILLED WITH SEDIMENT AND DEBRIS, OR AS DIRECTED BY THE LOCAL CONSERVATION DISTRICT OR MUNICIPAL REMOVE THE GRATE, ENGAGE THE LIFTING BARS OR HANDLES WITH THE FLEXSTORM REMOVAL TOOL, AND LIFT THE

FLEXSTORM INLET FILTER FROM THE DRAINAGE STRUCTURE. MACHINE ASSISTANCE IS NOT REQUIRED.

- DISPOSE OF THE SEDIMENT OR DEBRIS AS DIRECTED BY THE LOCAL CONSERVATION DISTRICT OR MUNICIPAL INSPECTOR. (AS AN ALTERNATIVE, AN INDUSTRIAL VACUUM MAY BE USED TO COLLECT THE ACCUMULATED SEDIMENT IF REMOVE ANY CAKED-ON SILT FROM THE SEDIMENT BAG AND REVERSE FLUSH THE BAG FOR OPTIMAL FILTRATION.
- NOTE: IF PROPERLY MAINTAINED, THE WOVEN SEDIMENT BAG SHOULD LAST A MINIMUM OF 4 YEARS IN THE FIELD. SEDIMENT BAG REPLACEMENT: WHEN REPLACING A SEDIMENT BAG, REMOVE THE BAG BY LOOSENING OR CUTTING OFF THE CLAMPING BAND. TAKE THE NEW SEDIMENT BAG, WHICH IS EQUIPPED WITH A STAINLESS-STEEL WORM DRIVE CLAMPING BAND, AND USE A DRILL OR SCREW DRIVER TO TIGHTEN THE BAG AROUND THE FRAME CHANNEL. ENSURE THE
- VEGETATED SWALE BMP INSTALLATION SEQUENCE BMP #4

BAG IS SECURE AND THAT THERE IS NO SLACK AROUND THE PERIMETER OF THE BAND.

MEASURES ARE IN PLACE AND BEFORE PLACEMENT OF PAVING 2. ROUGH GRADE THE VEGETATED SWALE. EQUIPMENT SHALL AVOID EXCESSIVE COMPACTION AND/OR LAND DISTURBANCE, OPERATING FROM THE SIDE OF THE SWALE AND NEVER ON THE BOTTOM. EXCAVATE THE BOTTOM OF THE SWALE AND INSTALL INLET, GRAVEL & UNDERDRAIN, AND SOIL/PLANTING MIX PER DETAIL.

BEGIN VEGETATED SWALE CONSTRUCTION ONLY WHEN UPGRADIENT EROSION AND SEDIMENTATION CONTROL

4. SEED VEGETATE AND INSTALL PROTECTIVE LINING PER PLANS AND DETAILS. PLANT SWALE AT A TIME OF THE YEAR WHEN SUCCESSFUL ESTABLISHMENT WITHOUT IRRIGATION IS MOST LIKELY. VEGETATION SHOULD BE ESTABLISHED AS SOON AS POSSIBLE TO PREVENT EROSION AND SCOUR. . ONCE ALL TRIBUTARY AREAS REACH FINAL STABILIZATION, REMOVE TEMPORARY EROSION AND SEDIMENTATION

CONTROLS. REGRADE AND RESEED IMMEDIATELY AFTER CONSTRUCTION AND STABILIZATION HAVE OCCURRED. ANY

NOTE: IF A VEGETATED SWALE IS USED FOR RUNOFF CONVEYANCE DURING CONSTRUCTION, IT SHOULD BE REGRADED AND RESEEDED IMMEDIATELY AFTER CONSTRUCTION AND STABILIZATION HAS OCCURRED. ANY DAMAGED AREAS SHOULD BE FULLY RESTORED TO ENSURE FUTURE FUNCTIONALITY OF THE SWALE.

DAMAGED AREAS SHOULD BE FULLY RESTORED TO ENSURE FUTURE FUNCTIONALITY OF THE SWALE.

VEGETATED SWALE BMP MAINTENANCE BMP #4 (TO BE DONE AS NEEDED) PLANT ALTERNATIVE GRASS SPECIES IN THE EVENT OF UNSUCCESSFUL ESTABLISHMENT

ROTOTILL AND REPLANT SWALE IF DRAW DOWN TIME IS MORE THAN 48 HOURS.

- RESEED BARE AREAS; INSTALL APPROPRIATE EROSION CONTROL MEASURES WHEN NATIVE SOIL IS EXPOSED OR EROSION CHANNELS ARE FORMING.
- INSPECT SWALE IMMEDIATELY AFTER THE SPRING MELT, REMOVE RESIDUALS (E.G. SAND, ROOF RUNOFF, ETC.) AND REPLACE DAMAGED VEGETATION WITHOUT DISTURBING REMAINING VEGETATION.

ADS N-12 ST IB PIPE (PER AASHTO) SHALL HAVE A SMOOTH INTERIOR AND ANNULAR EXTERIOR CORRUGATIONS. • 4- THROUGH10-INCH (100 TO 250 MM) SHALL MEET AASHTO M252, TYPE S OR SP. • 12- THROUGH 60-INCH (300 TO 1500 MM) SHALL MEET AASHTO M294, TYPE S OR SP OR ASTM F2306. MANNING'S "N" VALUE FOR USE IN DESIGN SHALL BE 0.012. • REPLACE THE BAG IF THE GEOTEXTILE IS TORN OR PUNCTURED TO ½" DIAMETER OR GREATER ON THE LOWER HALF OF

USE IN GRAVITY-FLOW DRAINAGE APPLICATIONS.

PE SHALL BE JOINED USING A BELL & SPIGOT JOINT MEETING AASHTO M252, AASHTO M294 OR ASTM F2306. THE JOINT SHALL BE SOIL-TIGHT AND GASKETS, WHEN APPLICABLE, SHALL MEET THE REQUIREMENTS OF ASTM F477. GASKETS SHALL BE INSTALLED BY THE PIPE MANUFACTURER AND COVERED WITH A REMOVABLE WRAP TO ENSURE THE GASKET IS FREE FROM DEBRIS. A JOINT LUBRICANT SUPPLIED BY THE MANUFACTURER SHALL BE USED ON THE GASKET AND BELL DURING ASSEMBLY.

THIS SPECIFICATION DESCRIBES 4- THROUGH 60-INCH (100 TO 1500 MM) ADS N-12 ST IB PIPE (PER AASHTO) FOR

FITTINGS SHALL CONFORM TO AASHTO M252, AASHTO M294, OR ASTM F2306. BELL AND SPIGOT CONNECTIONS SHALL UTILIZE A SPUN-ON OR WELDED BELL AND VALLEY OR SADDLE GASKET MEETING THE SOIL-TIGHT JOINT PERFORMANCE REQUIREMENTS OF AASHTO M252, AASHTO M294 OR ASTM F2306.

TRGIN MATERIAL FOR PIPE AND FITTING PRODUCTION SHALL BE HIGH DENSITY POLYETHYLENE CONFORMING WITH THE MINIMUM REQUIREMENTS OF CELL CLASSIFICATION 424420C FOR 4- THROUGH 10-INCH (100 TO 250 MM) DIAMETERS, OR 435400C FOR 12- THROUGH 60-INCH (300 TO 1500 MM) DIAMETERS, AS DEFINED AND DESCRIBED IN THE LATEST VERSION OF ASTM D3350, EXCEPT THAT CARBON BLACK CONTENT SHOULD NOT EXCEED 4%. THE 12-THROUGH 60-INCH (300 TO 1500 MM) VIRGIN PIPE MATERIAL SHALL COMPLY WITH THE NOTCHED CONSTANT LIGAMENT-STRESS (NCLS) TEST AS SPECIFIED IN SECTIONS 9.5 AND 5.1 OF AASHTO M294 AND ASTM F2306,

INSTALLATION SHALL BE IN ACCORDANCE WITH ASTM D2321 AND ADS RECOMMENDED INSTALLATION GUIDELINES, WITH THE EXCEPTION THAT MINIMUM COVER IN TRAFFICKED AREAS FOR 4- THROUGH 48-INCH (100 TO 1200 MM) DIAMETERS SHALL BE ONE FOOT. (0.3 M) AND FOR 54- AND 60-INCH (1350 AND 1500 MM) DIAMETERS. THE MINIMUM COVER SHALL BE 2 FT. (0.6 M) IN SINGLE RUN APPLICATIONS. BACKFILL FOR MINIMUM COVER SITUATIONS SHALL CONSIST OF CLASS 1. CLASS 2 (MINIMUM 90% SPD) OR CLASS 3 (MINIMUM 90%) MATERIAL. MAXIMUM FILL HEIGHTS DEPEND ON EMBEDMENT MATERIAL AND COMPACTION LEVEL; PLEASE REFER TO TECHNICAL NOTE 2.01. CONTACT YOUR LOCAL ADS REPRESENTATIVE OR VISIT OUR WEBSITE AT WWW.ADS-PIPE.COM FOR A COPY OF THE LATEST

1 ADS N-12® ST IB PIPE (PER AASHTO) SPECIFICATION


SCALE: AS NOTED REVISIONS

ARCHITECT: LE DRAFTSMAN: CWT

7n2-R

CHECKED BY: CAD





Development, et, 3rd Floor et, 38103 eax: (901) 495-8969

SCALE: AS NOTED

ARCHITECT: LE DRAFTSMAN: CWT CHECKED BY: CAD


6-25-2021



SITE LOCATION MAP SCALE: 1"=2,000'

GENERAL UTILITY NOTES

- 1. CONTRACTOR SHALL CONTACT RESPECTIVE UTILITY COMPANIES PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES, TO COORDINATE REQUIREMENTS TO ENSURE TIMELY SERVICE INSTALLATION.
- 2. PROPER COORDINATION WITH THE RESPECTIVE UTILITY COMPANIES SHALL BE PERFORMED BY THE CONTRACTOR TO INSURE THAT ALL UTILITY COMPANY, LOCAL MUNICIPALITY, AND LOCAL COUNTY STANDARDS FOR MATERIALS AND CONSTRUCTION METHODS ARE MET.
- 3. THE CONTRACTOR SHALL VISIT THE SITE AND VERIFY THE ELEVATION AND LOCATION OF ALL UTILITIES BY VARIOUS MEANS PRIOR TO BEGINNING ANY EXCAVATION. TEST PITS SHALL BE DUG AT ALL LOCATIONS WHERE SEWERS CROSS EXISTING UTILITIES, AND THE HORIZONTAL AND VERTICAL LOCATIONS OF THE UTILITIES SHALL BE DETERMINED. THE CONTRACTOR SHALL CONTACT THE OWNER IN THE EVENT OF ANY UNFORESEEN CONFLICTS BETWEEN EXISTING AND PROPOSED UTILITIES SO THAT AN APPROPRIATE MODIFICATION MAY BE MADE.
- 4. THE CONTRACTOR SHALL ARRANGE FOR AND COORDINATE WITH THE RESPECTIVE UTILITY COMPANIES FOR SERVICE INSTALLATIONS AND CONNECTIONS AND MAIN AND SERVICE RELOCATIONS. THE CONTRACTOR SHALL COORDINATE THE WORK TO BE PERFORMED BY THE VARIOUS UTILITY COMPANIES AND SHALL SECURE ALL PERMITS AND PAY ALL FEES FOR CONNECTIONS, DISCONNECTIONS, RELOCATIONS, INSPECTIONS, AND DEMOLITION, AS NECESSARY
- 5. THE CONTRACTOR SHALL MAINTAIN ALL FLOWS AND UTILITY CONNECTIONS TO EXISTING BUILDINGS, ETC. WITHOUT INTERRUPTION UNLESS/UNTIL AUTHORIZED TO DISCONNECT BY THE OWNER, UTILITY COMPANIES, AND GOVERNING AUTHORITIES. THE CONTRACTOR SHALL INSTALL AS NECESSARY, TEMPORARY SITE LIGHTING, GAS, SANITARY, WATER, STORM, ELECTRIC, TELEPHONE, AND CABLE SERVICES TO SERVICE BUILDING(S) TO REMAIN OPEN.
- 6. ALL EXISTING PAVEMENT WHERE UTILITY PIPING IS TO BE INSTALLED SHALL BE SAW CUT AND REPLACED IN ACCORDANCE WITH THE PAVEMENT REPAIR REQUIREMENTS OF LOCAL MUNICIPALITY AND THE DETAILS CONTAINED HEREIN.
- ALL WATER MAINS, WATER SERVICES AND SANITARY SEWER LATERALS SHALL CONFORM TO THE DEPARTMENT OF ENVIRONMENTAL PROTECTION, APPLICABLE COUNTY AND LOCAL DEPARTMENTS, AND APPROPRIATE UTILITY COMPANY
- 8. ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER ACCURATE METHOD.
- 9. TEST PITS SHALL BE SHOWN AT ALL UTILITY CROSSINGS AND AT THE POINTS OF CONNECTION TO EXISTING WATER MAINS. AT LEAST 10 DAYS PRIOR TO CONSTRUCTION ACTIVITY THE CONTRACTOR MUST OBTAIN THE TEST PIT DATA AND COORDINATE WITH THE INSPECTOR. IF THE TEST RESULTS SHOW A POTENTIAL CONFLICT OR NON-COMPLIANCE WITH THE APPROVED PLAN, REVISIONS TO THE PLANS MUST BE SUBMITTED FOR APPROVAL. IN SUCH INSTANCES, NO WORK SHALL COMMENCE UNTIL CONFLICTS ARE RESOLVED AND REVISIONS APPROVED.
- 10. RELOCATION OF ANY UTILITY COMPANY FACILITIES TO BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE UTILITY COMPANY AND LOCAL MUNICIPALITY.
- 11. THE CONTRACTOR SHALL COMPACT PIPE BACKFILL IN MAX. 8" LOOSE LIFTS TO 95% OF THE MAXIMUM DRY DENSITY PER ASTM D1557, ACCORDING TO THE PIPE BEDDING DETAILS. TRENCH BOTTOM SHALL BE STABLE IN HIGH GROUNDWATER AREAS. A PIPE FOUNDATION SHALL BE USED IN AREAS OF ROCK EXCAVATION.
- 12. CONTRACTOR TO PROVIDE SLEEVES UNDER FOOTINGS OR THROUGH FOUNDATIONS FOR UTILITY CONNECTIONS.
- 13. CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC. AS REQUIRED FOR PIPE CONNECTIONS TO BUILDING/CANOPY STUB-OUTS, INCLUDING ROOF/FOOTING DRAIN CONNECTIONS TO ROOF LEADERS AND TO STORM DRAINAGE
- 14. UTILITY CONDUIT PIPE SHALL BE SCHEDULE 80 PVC AND/OR AS REQUIRED BY THE LOCAL UTILITY COMPANY. SERVICES MAY BE INSTALLED IN A COMMON TRENCH WITH 12" CLEAR SPACE BETWEEN SERVICES. MINIMUM COVER SHALL BE 36" ON ELECTRIC CONDUITS AND 24" ON TELEPHONE AND CABLE CONDUITS. SERVICES SHALL BE MARKED WITH MAGNETIC LOCATOR TAPE. GALVANIZED STEEL ELECTRICAL CONDUIT SHALL BE USED AT POLE AND TRANSFORMER LOCATIONS. INSTALL HAND HOLES AS
- 15. ALL UTILITY CONSTRUCTION IS SUBJECT TO INSPECTION PRIOR TO APPROVAL FOR BACKFILL, IN ACCORDANCE WITH THE APPROPRIATE UTILITY COMPANY, LOCAL MUNICIPALITY, AND/OR LOCAL COUNTY REQUIREMENTS.
- 16. MANHOLE RIMS AND STORM INLETS SHALL BE SET TO ELEVATIONS SHOWN. ADJUST ALL EXISTING MANHOLE FRAMES AND COVERS, STORM INLET GRATES, VALVE BOXES, ETC., TO BE RAISED OR LOWERED, TO PROPOSED FINISHED GRADE, FLUSH WITH THE ADJACENT GRADE.
- 17. THE CONTRACTOR SHALL RESTORE ANY STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS, ETC. DISTURBED DURING CONSTRUCTION TO THE ORIGINAL CONDITION OR BETTER.
- 18. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, ALL SANITARY SEWER PIPING SHALL BE POLYVINYL CHLORIDE (PVC) PIPE AND FITTINGS ASTM D3034, TYPE PSM WITH A MAXIMUM SDR OF 35, WITH FLEXIBLE ELASTOMERIC SEAL JOINTS, ASTM D3212.
- 19. ALL SANITARY SEWER PIPING SHALL HAVE A MINIMUM OF 6" OF COARSE AGGREGATE
- 20. THE CONTRACTOR SHALL CONTACT THE LOCAL COUNTY HEALTH DEPARTMENT AND FILE AND OBTAIN A PLUMBING PERMIT FOR THE WORK INDICATED HEREON AND COMPLIANCE WITH THE LOCAL COUNTY PLUMBING CODE.
- 21. OBTAIN REQUIRED SANITARY SEWER CONNECTION PERMIT AND PAY ALL CONNECTION AND TAPPING FEES BEFORE CONNECTING ANY NEW SEWER LINE TO THE AUTHORITY'S SEWER LINES (FEES TO BE PAID BY OWNER).
- 22. WATER LINE AFTER WATER METER SHALL BE ENCASED IN 4" SCH. 40 PVC CONDUIT UNDER ALL CONCRETE OR ASPHALT SURFACES AND TO 1" ABOVE FINISHED FLOOR.
- 23. THE CONTRACTOR SHALL BE ADVISED THAT ALL EXCAVATION IS CONSIDERED UNCLASSIFIED AND THAT IT SHALL BE RESPONSIBLE FOR ALL MEANS, METHODS, AND MATERIALS OF CONSTRUCTION TO COMPLETE CONSTRUCTION AS DESIGNED. ADDITIONALLY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OFF-SITE DISPOSAL OF ANY AND ALL EXCESS OR UNSUITABLE MATERIAL UNABLE TO BE PLACED ON SITE AND THE IMPORTATION OF ANY BORROW MATERIAL NECESSARY TO COMPLETE
- 24. COORDINATE INSTALLATION OF LOT LIGHTS, TREES, SIGNS, ETC., WITH PROPOSED UNDERGROUND UTILITIES. CONTACT OWNER OF ANY DISCREPANCIES PRIOR TO CONSTRUCTION.



REVISIONS 1 11-30-21 PER BOROUGH & COUNTY COMMEN

SCALE: 1" = 20'-0"


ARCHITECT: LE


DRAFTSMAN: CWT CHECKED BY: CAD


7n2-R





SHEET 15 of 16























Development,
3t, 3rd Floor
⇒ 38103
-ax: (901) 4°
stor 1-°

DF ST. CLAIR
PENNSYLVANIA

Store No.: 2800 489 POTTSVILLE ST. CLAIR HIGHWAY TOWNSHIP OF EAST NORWEGIAN & BOROUGH OF S COUNTY OF SCHUYLKILL, COMMONWEALTH OF PEN

SCALE: AS NOTED

REVISIONS

1. 11-30-21 PER BOROUGH & COUNTY COMMENT

2.

3.

6.
7.
ARCHITECT: LE

DRAFTSMAN: CWT
CHECKED BY: CAD

DATE
6-25-2021

6-25-2021
PROTOTYPE SIZE
7n2-R



U1.1SHEET 16 of 16